

Final Pre-CMS Data Collection Work Plan

FORMER RHONE POULENC SITE

TUKWILA, WASHINGTON

April 26, 2021

Prepared for:

Container Properties, LLC

Tukwila, Washington

Prepared by:

DALTON, OLMSTED, & FUGLEVAND, INC.

1001 SW Klickitat Way, Suite 200B

Seattle, Washington 98134

Certification

On behalf of the respondents, I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to evaluate the information submitted. I certify that the information contained in or accompanying this Final Pre-CMS Data Collection Work Plan is true, accurate, and complete. As to those portions of the report for which I cannot personally verify accuracy, I certify under penalty of law that this report and all attachments were prepared in accordance with procedures designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who may manage the system, or those directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

By: Natasya AD Gray
Ms. Natasya Gray, DOF, Project Coordinator

Date: 4/26/21

Table of Contents

| | | |
|--------|---|----|
| 1. | Introduction | 1 |
| 1.1. | Statement of the Problem | 1 |
| 1.1.1. | Long Term Hydraulic Control Operations | 1 |
| 1.1.2. | Post-Carbon Dioxide Pilot Study Design | 2 |
| 1.1.3. | Current Conditions Contaminant Concentrations | 2 |
| 2. | Data Collection Objectives | 3 |
| 2.1. | Hydraulic Control Performance Evaluation | 3 |
| 2.2. | CO ₂ Treatment Pre-Design Information | 4 |
| 2.3. | Contaminant Conceptual Site Model Update | 4 |
| 2.3.1. | Consideration for Revised PRGs | 5 |
| 2.3.2. | Consideration for Post-Interim Measures Conditions | 1 |
| 2.3.3. | Consideration for Recent Contaminant Characterization | 9 |
| 3. | Approach | 11 |
| 3.1. | Preliminary Remediation Goals (PRGs) Update | 11 |
| 3.2. | Temporary Groundwater Pumping Cessation | 11 |
| 3.2.1. | Baseline Monitoring | 12 |
| 3.2.2. | Water Level Monitoring | 12 |
| 3.2.3. | Water Quality Monitoring | 12 |
| 3.2.4. | Treatment System Operations During Evaluation | 13 |
| 3.3. | Groundwater Sample Collection | 13 |
| 4. | Data Collection Methods | 14 |
| 4.1. | Well Inspection and Rehabilitation | 14 |
| 4.2. | Groundwater Elevation Monitoring | 14 |
| 4.3. | Groundwater Sample Collection | 14 |
| 4.4. | Groundwater Pumping System Monitoring | 15 |
| 5. | Reporting | 17 |
| 6. | Schedule | 19 |
| 7. | References | 20 |

TABLES

| | |
|---------|---|
| Table 1 | Groundwater Sample Collection and Rationale |
|---------|---|

FIGURES

| | |
|----------|--------------------------------|
| Figure 1 | Vicinity Map |
| Figure 2 | Site Layout |
| Figure 3 | Historic Structures |
| Figure 4 | Interim Measures Locations |
| Figure 5 | Adaptive Management Flow Chart |
| Figure 6 | Water Level Monitoring Plan |
| Figure 7 | Sampling Plan |

ATTACHMENTS

| | |
|--------------|--|
| Attachment 1 | Relevant 2014 Draft CMS Work Plan Maps & Technical Meeting Figures |
| Attachment 2 | List of Hazardous Constituents and Maximum Concentrations |
| Attachment 3 | Tabulated Preliminary Screening Tables and PRGs |
| Attachment 4 | Groundwater Sampling Field Log |

ACRONYMS AND ABBREVIATIONS

| | |
|-----------------------|--|
| C | Celsius |
| CMS | Corrective Measures Study |
| CO ₂ | carbon dioxide |
| COC | constituent of concern |
| DI | deionized |
| DO | dissolved oxygen |
| DOC | dissolved organic carbon |
| DOF | Dalton, Olmsted & Fuglevand, Inc. |
| EPA | Environmental Protection Agency |
| GAC | granular activated carbon |
| GWPT | groundwater pump & treat |
| HCIM | hydraulic control interim measure |
| mg/L | milligrams per liter |
| mV | millivolts |
| NTU | nephelometric turbidity units |
| Order | Administrative Order on Consent No. 1091-11-20-3008(h) |
| PCBs | Polychlorinated Biphenyls |
| PMP | Performance Monitoring Plan |
| PRG | Preliminary Remediation Goal |
| RCRA | Resource Conservation and Recovery Act |
| S/cm | siemens per centimeter |
| SVE | soil vapor extraction |
| SVOCs | semi-volatile organic compounds |
| TPH | total petroleum hydrocarbons |
| TDS | total dissolved solids |
| TSS | total suspended solids |
| VOCs | volatile organic compounds |

1. INTRODUCTION

The former Rhone-Poulenc facility (site) is located adjacent to the Duwamish Waterway in Tukwila, Washington. This Pre-Corrective Measure Study Data Gaps Work Plan (work plan) was prepared in response to The Environmental Protection Agency's (EPA) March 2021 letter regarding the "Determination of Need for Additional Work" to identify data gaps and document plans for performing data collection to support preparation of the Corrective Measures Study (CMS). The CMS is being performed to address the requirements of the Resource Conservation and Recovery Act (RCRA) Administrative Order on Consent (Order) No. 1091-11-20-3008(h).

The site is located on about 750 feet of shoreline on the east side of the Lower Duwamish Waterway (LDW) just north of Slip 6, at approximately river mile 4.2. The West Parcel is bounded by the Museum of Flight and Raisbeck Aviation High School to the east, the 8801 E Marginal Way South Site to the north, the LDW to the west, and Slip 6 to the south (Figure 1). Investigation and cleanup of the Facility is being conducted under the above-referenced Order by former owners, including Solvay, Inc. (formerly Rhodia Inc.) and Bayer CropScience Inc. (corporate successors to the former Rhone-Poulenc company), and the current owner, Container Properties, L.L.C.

This work plan documents the objectives, data gaps, and data collection that will assist in preparation of the CMS.

1.1. Statement of the Problem

In 2006, the property underwent redevelopment and was split into two parcels. The East Parcel was investigated and cleaned up in cooperation with EPA. The EPA determined in 2017 that the East Parcel cleanup was fully complete with no controls required. This parcel was purchased and redeveloped by the Museum of Flight in 2006. The cleanup of West Parcel is ongoing in cooperation with EPA under the Order.

Significant progress has been made at the West Parcel in investigating groundwater, soil, and sediment contamination and controlling risks posed by contamination. An Agency Draft CMS Work Plan was prepared in 2014 and the CO₂ Pilot Study was conducted after that. The draft CMS Work Plan presented contaminant conceptual model information to support evaluation of cleanup alternatives, but seven years have passed, additional treatment and natural degradation has occurred, and relevant site preliminary remediation goals have been revised. All of these factors warrant collection of additional data to:

1. Support engineering design information that will be used to assess corrective measures alternatives in the CMS.
2. Update the understanding of current contaminant conditions.

1.1.1. LONG TERM HYDRAULIC CONTROL OPERATIONS

The hydraulic control interim measure (HCIM) groundwater pretreatment system has been in operation since 2003 following installation of a low-permeability subsurface barrier wall, a groundwater recovery system, and a performance monitoring well network inside and outside the barrier wall. The HCIM

resulted in control of a majority of the contaminated groundwater plume at the West Parcel and continues to work effectively as an interim measure. Construction of the barrier wall and groundwater recovery system is documented in the Hydraulic Control Interim Measures Implementation Report (RCI, 2003). The facility underwent redevelopment in 2006 including regrading and repaving, effectively capping the area encompassed by the barrier wall. Since 2008, the system has treated and discharged between 1 and 2 million gallons annually, dependent on precipitation driving the Duwamish Waterway river stage. The system has maintained a 72-hour averaged inward hydraulic gradient of greater than 1-foot since start of operations.

The Agency Draft CMS Work Plan (AMEC, 2014) included a preliminary screening of remedial technologies to be included in the CMS for the site. This evaluation included consideration of potentially shutting down the groundwater pumping component of the HCIM as part of the final remedy for the site. Conducting a temporary passive operation of the interim measure, under intensive monitoring, will allow water levels to rise and hydraulic gradients to equalize, while still being protective of potential down gradient receptors. This passive operation will provide data to allow for better evaluation of contaminant concentrations and migration.

1.1.2. POST-CARBON DIOXIDE PILOT STUDY DESIGN

A pilot study of the technology using carbon dioxide (CO₂) injection for neutralizing groundwater affected by high pH was conducted between 2018 and 2019. This technology has had a limited history of use; site-specific testing was conducted to assess its applicability and to collect detailed information needed to evaluate CO₂ injection as a component of the CMS alternatives. Results of the study were promising; however, full scale design questions have been identified that would be helpful to address prior to completing the CMS.

1.1.3. CURRENT CONDITIONS CONTAMINANT CONCENTRATIONS

The Agency Draft CMS Work Plan (AMEC, 2014) included presentation of site contaminants and historical operations, as a supplement to the much older 1995 RCRA Facility Investigation; however, EPA has requested that the CMS more clearly identify and consider:

- Historical contaminant source areas;
- Interim actions completed to address contamination; and
- Current site contaminant conditions still warranting remedial action.

In addition, the relevant Preliminary Remediation Goals (PRGs) require review and update based on current regulations, site conditions, and potential future site uses.

Select figures from the Agency Draft CMS work Plan (AMEC, 2014) and data figures discussed in a March 2021 technical meeting with EPA are provided in Attachment 1.

2. DATA COLLECTION OBJECTIVES

The objective of the data collection tasks described in this section is to address the data gaps identified in Section 1, specifically:

- Collecting information to be used for future evaluation of long term remedial options that may eliminate reliance on the HCIM.
- Collecting information to be used for future evaluation of full scale design detail for groundwater pH neutralization.
- Updating the conceptual site model for current conditions to be addressed by the final corrective measure.

These objectives are discussed further in the following subsections.

2.1. Hydraulic Control Performance Evaluation

The HCIM included the installation of a subsurface low-permeability barrier wall that surrounds, to the extent practicable, the environmentally impacted upland portion of the site. The area surrounded by the barrier wall is shown on Figure 2. The barrier wall is complemented by a system of groundwater extraction wells that pumps groundwater from inside the contained area to establish and maintain an inward-directed groundwater gradient. The recovered groundwater is pretreated in a permitted, on-site treatment system and is discharged to a King County treatment works. The surface of the site is almost entirely paved with asphalt. The pavement surface, in conjunction with a stormwater drainage system, minimizes infiltration of surface water to the subsurface area enclosed by the barrier wall (AMEC, 2014).

The objective of the hydraulic control performance evaluation proposed in this work plan is to determine how the HCIM hydrogeologic system and contaminant concentrations and transport behave during a period of temporary groundwater pumping cessation. The wall is one of the subsurface features that influences and will continue to influence the site conceptual model and must be considered as part of the basis for remedial design. The shutdown period will allow for collection of the following information:

1. COC concentration information inside and outside of the HCIM wall.
2. Information related to how COCs could potentially migrate vertically and horizontally across the site without an inward hydraulic gradient.
3. Information related to the effects of water level rebound on the potential for COCs mobilizing from the vadose zone to groundwater.
4. Additional information to aid in design for corrective measures that do not rely on the HCIM as a long-term solution.

Proposed data collection includes assessing cross-wall containment transport and groundwater flow response under passive hydraulic containment conditions by allowing groundwater elevations inside the barrier wall to fluctuate with the exterior, tidally influenced, groundwater elevations.

2.2. CO₂ Treatment Pre-Design Information

The CO₂ Neutralization Pilot Study Results report (Wood, 2020) confirmed the technical feasibility of injecting carbon dioxide for neutralizing high pH groundwater, but concluded that further evaluation was necessary to design for scaled-up neutralization of the high pH target area. In particular, the report suggested that relative remedial costs for different application scenarios need to be evaluated in parallel with other site remediation action objectives to determine the most effective remediation plan. Pilot study injections were completed in 2018 with the last round of pilot study monitoring completed in February 2019.

The objective of additional monitoring is to confirm the report's conclusions on pH rebound and soil buffering capacity, as well as pH and contaminant migration. Confirming rebound and migration trends will aid in choosing and designing an effective corrective measure. Proposed data collection includes collecting groundwater data for geochemical parameters and targeted contaminants in the area treated by the pilot study.

2.3. Contaminant Conceptual Site Model Update

The historical sources of soil and groundwater contamination at the site were summarized in the 2014 Agency Draft CMS Work Plan (AMEC, 2014), and documented in numerous historical reports which describe the historical industrial operations that occurred at the site. Historical reports describe that the historical manufacture of artificial vanilla flavoring, or vanillin, through chemical processing of wood cellulose contributed to sources of contamination at the site. The manufacture of vanillin involved the use of toluene, copper sulfate, and caustic soda. Figure 3 shows historic operational areas, as documented in the 2014 Agency Draft CMS Work Plan (AMEC, 2014).

Since the implementation of the HCIM and other interim measures, groundwater conditions have changed. In order to proceed into the CMS it is important that the current site conditions be understood, in addition to documenting past sources and nature of contamination. This includes consideration of:

- Updates to Preliminary Remediation Goals (PRGs),
- Interim remedial measures conducted at the site, and
- Recently collected data at and near the site.

The objective of the data collection proposed for this data gap is to address uncertainty associated with the current conditions, as presented in the 2014 Agency Draft CMS Work Plan, and to adequately determine the nature and extent of contamination. Current soil, groundwater, and sediment contaminants and contaminant concentrations are needed to evaluate appropriate corrective measures technologies and address risk posed by contaminants in soil, groundwater, and sediments. Proposed tasks include:

- Assessing conditions of and rehabilitating monitoring wells, as necessary, for obtaining representative samples.

- Assess current conditions of the site groundwater by collecting and analyzing groundwater samples from select existing monitoring wells for volatile organic compounds (VOCs), semivolatile organic compounds (SVOCs), polycyclic biphenyls (PCBs), dioxins/furans, or metals in areas of the site for which data gaps exist spatially, vertically, and temporally.
- Developing a revised list of soil, groundwater, and sediment contaminants of concern (COCs) based on newly collected groundwater data, existing data, and updated PRGs.

2.3.1. CONSIDERATION FOR REVISED PRGS

EPA developed the original PRGs for the site in March 2014. Since then, revisions have been required because of changes to assumptions and criteria used to inform the PRGs. Accordingly, EPA prepared spreadsheets with current criteria for soil and groundwater constituents and provided these to DOF in September 2020. In order to revise PRGs EPA developed a comprehensive list of potential COCs based on investigations that documented the presence of hazardous constituents in the soils, groundwater, sediments, and pore water at the site. In addition to quarterly groundwater monitoring, investigations of the West Parcel include the following:

- 1986 – Site Screening Investigation, Dames and Moore
- 1990 – RCRA Facility Assessment, PRC Environmental for EPA
- 1991 – Site Assessment, Landau Associates
- 1995 – Final RCRA Facility Investigation Report, CH2M Hill
- 1996 – Round 3 Data and Sewer Sediment Technical Memorandum, RCRA Facility Investigation
- 1998 – Interim Measures Report, PCB Remediation & Sewer Cleaning, Rhodia, Inc.
- 2000 – Round 6 Groundwater Monitoring, AGI
- 2001 – Geoprobe Investigation Report, AGI
- 2006 – Revised Pre-Demolition Investigation Report, Geomatrix Consultants
- 2006 – Voluntary Interim Measure Report, Hazardous Waste Storage Area and Transformer A Area Cleanup, Geomatrix Consultants
- 2007 – West Parcel Redevelopment Report, Geomatrix Consultants
- 2007 – Northwest Corner Affected Soil Removal Report, Geomatrix Consultants
- 2012 – Sediment Characterization Data Report, AMEC Environment & Infrastructure, Inc.
- 2012 – Shoreline Soil and Groundwater Characterization Data Report, AMEC Environment & Infrastructure, Inc.

The primary hazardous constituents known to be present at the site include toluene, copper, and elevated pH due to release of caustic materials. Additional potential COCs include PCBs, polycyclic aromatic hydrocarbons, semivolatile organic compounds, and several metals. A complete list of hazardous constituents and their maximum concentrations detected in soil, groundwater, and

sediments that was generated by EPA as part of reviewing PRGs at the Facility is provided in Attachment 2, along with background information provided by EPA regarding PRGs.

EPA shared spreadsheets containing draft revised PRGs with DOF to facilitate updating the site conceptual model of contamination for the CMS and identify data gaps. These PRGs will be used to refine the COCs to be evaluated in the upcoming CMS. Actual cleanup levels and points of compliance will be determined during the CMS process. It is possible that COCs may be added or removed for specific areas or throughout the site, as will be further determined in the CMS.

DOF performed the following steps to identify data gaps the new PRGs might present leading into the CMS.

- Compared highest historical concentrations of potential COCs to revised PRGs to determine which analytes have ever been detected above a potential PRG in various media.
- Reviewed how recently collected data (last five years) compared to draft PRGs.
- Reviewed recent data to determine if data are available for different areas of the site (i.e. inside and outside barrier wall).
- Reviewed other analytes of interest discussed with EPA.

Results of these steps are described below and tabulated summaries are included in Attachment 3.

Screening of Historical Highs

Step 1: DOF screened the highest historical detection in groundwater against the draft 2020 PRGs provided by EPA. Data used in screening were identified from EPA's historical review completed as part of drafting updated PRGs and was cross-checked with the project database. The following constituents were detected at least once at a level that exceeded the draft PRGs:

Metals:

| | | |
|------------------|-----------|----------|
| Aluminum | Iron | Nickel |
| Arsenic | Lead | Selenium |
| Cadmium | Manganese | Vanadium |
| Chromium (total) | Mercury | Zinc |
| Copper | | |

Volatile Organic Compounds (VOCs):

| | |
|--------------|-------------|
| Benzene | Toluene |
| Ethylbenzene | Naphthalene |

Semi-volatile Organic Compounds (SVOCs):

| | | |
|-------------------|----------------|--------|
| Pentachlorophenol | 2-Methylphenol | Phenol |
|-------------------|----------------|--------|

Step 2: DOF screened the highest historical detection in soil against draft 2020 PRGs. Data used in screening were identified from EPA's historical review completed as part of drafting updated PRGs and was cross-checked with the project database. The following constituents were detected at least once at a level that exceeded the draft PRGs:

Metals:

Antimony
Arsenic
Barium
Cadmium
Chromium
Cobalt

Copper
Iron
Lead
Manganese
Mercury
Nickel

Selenium
Silver
Vanadium
Zinc

VOCs:

Acetone
Benzene
Bromoform
1,4 Dichlorobenzene
Ethylbenzene

Formaldehyde
Methylene Chloride
Toluene
Trichloroethene
Xylenes

Naphthalene

SVOCs:

Pentachlorophenol
Benzo(a)anthracene
Benzo(a)pyrene
Benzo(b)fluoranthene
Benzyl alcohol

Bis(2-ethylhexyl)phthalate
2,4-Dimethylphenol
Fluoranthene
2-Methylphenol

4-Methylphenol
Phenol
2-Propanol

Pesticides:

Alpha chlordane
4,4'-DDD

4,4'-DDE
4,4'-DDT

Dieldrin
Chlordane

PCBs:

Aroclor 1254

Step 3: Constituents detected in soil that only exceeded the soil PRG protective of groundwater, that were not identified as a potential groundwater constituent of concern in Step 1 were eliminated. This reduced the soil list of constituents to:

Metals:

Arsenic
Cadmium
Chromium
Copper

Iron
Lead
Manganese
Mercury

Nickel
Selenium
Vanadium
Zinc

VOCs:

Benzene
Ethylbenzene

Toluene
Naphthalene

SVOCs:

Pentachlorophenol
Benzo(a)pyrene
Benzyl alcohol

Bis(2-ethylhexyl)phthalate
2,4-Dimethylphenol
Fluoranthene

2-Methylphenol
4-Methylphenol
Phenol

Pesticides:

4,4-DDT

Dieldrin

PCBs:

Aroclor 1254

Additionally, several constituents were eliminated in Step 3, but associated groundwater data for these constituents was not located. This will be reviewed as part of the data gaps assessment through further historical record review and consideration of data gaps groundwater sampling.

Sediment screening is pending receipt of 2020 Lower Duwamish River sampling and will be assessed once those data are received later in 2021. EPA has shared preliminary results and expects a results report to be released this spring.

Recent Groundwater Data

Groundwater is currently monitored at a variety of wells for metals and VOCs (aluminum, arsenic, cadmium, chromium, copper, lead, mercury, nickel, selenium, vanadium, zinc, benzene, ethylbenzene, and toluene) as part of HCIM performance monitoring. SVOCs (including naphthalene) were monitored in 2015 across the site, but not since. Results were generally non-detect but reporting limits were higher than are attainable now.

See Attachment 3 for tabulated screening summary tables. This assessment will be reviewed and revised after completion of 2021 groundwater sampling events conducted as part of this data gaps assessment and groundwater sampling Rounds 91 and 93.

2.3.2. CONSIDERATION FOR POST-INTERIM MEASURES CONDITIONS

Several interim measures have been conducted at the facility since the original contaminant characterization work was completed in the 1990s. These actions need to be considered in planning for a final corrective measure at the site as they have altered and generally improved site conditions with regards to remaining contamination. Figure 4 shows the approximate locations of interim measures described in this section.

2.3.2.1. 1995 Interim Measures

Polychlorinated biphenyls (PCBs) were removed from soils, process drains, and storm sewers at the Facility in 1995. Activities were summarized in a 1998 Interim Measures Report (Rhodia, 1998). The PCBs were detected during RFI sampling in the area of a concrete autoclave compressor pad and a sewer line. Once the concrete compressor pad was removed, the underlying soil in an area approximately 16 feet by 21 feet to a depth of 10 feet was excavated for disposal. Confirmation soil samples results showed PCB concentrations all below 2.5 mg/kg.

PCBs were also detected in a decommissioned buried 8-inch drainpipe discovered during installation of underground power lines. A trench was excavated with soil removed from an area 31 feet long by five feet wide trench and 3.75 feet deep and several areas were widened based on soil sampling performed during the excavation. Confirmation soil samples showed one sample with a result slightly higher than the other area of cleanup (31.12 mg/kg Aroclor 1254). Sewer lines were also cleaned at this time since the plant had ceased operations and Metro had notified Rhone Poulenc Inc. that stormwater could no

longer go to the sanitary sewer and needed to reroute to the Duwamish Waterway. The lines were cleaned prior to this modification. Groundwater was not recently tested in this area of the site. The location of both of these excavation areas are shown on Figure 4.

2.3.2.2. 1999-2002 Soil Vapor Extraction

A soil vapor extraction (SVE) interim measure to remove toluene from the subsurface in the area near the former toluene storage tank was completed in 2002. This area is located south of Building 3 and shown on Figure 4. This SVE system operated from October 1999 through November 2002. Approximately 61,300 pounds of toluene and other volatile chemicals were documented as removed from the subsurface by this system (AMEC, 2014).

2.3.2.3. 2003 Hydraulic Control

Hydraulic control included a barrier wall, extractions wells, hydraulic control monitoring wells, conveyance piping, and pre-treatment system (Originally installed in the Main Distribution Center Building [Building 3, Figure 3]). The barrier wall was designed and constructed in 2002-2003 to encircle the areas of historical releases of primary COCs to the extent possible. It is located approximately 50 feet inland from the shoreline due to stability constraints and to allow for potential future shoreline habitat restoration, as shown on Figure 2.

2.3.2.4. 2006 Actions Triggered by Property Development

Several interim actions were conducted in 2006 to remove areas of contamination identified during demolition of aboveground structures at the facility. These were documented in the 2014 Agency Draft CMS Work Plan and various reports provided to EPA during the redevelopment of the facility. Work included:

- Demolition and removal of remaining historic structures, including remaining buildings and sumps.
- Demolition of the cement pad at the former hazardous waste storage area revealed oil-stained soils containing TPH in the oil and diesel ranges. These soils were excavated for off-site disposal.
- Contaminated soil was excavated along the northwestern corner of the property to remove soils affected by petroleum, copper, and other contaminants released by apparent historic dumping of materials along the northern property line (Geomatrix, 2007).
- Toluene impacts to soil and groundwater were identified on the border between the Museum of Flight and Container Properties parcels, resulting from a toluene release from an underground pipe. The pipe was cut, drained, and a portion was removed during the excavation work. To mitigate toluene-impacted groundwater in this area SVE and air sparging were conducted. Low levels of toluene remained in a small portion of the Museum of Flight property adjacent to the West Parcel following SVE Operations. The groundwater cleanup continued in a limited area in the southwest corner of the East Parcel and southeast corner of West Parcel via biosparge operations between 2012 and 2015. Four subsequent groundwater sampling events were conducted between September 2015 and July 2016, during which toluene concentrations

remained below laboratory detection limits. The EPA determined in 2017 that the East Parcel cleanup was fully complete with no controls required (EPA, 2017).

In addition to removal of contamination and demolition of historic structures, new redevelopment on the West Parcel included (shown in Figure 2):

- The site was regraded and paved;
- A new stormwater system including new piping, catch basins, and treatment vault were added;
- A new GWPT building was constructed along the northern property line and extraction well piping was re-routed; and

While primarily done for property development, the combination of paving and stormwater improvements reduced infiltration of stormwater inside the barrier wall.

2.3.2.5. 2018-2019 CO₂ Pilot Study

The CO₂ pilot study was performed to assess the effectiveness and feasibility of CO₂ injection to neutralize high pH groundwater prior to preparation of the CMS. The pilot study was performed inside the barrier wall (Figure 4) to limit potential adverse effects during the study. The pilot study confirmed the technical feasibility of the technology, but indicated additional evaluation was necessary to implement full-scale use.

2.3.3. CONSIDERATION FOR RECENT CONTAMINANT CHARACTERIZATION

Historical soil and groundwater investigations conducted at the site have shown that the west side and southwest corner of the site have been affected by releases of potential COCs. Other COCs at the site that have been investigated over time include polycyclic aromatic hydrocarbons, methylene chloride, benzene, PCBs, SVOCs, aluminum, arsenic, chromium, lead, mercury, nickel, vanadium, and dioxins/furans.

Historic data trends presented in routine performance monitoring reports have shown toluene to be the primary VOC observed and decreases in toluene concentrations have occurred at locations monitored inside the subsurface barrier wall (MW-17, MW-28, MW-29). Toluene has remained low in concentration at locations monitored outside the barrier wall since 2003. Trends in dissolved metals, with copper being the primary metal detected, show copper has decreased at exterior wells MW-40 and MW-41 and increased at interior pumping well EX-3. pH levels have remained generally stable, with higher pH found in the southwest corner of the site. Carbon dioxide treatment for in this area may have altered conditions in recent years. SVOCs were last tested across the site in 2015 and were not detected, but lower reporting limits are now attainable by the laboratory.

Preliminary reporting provided by EPA showed dioxins/furans and PCBs were recently detected in sediments as part of design investigations being performed as part of the Lower Duwamish Waterway Superfund cleanup. A former incinerator was identified in historical drawings as being present at one point near the shoreline north of the site (Figure 3 [Location 41]). Recent groundwater sampling has not included either dioxin/furan or PCBs at the site, though historical samples did not identify either of these as COCs in groundwater. Collection of samples near the shoreline and in areas related to historical use

would allow for updating the current conceptual model and accounting for improved laboratory methods that can achieve lower reporting limits.

3. APPROACH

This section describes what additional data collection or analysis is proposed to address data gaps.

3.1. Preliminary Remediation Goals (PRGs) Update

As described in Section 2, initial screening of revised PRGs was performed in 2020 using historical site data. Additional sampling for groundwater and soil constituents was determined to be necessary to provide current site condition data for comparison against the revised PRGs. As part of completing the data gaps work, newly collected data will be screened against revised PRGs to develop a revised list of soil, groundwater, and sediment COCs.

3.2. Temporary Groundwater Pumping Cessation

The hydraulic control performance evaluation is targeted to coincide with falling river stage levels in the Duwamish Waterway generally observed in later winter or spring each year. Monitoring under passive hydraulic control conditions will include collection of:

1. Baseline water level and analytical data (prior to system shutdown),
2. Monthly observation of water levels inside and outside the barrier wall (at multiple depths), and
3. Periodic field parameter and analytical monitoring of barrier wall perimeter monitoring wells (depending on baseline observations.)

The approach to this task is outlined in the adaptive management flow chart presented in Figure 5. An adaptive management approach will be used to continually collect data, assess, and determine next steps over the course of the planned six month test period. The six month test period is inclusive of the annual sampling event (Round 93, September 2021) allowing for collection of groundwater samples within the subsurface barrier wall following water level equilibration. If data gaps are remaining after Round 93, then a request for an extension to the test period will be requested from EPA to allow for collection of additional data.

The combination of hydraulic information (vertical and horizontal gradients, water table elevation, etc.), field water quality parameters, and contaminant concentrations will be utilized to assess changes in fate and transport inside and outside the barrier wall. Trends and changes in this data will be compared over the test period and also compared to the extensive historic data sets from previous performance monitoring. The baseline data, in concert with the decades of historic data, will aid in evaluation of changes and may help determine the cause of changes (i.e. if changes are a result of movement across the wall or water coming up through the aquitard or changes in environmental conditions from an outside influence).

If data collection indicates a threat to water quality outside the HCIM as detailed in Figure 5, system pumping will resume in accordance with the Revised Operation, Monitoring, Inspection, and Maintenance Plan (AMEC Geomatrix, 2010).

3.2.1. BASELINE MONITORING

As initial round of water level measurements and groundwater quality sampling will be conducted prior to system shutdown to provide a baseline data set for evaluation purposes during pumping cessation. Water level measurements will provide data for calculation of horizontal and vertical gradients inside and across the barrier wall to further understand the changing gradients that may occur during the test. Groundwater quality samples will provide initial concentrations for use in determining monitoring requirements during pumping cessation.

Water level measurements will be measured at the wells shown in Figure 6 including from wells near the barrier wall on both the inside and outside, as well as centrally located within the wall where there are well pairs with multiple screen intervals. These same wells will continue to be monitored throughout the performance evaluation period.

Analytical samples will also be collected from the wells shown in Figure 7, gathering data from wells near the barrier wall on both the inside and outside.

3.2.2. WATER LEVEL MONITORING

As part of performance monitoring, water levels are monitored on a quarterly basis. Water level monitoring during the pumping cessation will increase in frequency for both those collected manually and via transducer measurement. During the evaluation period, monthly water level measurements will be collected within the barrier wall; and transducers currently installed in wells MW-51, MW-52, and MW-53 will be set to record groundwater elevations hourly (Figure 6). The transducer in MW-47 will be set to record hourly and will be moved to MW-54, allowing for continuous water level monitoring for the upper and lower zone well pair (MW-53 and MW-54). Monitoring will provide adequate spatial coverage and frequency to assess performance of the barrier wall while water levels inside equilibrate and allow for detection of changes in gradients that may require additional analytical monitoring to assess the potential to accelerate contaminant migration across the wall. Historic transducer water level data from MW-49 and DM-8 provides decades of data for comparison to help assess if changes due to pumping cessation are out of the previously normal range.

Previous water level observations have generally shown an upward hydraulic gradient from the deep aquifer to the lower zone of the shallow aquifer, through the aquitard. Changes in the gradients (direction and size) and water levels in the wells will be monitored during the pumping cessation period and compared to the baseline results, as well as historical gradients and water levels, to evaluate changing conditions as water levels within the barrier wall rise. Due to variations in lithology (heterogeneity) within the deep aquifer, variability across the site is expected.

3.2.3. WATER QUALITY MONITORING

Water quality monitoring (analytical and field parameter monitoring) will be used to assess the impact of water level rebound within the barrier wall on COCs, i.e. the potential mobilization of COCs within the vadose zone and the potential cross barrier-wall/aquitard COC transport.

Analytical and field parameter monitoring will be conducted at key locations identified following baseline monitoring through the adaptive management flow chart (Figure 5). From this flow chart, wells

will either be sampled on a monthly or semiannual basis for COCs outlined as part of the baseline monitoring event.

The objective of the of the water quality monitoring is to assess changes in groundwater chemistry inside and outside the wall and to determine the potential for COC migration from the interior of the site to the exterior wells with or without the hydraulic containment measure.

The baseline monitoring data set along with previous semiannual performance monitoring data collected, will be used for assessing changes in groundwater chemistry during the passive evaluation period. These general parameters are helpful for evaluating changes in geochemistry. General water quality parameters (pH, oxidation/reduction potential [ORP], dissolved oxygen, specific conductance, and temperature) reached steady-state conditions as of September 2005 (AMEC Geomatrix, 2009). Significant change in pH or ORP could indicate changes in potential for metals migration or adsorption. Groundwater flow through the wall is very slow and semi-annual monitoring has proved to be sufficient for cross-wall geochemical changes (AMEC Geomatrix, 2009).

If contaminant concentrations are greater inside the barrier wall than outside the barrier wall, more frequent monitoring will be conducted throughout the duration of the pumping cessation to check for signs of migration. If concentrations are greater outside the wall than inside the wall, then wells will be monitored semi-annually, coinciding with performance monitoring events. If contaminant concentrations outside the wall begin to increase during the evaluation period and are projected to exceed PRGs within five years from the sampling date, the pumping system would be restarted.

3.2.4. TREATMENT SYSTEM OPERATIONS DURING EVALUATION

The HCIM will be switched to passive operations, with the groundwater pretreatment system extraction wells turned off during the evaluation. Power to the treatment system will remain on to allow recording of the water levels in wells MW-49 and DM-8. During the evaluation, the system will be periodically cycled to verify functionality. The granular activated carbon (GAC) vessels will be drained between cycling events to prevent fouling during the extended period of shut down.

3.3. Groundwater Sample Collection

As described in EPA's March 2021 letter, EPA and DOF collaborated over several technical meetings to establish a specific groundwater sampling task to address uncertainty associated with the current conditions, as presented in the 2014 Agency Draft CMS work plan, and to more precisely determine the nature and extent of contamination. Groundwater samples will be collected from a broader suite of wells and for a broader suite of potential COCs than have previously been tested and thereby provide a current snapshot of conditions. Data collected will also inform the performance evaluation during groundwater pumping cessation and the geochemical conditions in the vicinity of the CO₂ pilot study.

Figure 7 shows the sampling to be conducted to address this current data gap and includes testing for all of the analytes mentioned in EPA's 2021 letter. Table 1 summarizes the samples to be collected and the rationale for this sampling. An updated version of the project Quality Assurance Project Plan (QAPP) was also prepared and will be submitted to EPA concurrent with this work plan (DOF, 2021). The QAPP update accounts for current staff, the data gap scope of work, and updated sampling methods to attain the mandated lower reporting limits.

4. DATA COLLECTION METHODS

This section describes the methods to be used to implement the various pre-CMS data gap tasks.

4.1. Well Inspection and Rehabilitation

Twenty-five of the wells identified for monitoring are not part of the current performance monitoring well network and therefore have not been inspected or sampled in years. These wells, along with currently monitored wells, were inspected to verify suitability for sampling groundwater and to evaluate if redevelopment will be necessary prior to sample collection. Inspection of the monitoring wells included removal of the dedicated pump(s), if necessary, and measuring the total depth to evaluate siltation at the bottom of the well. Recent sampling data were reviewed to evaluate if evident decreases in purge rates or water level drawdown occurred outside of allowable ranges.

Seven wells were identified for redevelopment. A summary of the inspection and recommendation was submitted via email to EPA on March 26, 2021 to allow for appropriate redevelopment of wells as much ahead of before groundwater sampling as practicable. Well development will follow EPA's Ground Water Forum document *Monitoring Well Development Guidelines for Superfund Project Managers* (EPA, 1992).

4.2. Groundwater Elevation Monitoring

Manual water levels will be measured either during a low tide or high tide to minimize tidal influence during the measurement period, per procedures identified in the Performance Monitoring Plan (AMEC Geomatrix, 2009). The observed groundwater elevation conditions will be compared to similar tidal conditions observed during the baseline monitoring event along with the monthly groundwater elevation measurements.

The water level information taken from the transducers loggers will be downloaded monthly during the manual water level measurement collection events. The transducer water level data for DM-8, MW-49, MW-51, MW-52, MW-53 and MW-54 will be tracked for the duration of the pumping cessation period.

4.3. Groundwater Sample Collection

Groundwater samples for laboratory analysis will be collected as described in Section 3.3. Groundwater sample collection procedures will follow the Performance Monitoring Plan (AMEC Geomatrix, 2009) and Revised Quality Assurance Project Plan (DOF, 2021). All exterior monitoring network wells along the west and south portions of the barrier wall will be sampled during a falling tide. During purging, general water quality parameters will be monitored for stabilization in all wells prior to sampling.

Based on discussions with EPA, we have considered and incorporated additional sample collection protocols to account for the collection of samples being analyzed for potential COCs that are particularly susceptible to bias from higher turbidity or background contamination. These protocols include:

- Sample collection outside the subsurface barrier wall (tidally influenced), requires sample collection during a falling tide when the groundwater flow direction is from the inland source area to the waterway.

- A peristaltic pump or dedicated bladder pump will be used to purge and sample wells. For wells sampled by peristaltic pump, the tubing will be disposable single use low-density polyethylene and silicone tubing. Pump and tubing intake for sample collection will be located at the center of the well screen interval.
- Sample locations will be purged for a minimum of 15 minutes (five stabilization readings, collected every three minutes).
- A water quality instrument will be used to establish stabilization of the following water quality parameters prior to sampling:
 - *Turbidity*: Turbidity > 5 NTU, $\pm 10\%$; if 3 readings < 5, consider stabilized (NTU)
 - *Dissolved Oxygen (DO)*: DO > 0.5, $\pm 10\%$; if 3 readings < 0.5, consider stabilized (mg/L)
 - *Specific Conductance*: $\pm 3\%$ (S/cm)
 - *Temperature*: ± 1 degree C
 - *pH*: ± 0.1 standard units
 - *Oxidation Reduction Potential*: ± 10 mV
- The water level meter will be washed onsite with warm tap water and non-phosphate detergent prior to use and rinsed with laboratory-provided DI prior to placement down the well.
 - For wells to be sampled for PCBs, decontamination of the water level meter will include a final rinse with hexane and laboratory DI rinse.
- Low flow purging will continue for a maximum of two hours to achieve a turbidity less than 5 Nephelometric Turbidity Units (NTU) prior to sample collection. If turbidity does not decrease to below 5 NTU, two samples will be collected and analyzed, one for total and one for filtering, by the analytical laboratory for PCB analysis, dioxins and furans, and SVOCs.
 - If sample volume is collected for laboratory filtering, additional volume will be collected for total suspended solids (TSS), total dissolved solids (TDS), total solids, chloride, specific conductance, and dissolved organic carbon (DOC).
 - Laboratory filtering will be through a 1 micron filter.

Other standard operating procedures and equipment calibration requirements are included in the Performance Monitoring Plan (AMEC Geomatrix, 2009) and the Revised Quality Assurance Project Plan (DOF, 2021). The field log for groundwater sample collection is included as Attachment 4. All purge water and decontamination water generated as part of groundwater sample collection will be processed through the pre-treatment system and discharge to King County.

4.4. Groundwater Pumping System Monitoring

During the period of pumping cessation of the groundwater pretreatment (GWPT) system, the GAC treatment vessels will be drained to reduce biological growth within the treatment media. The vessels will be drained through movement of hoses to allow the units to gravity drain to the sewer line. After draining, the hoses will be re-installed in their normal orientation, in the event the system must be restarted.

Quarterly cycling of the GWPT system will be done to assure an operational system, in the event the evaluation indicates restart of the system is necessary. This cycling will include manual operation of each of the three individual extraction wells for a 20 minute period (one hour total) and then turning all pumps to automatic operation to confirm proper function of the Programable Logic Controller (PLC). During cycling of the system, purge water from groundwater monitoring will be processed through the GWPT system. Following the quarterly cycling, the GAC units will be drained as discussed above.

5. REPORTING

This section discusses the reporting approach for the pre-CMS data gaps work.

Progress Reporting

The quarterly Progress Reporting frequency will be increased to monthly during implementation of the work plan. The progress reports will include the following items, in addition to standard progress reporting requirements discussed in the Performance Monitoring Plan (AMEC Geomatrix, 2009):

- Monthly water level measurements;
- Validated analytical data, as it becomes available;
- Discussion of chemical concentration projections, in relation to the adaptive management flow chart provided as Figure 5;
- Documentation of operational decisions made in cooperation with EPA; and
- Discussion of quarterly treatment system operations and maintenance testing.

Round 91 Progress Report

The regular Round 91 progress report will include results of standard spring groundwater sampling typically performed at the site, along with the rest of the baseline groundwater sampling event to be conducted under this Work Plan.

Pre-CMS Conditions Report

A Current Conditions Report will be prepared following conclusion of the work plan tasks and the September Round 93 sampling event. The report will provide:

- A summary of the results of samples collected to address data gaps;
- A discussion of current constituent concentrations relative to historical data;
- An updated description of the nature and extent of contamination that incorporates data collected as part of these tasks as well as pending relevant data from outside sources such as the Lower Duwamish Waterway Group;
- An evaluation of the HCIM hydrogeologic system and effect on contaminant concentrations and transport during the period of temporary pumping cessation;
- Discussion of engineering design data collected to further evaluate long-term effectiveness of the CO₂ neutralization technique used in the pilot study; and
- Revised constituents of concern based on data comparison to the updated PRGs.

This report will provide the additional data necessary to begin preparation of the CMS for the site. The report will also include results from the Round 93 performance monitoring event (September 2021) and

will be submitted on the schedule for the Round 93 report (60 days after the validated data set is received).

6. SCHEDULE

Following EPA's approval of this work plan (assumed to occur in April 2021) baseline groundwater samples will be collected as close to the seasonal decrease in river stage as practical. Collection of the Round 91 performance monitoring samples will coincide with the baseline sample collection. Following completion of the baseline sampling event, the groundwater pump and treatment system (system) will be turned off, allowing water levels inside the barrier wall to begin to rise. Following the system shutdown, monitoring will be adaptively managed per the adaptive management flow chart provided as Figure 5.

Monthly groundwater levels and sample collection will occur per Figure 5 and if conditions warrant restart of the system, the pumping cessation test will be abandoned and pumping resume to attain the 1-foot differential across the barrier wall. If conditions do not warrant restart of the system, the pumping cessation will continue until Round 93 sampling occurs in September 2021. At the conclusion of the test, the data report discussed above will be prepared to coincide with submittal of the Round 93 performance monitoring report.

Regular communication between DOF and EPA will continue throughout the implementation of the work plan to discuss field activities and results, allowing for adaptive management during implementation.

7. REFERENCES

- AMEC Geomatrix, 2009, Interim Measures Performance Monitoring Plan, Former Rhone-Poulenc Site, Tukwila, Washington: Prepared for Container Properties, L.L.C., August.
- AMEC Geomatrix, 2010, Revised Operation, Monitoring, Inspection, and Maintenance Plan, Former Rhone-Poulenc Site, Tukwila, Washington: Prepared for Container Properties, L.L.C., January.
- AMEC, 2014, Agency Draft Corrective Measures Study Work Plan, Former Rhone-Poulenc Site, Tukwila, Washington: Prepared for Container Properties, L.L.C., September.
- DOF, 2021, Revised Quality Assurance Project Plan, Former Rhone-Poulenc Site, Tukwila, Washington: Prepared for Container Properties, L.L.C., April.
- EPA, 1992, Ground Water Forum, Monitoring Well Development Guidelines for Superfund Project Managers, April.
- EPA, 2017, Letter from Timothy B. Hamlin (EPA) to Gary Dupuy (AMEC Foster Wheeler), RE: Determination of Corrective Action Complete without Controls for East Parcel Administrative Order on Consent for Corrective Action (Order) Under the Resource Conservation and Recovery Act (RCRA), Docket No. 1091-11-20-3008(h), August 29.
- Geomatrix, 2006, Voluntary Interim Measure Report, Hazardous Waste Storage Area and Transformer A Area Cleanup, Former Rhone-Poulenc Site, Tukwila, Washington, August.
- Geomatrix, 2007, Northwest Corner Affected Soil Removal Report, Former Rhone-Poulenc Site, Tukwila, Washington, January.
- Rhodia, 1998, Interim Measures Report, Rhodia Inc. Facility, Tukwila, Washington, August 8.
- Wood, 2020, Carbon Dioxide Neutralization Pilot Study Results, Former Rhone-Poulenc Site, Tukwila, Washington: Prepared for Container Properties, L.L.C., May 15.

Tables

TABLE 1
GROUNDWATER SAMPLING COLLECTION AND RATIONALE
Former Rhone-Poulenc Facility
Tukwila, Washington

| Well ID | Rationale | GW Quality Parameters | Chemical Analysis | | | | | | | | | | | |
|----------------|--|-----------------------|-------------------|-------------------|------|-------|---------------|--------------|----|----|-----|------------|----------|--------|
| | | | BTEX | Total Metals | PCBs | SVOCs | Dioxin/Furans | Geochemistry | | | | | | |
| | | | | | | | | Cation/Anion | Mn | Fe | TDS | Alkalinity | Hardness | Silica |
| A2 | Not recently sampled. Historically detected coper (230 ug/L in 2000). | X | | X ² | | | | | | | | | | |
| B1A | Sampled semi-annually as part of the PMP. | X | X | X ¹ | | | | | | | | | | |
| B1B | Not recently sampled. Historically detected copper (22.5 ug/L in 1994). | X | | X ² | | | | | | | | | | |
| B6 | Not recently sampled. Historically higher levels of copper (304 ug/L in 1994) and located near the 1995 PCB Autoclave Building sewer line cleanup. The SVOC naphthalene was detected at 2 ug/L in 1994. | X | | X ² | X | X | | | | | | | | |
| DM-4 | Not recently sampled. Located near historical "pentachlorophenol handling area" of site, as identified in the 1990 RCRA Facility Assessment. | X | | | | X | | | | | | | | |
| DM-5 | Sampled annually as part of the PMP, but not for PCBs. Located near the 1995 PCB Autoclave Building sewer line cleanup. | X | Sept | Sept ¹ | X | | | | | | | | | |
| DM-8 | Sampled semi-annually as part of the PMP, but not for PCBs or SVOCs. Location is along western shoreline which allows for assessing PCB concentrations in groundwater near the Duwamish Waterway. Located in historically downgradient direction from H-10, which had a historical SVOC detection. | X | X | X ¹ | X | X | | | | | | | | |
| EX-1 | Not recently sampled. Located near historical "pentachlorophenol handling area" of site, as identified in the 1990 RCRA Facility Assessment. | X | | | | X | | | | | | | | |
| EX-3 | Sampled quarterly as part of the PMP. | X | X | X ¹ | | | | | | | | | | |
| H-10 | Not recently sampled. Historically detected toluene (330,000 ug/L in 1991), copper (96 ug/L in 1991) and pentachlorophenol (5 ug/L in 1994). | X | X | X ² | | X | | | | | | | | |
| Injection Well | Geochemical data will inform long term effects of CO ₂ pilot study | X | | | | | | | | | | | | X |
| IMW-A1-D | Geochemical data will inform long term effects of CO ₂ pilot study | X | | X ² | | | | | X | X | | | | X |
| IMW-A2-D | Geochemical data will inform long term effects of CO ₂ pilot study | X | | | | | | | | | | | | X |
| IMW-A2-S | Geochemical data will inform long term effects of CO ₂ pilot study | X | | | | | | | | | | | | X |
| IMW-B1-D | Geochemical data will inform long term effects of CO ₂ pilot study | X | | | | | | | | | | | | X |
| IMW-B1-S | Geochemical data will inform long term effects of CO ₂ pilot study | X | | | | | | | | | | | | X |
| MW-12 | Not recently sampled. Historically a higher toluene (84,000 ug/L in 1994) and copper (84.1 ug/L in 1994). SVOCs were not detected in 1994. Centrally located on the site. | X | X | X ² | | | | | | | | | | |
| MW-17 | Sampled annually as part of the PMP. | Sept | Sept | Sept ¹ | | | | | | | | | | |
| MW-22 | Not recently sampled. Location is near western shoreline which allows for assessing PCB concentrations in groundwater near the Duwamish Waterway. Not high for BTEX or metals historically, but not sampled for SVOCs. Located relatively near historical "pentachlorophenol handling area" of site, as identified in the 1990 RCRA Facility Assessment and closer to shoreline. | X | | | X | X | | | | | | | | |
| MW-27 | Sampled annually as part of the PMP. Historically high toluene concentrations in this area. Located in historically downgradient direction from H-10, which had a historical SVOC detection. | X | Sept | Sept ¹ | | X | | | | | | | | |
| MW-28 | Sampled annually as part of the PMP. Historically high toluene concentrations in this area. Located in historically downgradient direction from H-10, which had a historical SVOC detection. | X | Sept | Sept ¹ | | X | | | | | | | | |
| MW-29 | Sampled annually as part of the PMP. | Sept | Sept | Sept ¹ | | | | | | | | | | |
| MW-38R | Sampled semi-annually as part of the PMP. Near the vicinity of former incinerator reported in the 1990 RFA, as being north of the this area. PCBs detected in shallow soils nearby in 2015 and is near the shoreline. Located relatively near historical "pentachlorophenol handling area" of site, as identified in the 1990 RCRA Facility Assessment and closer to shoreline. | X | X | X ¹ | X | X | X | | | | | | | |
| MW-39 | Sampled semi-annually as part of the PMP. | X | X | X ¹ | | | | | | | | | | |
| MW-40 | Sampled semi-annually as part of the PMP. | X | X | X ¹ | | | | | | | | | | |
| MW-41 | Sampled semi-annually as part of the PMP. Location is on the western shoreline which allows for assessing PCB concentrations in groundwater near the Duwamish Waterway. | X | X | X ¹ | X | | | | | | | | | |
| MW-42 | Sampled semi-annually as part of the PMP. | X | X | X ¹ | | | | | | | | | | |
| MW-43 | Sampled semi-annually as part of the PMP, assessment of geochemical parameters will aid in assessing CO ₂ neutralization outside the barrier wall. | X | X | X ¹ | | | | X | | | X | X | X | X |

TABLE 1
GROUNDWATER SAMPLING COLLECTION AND RATIONALE
Former Rhone-Poulenc Facility
Tukwila, Washington

| Well ID | Rationale | GW Quality Parameters | Chemical Analysis | | | | | | | | | | | | |
|---------|--|-----------------------|-------------------|----------------|------|-------|-------------------|------------------|----|----|-----|------------|----------|--------|--|
| | | | BTEX | Total Metals | PCBs | SVOCs | Dioxin/ Furans | Geochemistry | | | | | | | |
| | | | | | | | | Cation/ Anion | Mn | Fe | TDS | Alkalinity | Hardness | Silica | |
| MW-44 | Sampled semi-annually as part of the PMP, assessment of geochemical parameters will aid in assessing CO ₂ neutralization outside the barrier wall. Location is along southern shoreline which allows for assessing PCB and SVOC concentrations in groundwater near the Duwamish Waterway. | X | X | X ¹ | X | X | | X | | | X | X | X | X | |
| MW-45 | Sampled semi-annually as part of the PMP, assessment of geochemical parameters will aid in assessing CO ₂ neutralization outside the barrier wall. | X | X | X ¹ | | | | X | | | X | X | X | | |
| MW-46 | Sampled semi-annually as part of the PMP, assessment of geochemical parameters will aid in assessing CO ₂ neutralization outside the barrier wall. Location is along southern shoreline which allows for assessing PCB concentrations in groundwater near the Duwamish Waterway. | X | X | X ¹ | X | | | X | | | X | X | X | | |
| MW-47 | Sampled semi-annually as part of the PMP. Near the vicinity of former incinerator reported in the 1990 RFA, as being north of the this area. PCBs detected in shallow soils nearby in 2015 and is near the shoreline. Part of well cluster with wells on either side of the subsurface barrier wall. Located relatively near historical "pentachlorophenol handling area" of site, as identified in the 1990 RCRA Facility Assessment and closer to shoreline. | X | X | X ² | X | X | X | | | | | | | | |
| MW-48 | Not recently sampled. Part of well cluster with wells on either side of the subsurface barrier wall. | X | X | X ² | | | | | | | | | | | |
| MW-49 | Not recently sampled. Part of well cluster with wells on either side of the subsurface barrier wall. Near former toluene SVE operations (1999-2002). Located in historically downgradient direction from H-10, which had a historical SVOC detection. | X | X | X ² | | X | | | | | | | | | |
| MW-50 | Not recently sampled. Part of well cluster with wells on either side of the subsurface barrier wall. | X | X | X ² | | | | | | | | | | | |
| MW-51 | Not recently sampled. Part of well cluster with wells on either side of the subsurface barrier wall. | X | X | X ² | | | | | | | | | | | |
| MW-52 | Not recently sampled. Part of well cluster with wells on either side of the subsurface barrier wall. | X | X | X ² | | | | | | | | | | | |
| MW-53 | Not recently sampled. Part of well cluster with wells on either side of the subsurface barrier wall. Assessment of geochemical parameters will aid in assessing CO2 neutralization near the barrier wall. | X | X | X ² | | | | X | | | X | X | X | X | |
| MW-54 | Not recently sampled. Part of well cluster with wells on either side of the subsurface barrier wall. Assessment of geochemical parameters will aid in assessing CO2 neutralization near the barrier wall. | X | X | X ² | | | | X | | | X | X | X | X | |
| MW-55 | Not recently sampled. Part of well cluster with wells on either side of the subsurface barrier wall. Assessment of geochemical parameters will aid in assessing CO2 neutralization near the barrier wall. | X | X | X ² | | | | X | | | X | X | X | X | |
| MW-56 | Not recently sampled. Part of well cluster with wells on either side of the subsurface barrier wall. Assessment of geochemical parameters will aid in assessing CO2 neutralization near the barrier wall. | X | X | X ² | | | | X | | | X | X | X | X | |
| MW-58 | Historically detected metals along northern property line in soil and some historical groundwater samples (see Figure 3-11 and 3-21 from the 2014 Draft CMS Work Plan) | X | | X ² | | | | | | | | | | | |
| MW-59 | Historically detected metals along northern property line in soil and some historical groundwater samples (see Figure 3-11 and 3-21 from the 2014 Draft CMS Work Plan) | X | | X ² | | | | | | | | | | | |

Notes:

Chemical concentration data presented was sourced from the 2014 Draft CMS Work Plan (Amec) or the project database shared with EPA.

X¹ = Aluminum, Arsenic, Cadmium, Chromium, Copper, Lead, Mercury, Nickel, Selenium, Thallium, Vanadium, Zinc

X² = Aluminum, Arsenic, Cadmium, Chromium, Copper, Lead, Mercury, Nickel, Selenium, Vanadium, Zinc

Thallium is only proposed for locations required under the Performance Monitoring Plan(PMP). Thallium has not been historically detected and has not been included as part of metals analysis in locations not included in the PMP.

Sept = sampled in September as part of PMP sampling

GW Quality Parameters = pH, specific conductivity, oxidation reduction potential, dissolved oxygen, turbidity, and temperature (field instrument measured)

Analytical methods to be used: BTEX by EPA 8260D, Total metals & iron by EPA 200.8 & 7470A, PCBs by EPA 8082A, SVOCs by EPA 8270E with SIM & 8041A, Dioxins/Furans by EPA 1613B, cation/anions/manganese by 6010C/D, chloride, sulfate by 300.0, Total phosphorous and total nitrogen by SM 4500, TDS/TSS by EPA SM2540, alkalinity by EPA 2320, hardness by 6010C, silica by 6010D

BTEX = benzene, toluene, ethylbenzene, and xylenes

Fe = iron

GW = groundwater

Cation/Anions = sodium, potassium, calcium, manganese, iron, chloride, sulfate, nitrate, magnesium, total phosphorous, total nitrogen.

Mn = manganese

PCBs = polychlorinated biphenyls

PMP = performance monitoring plan

RFA = RCRA Facility Assessment

SVOCs = semivolatile organic compounds

TDS = total dissolved solids

See Section 4.3 regarding potential TSS, TDS, total solids, chloride, dissolved organic carbon or filtered sample collection

Figures


PLOT TIME: 3/26/2021 4:01 PM MOD TIME: 3/26/2021 4:01 PM USER: Kelley Begley DWG: P:\Container Properties\CAD\Figures\2021-03\2021-03 Container Props Rhone-Poulenc 1 Site LayoutA.dwg



SOURCES:
PARCEL INFORMATION: KING COUNTY, WA.
AERIAL PHOTOGRAPHY: GOOGLE EARTH PRO, AUGUST 14, 2020.

LEGEND

— PARCEL LINE



**FORMER RHONE-POULENC SITE
TUKWILA, WASHINGTON**


VICINITY MAP

DOF DALTON
OLMSTED
FUGLEVAND


**FIGURE
1**

03/26/2021


PLOT TIME: 3/26/2021 11:30 AM MOD TIME: 3/26/2021 11:30 AM USER: Kelley Begley DWG: P:\Container Properties\CAD\Figures\2021-03\2021-03 Container Props Rhone-Poulenc 2 Site Layout.dwg



PLOT TIME: 3/25/2021 4:31 PM MOD TIME: 3/25/2021 4:04 PM USER: Kelley Bagley DWG: P:\Container Properties\CAD\Figures\2021-03\2021-03 Container Props Rhone-Poulenc 1 Historic.dwg



NOTE:
BASE MAP FROM AGENCY DRAFT CORRECTIVE MEASURES STUDY WORK
PLAN BY AMEC ENVIRONMENT & INFRASTRUCTURE, INC. (SEPTEMBER 2014)



**FORMER RHONE-POULENC SITE
TUKWILA, WASHINGTON**


Historic Structures

DOF DALTON
OLMSTED
FUGLEVAND


**FIGURE
3**

03/25/2021


PLOT TIME: 4/21/2021 10:25 AM MOD TIME: 4/21/2021 10:24 AM USER: Kelley Begley DWG: P:\Container Properties\CAD\Figures\2021-03\2021-03 Container Props Rhone-Poulenc 2 Interim Measures.dwg




PLOT TIME: 3/26/2021 4:46 PM MOD TIME: 3/26/2021 4:46 PM USER: Kelley Begley DWG: P:\Container Properties\CAD\Figures\2021-03\2021-03 Container Props Rhone-Poulenc 5 Adaptive Mngmt Flow Chart.dwg



PLOT TIME: 4/21/2021 10:28 AM MOD TIME: 4/21/2021 10:28 AM USER: Kelley Begley DWG: P:\Container Properties\CAD\Figures\2021-03\2021-03 Container Props Rhone-Poulenc 5 Water Monitoring.dwg





Attachment 1


Relevant 2014 Draft CMS Work Plan Maps & Technical Meeting Figures

Plot Date: 08/28/14 - 1:46pm, Plotted by: jeffrey.sanders
Drawing Path: C:\Users\jeffrey.sanders\appdata\local\temp\AcPublish_5212\, Drawing Name: FRP_SiteMap_081414.dwg

DUWAMISH WATERWAY

0 50 100
APPROXIMATE SCALE IN FEET

FORMER BARGE PIER



EXPLANATION

- APPROXIMATE LOCATION OF BARRIER WALL
- PROPERTY LINE
- FENCE LINE
- KING COUNTY 36" OUTFALL
- SEDIMENT SAMPLE LOCATION
- SOIL SAMPLE LOCATION
- DIRECT PUSH BORING LOCATION (2006) POST EXCAVATION EXCEED THE PRG FOR TOLUENE.
- TOLUENE CONCENTRATION IS BELOW PRELIMINARY REMEDIATION GOAL (PRG)
- TOLUENE CONCENTRATION IS > PRG, BUT ≤ 10X PRG
- TOLUENE CONCENTRATION IS > 10X PRG, BUT ≤ 100X PRG
- UPLAND AREA
- HCIM AREA
- SEDIMENT AREA
- SHORELINE AREA
- SLIP 6 SHORELINE AREA OWNED BY THE BOEING COMPANY

NOTES:

- UPLAND AND HCIM AREA SOILS PRELIMINARY REMEDIATION GOAL FOR TOLUENE IS 98.1 mg/kg.
- SHORELINE AREA SOILS PRELIMINARY REMEDIATION GOAL FOR TOLUENE IS 0.670 mg/kg.
- TOLUENE IS NOT A COC FOR SEDIMENT.
- POINTS THAT ARE NOT HIGHLIGHTED WERE NOT ANALYZED FOR THE GIVEN CONSTITUENT.
- BOUNDARY BETWEEN SEDIMENT AND SHORELINE AREAS IS DEFINED AS 12 FEET MLLW.

TOLUENE CONCENTRATIONS IN SOIL Former Rhone-Poulenc Site Tukwila, Washington

By: APS Date: 08/28/14 Project No. 08769





Figure 3-5

Plot Date: 08/28/14 - 3:41pm, Plotted by: jeffrey.sanders
Drawing Path: G:\Seattle\8769 - Former Rhone-Poulenc Site\112_CMS Work Plan\ Drawing Name: FRP_SiteMap_081414.dwg

DUWAMISH WATERWAY

0 50 100
APPROXIMATE SCALE IN FEET



EXPLANATION

- APPROXIMATE LOCATION OF BARRIER WALL
- PROPERTY LINE
- FENCE LINE
- KING COUNTY 36" OUTFALL
- SEDIMENT SAMPLE LOCATION
- SOIL SAMPLE LOCATION
- PCB CONCENTRATION IS < PRELIMINARY REMEDIATION GOAL (PRG)
- SOILS: PCB CONCENTRATION IS > PRG, BUT < 10X PRG
- SEDIMENT: PCB CONCENTRATION IS BETWEEN THE PRG AND REMEDIAL ACTION LEVEL (RAL) FOR THE LOWER DUWAMISH WATERWAY (LDW)
- SOILS: PCB CONCENTRATION IS > 10X PRG
- SEDIMENT: PCB CONCENTRATION IS > RAL FOR THE LDW
- UPPER INTERVAL (Top 10 cm)
- LOWER INTERVAL (10-45 cm)
- UPLAND AREA
- HCIM AREA
- SEDIMENT AREA
- SHORELINE AREA
- SLIP 6 SHORELINE AREA OWNED BY THE BOEING COMPANY

NOTES:


1. UPLAND AND HCIM AREAS PRELIMINARY REMEDIATION GOAL FOR PCB (AROCOR 1254) IS 7.4 mg/kg.
2. SHORELINE AREA SOILS PRELIMINARY REMEDIATION GOAL FOR PCB IS 12 mg/kg ORGANIC CARBON. WHERE TOTAL ORGANIC CARBON DATA IS NOT AVAILABLE, OR WHEN OUTSIDE OF THE RECOMMENDED RANGE, CONCENTRATIONS WERE COMPARED WITH THE PUGET SOUND APPARENT EFFECTS THRESHOLD (AET) VALUE OF 130 µg/kg DRY WEIGHT.
3. SEDIMENT AREA PRELIMINARY REMEDIATION GOAL FOR PCB FOR 0-10 cm DEPTH INTERVAL IS 2 µg/kg AND FOR 10-45 cm DEPTH INTERVALS IS 12 mg/kg ORGANIC CARBON.
4. DATA REPORTED FOR THE LOWER INTERVAL AT LOCATION SH-5 IS NORMALIZED TO ORGANIC CARBON, EVEN THOUGH TOTAL ORGANIC CARBON WAS OUTSIDE OF RECOMMENDED RANGE.
4. POINTS THAT ARE NOT HIGHLIGHTED WERE NOT ANALYZED FOR THE GIVEN CONSTITUENT.
5. BOUNDARY BETWEEN SEDIMENT AND SHORELINE AREAS IS DEFINED AS 12 FEET MLLW.
6. IF A HALF CIRCLE IS SHOWN, THE OTHER INTERVAL WAS NOT SAMPLED, OR NOT ANALYZED.
7. SOURCES OF DATA USED TO PREPARE THIS FIGURE ARE DESCRIBED IN SECTION 2.3.1 OF THE CMS WORK PLAN.
8. PCB RAL FOR 0-10 CM DEPTH INTERVAL = 12 mg/kg ORGANIC CARBON, AND FOR 10-45 CM DEPTH INTERVAL = 65 mg/kg ORGANIC CARBON.
9. DATA REPORTED FOR THE LOWER INTERVAL FROM SAMPLES WITH 'RP-' PREFIX WAS COLLECTED FROM THE 2-3 FEET DEPTH INTERVAL.

PCB CONCENTRATIONS IN SEDIMENT AND SOIL Former Rhone-Poulenc Site Tukwila, Washington

By: APS Date: 08/28/14 Project No. 08769



Figure 3-7



| | |
|--|--|
| | APPROXIMATE LOCATION OF BARRIER WALL |
| | PROPERTY LINE |
| | FENCE LINE |
| | KING COUNTY 36" OUTFALL |
| | SEDIMENT SAMPLE LOCATION |
| | SOIL SAMPLE LOCATION |
| | BENZYL ALCOHOL CONCENTRATION IS < PRELIMINARY REMEDIATION GOAL (PRG) |
| | BENZYL ALCOHOL CONCENTRATION IS > PRG, BUT < 5X PRG |
| | UPLAND AREA |
| | HCIM AREA |
| | SEDIMENT AREA |
| | SHORELINE AREA |
| | SLIP 6 SHORELINE AREA OWNED BY THE BOEING COMPANY |

1. SEDIMENT AREA PRELIMINARY REMEDIATION GOAL FOR BENZYL ALCOHOL IS 57 µg/kg.
2. BENZYL ALCOHOL IS NOT A COC FOR THE HCIM, UPLANDS, OR SHORELINE AREAS.
3. POINTS THAT ARE NOT HIGHLIGHTED WERE NOT ANALYZED FOR THE GIVEN CONSTITUENT.
4. BOUNDARY BETWEEN SEDIMENT AND SHORELINE AREAS IS DEFINED AS 12 FEET MLLW.

BENZYL ALCOHOL CONCENTRATIONS IN SEDIMENT
Former Rhone-Poulenc Site
Tukwila, Washington

| | | |
|---------|----------------|-------------------|
| By: APS | Date: 08/28/14 | Project No. 08769 |
|---------|----------------|-------------------|

amec


Figure 3-8

Plot Date: 08/27/14 - 12:31pm, Plotted by: jeffrey.sanders
Drawing Path: C:\Users\jeffrey.sanders\appdata\localtemp\AcPublish_1760, Drawing Name: FRP_SiteMap_081414.dwg

DUWAMISH WATERWAY

0 50 100
APPROXIMATE SCALE IN FEET

FORMER BARGE PIER



EXPLANATION

- APPROXIMATE LOCATION OF BARRIER WALL
- - - PROPERTY LINE
- x - FENCE LINE
- ▼ KING COUNTY 36" OUTFALL
- △ SEDIMENT SAMPLE LOCATION
- SOIL SAMPLE LOCATION
- COPPER CONCENTRATION IS ≥ PRELIMINARY REMEDIATION GOAL (PRG), BUT < 10X PRG
- COPPER CONCENTRATION IS > 10X PRG, BUT < 100X PRG
- COPPER CONCENTRATION IS > 100X PRG
- UPLAND AREA
- HCIM AREA
- SEDIMENT AREA
- SHORELINE AREA
- SLIP 6 SHORELINE AREA OWNED BY THE BOEING COMPANY

NOTES:

1. UPLAND, HCIM, AND SHORELINE AREA SOILS PRELIMINARY REMEDIATION GOAL FOR COPPER IS 3.55 mg/kg.
2. COPPER IS NOT A SEDIMENT COC.
3. POINTS THAT ARE NOT HIGHLIGHTED WERE NOT ANALYZED FOR THE GIVEN CONSTITUENT.
4. BOUNDARY BETWEEN SEDIMENT AND SHORELINE AREAS IS DEFINED AS 12 FEET MLLW.
5. SOURCES OF DATA USED TO PREPARE THIS FIGURE ARE DESCRIBED IN SECTION 2.3.1 OF THE CMS WORK PLAN.

COPPER CONCENTRATIONS IN SOIL Former Rhone-Poulenc Site Tukwila, Washington

By: APS Date: 08/27/14 Project No. 08769




Figure 3-11

Plot Date: 08/28/14 - 12:15pm, Plotted by: jeffrey.sanders
Drawing Path: G:\Seattle\8769 - Former Rhone-Poulenc Site\112_CMS Work Plan\ Drawing Name: FRP_SiteMap_081414.dwg

DUWAMISH WATERWAY

0 50 100
APPROXIMATE SCALE IN FEET



EXPLANATION

- APPROXIMATE LOCATION OF BARRIER WALL
- PROPERTY LINE
- FENCE LINE
- KING COUNTY 36" OUTFALL
- MONITORING WELL LOCATION
- EXTRACTION WELL LOCATION
- PIEZOMETER LOCATION
- GROUNDWATER SAMPLING LOCATION
- PORE WATER SAMPLING LOCATION
- ABANDONED WELL
- TOLUENE CONCENTRATION IS < PRELIMINARY REMEDIATION GOAL (PRG)
- TOLUENE CONCENTRATION IS < 10X PRG
- TOLUENE CONCENTRATION IS BETWEEN 10X AND 100X PRG
- MONITORING WELL IS PART OF THE ACTIVE MONITORING NETWORK
- U UPPER ZONE MONITORING POINT
- L LOWER ZONE MONITORING POINT
- D DEEP AQUIFER MONITORING POINT

- UPLAND AREA
- HCIM AREA
- SEDIMENT AREA
- SHORELINE AREA
- SLIP 6 SHORELINE AREA OWNED BY THE BOEING COMPANY

NOTES:

- UPLAND AND HCIM AREA GROUNDWATER PRELIMINARY REMEDIATION GOAL FOR TOLUENE IS 1,000 µg/L.
- SHORELINE AREA GROUNDWATER PRELIMINARY REMEDIATION GOAL FOR TOLUENE IS 1,280 µg/L.
- GROUNDWATER LOCATIONS THAT DO NOT HAVE A PRG HIGHLIGHT WERE NOT SAMPLED FOR THIS COMPOUND.
- SOURCES OF DATA USED TO PREPARE THIS FIGURE ARE DESCRIBED IN SECTION 2.3.2 OF THE CMS WORK PLAN.

TOLUENE CONCENTRATIONS IN GROUNDWATER AND POREWATER SAMPLES Former Rhone-Poulenc Site Tukwila, Washington



By: APS Date: 08/28/14 Project No. 08769



Figure 3-14

Plot Date: 08/28/14 - 2:10pm, Plotted by: jeffrey.sanders
Drawing Path: G:\Seattle\8769 - Former Rhone-Poulenc Site\112_CMS Work Plan\ Drawing Name: FRP_SiteMap_081414.dwg

DUWAMISH WATERWAY



EXPLANATION

- APPROXIMATE LOCATION OF BARRIER WALL
- PROPERTY LINE
- FENCE LINE
- KING COUNTY 36" OUTFALL
- MONITORING WELL LOCATION
- EXTRACTION WELL LOCATION
- PIEZOMETER LOCATION
- GROUNDWATER SAMPLING LOCATION
- PORE WATER SAMPLING LOCATION
- ABANDONED WELL
- NAPHTHALENE AND PENTACHLOROPHENOL CONCENTRATION ARE BELOW PRELIMINARY REMEDIATION GOAL (PRG)
- NAPHTHALENE CONCENTRATION IS < PRG
- NAPHTHALENE CONCENTRATION IS > 10X PRG, BUT < 15X PRG
- PENTACHLOROPHENOL CONCENTRATION IS > 100X PRG
- MONITORING WELL IS PART OF THE ACTIVE MONITORING NETWORK

- U UPPER ZONE MONITORING POINT
- L LOWER ZONE MONITORING POINT
- D DEEP AQUIFER MONITORING POINT

- UPLAND AREA
- HCIM AREA
- SEDIMENT AREA
- SHORELINE AREA
- SLIP 6 SHORELINE AREA OWNED BY THE BOEING COMPANY

NOTES:

- UPLAND AND HCIM AREA GROUNDWATER PRELIMINARY REMEDIATION GOAL FOR NAPHTHALENE IS 0.14 µg/L.
- SHORELINE AREA GROUNDWATER PRELIMINARY REMEDIATION GOAL FOR NAPHTHALENE IS 25.6 µg/L.
- GROUNDWATER PRELIMINARY REMEDIATION GOAL FOR PENTACHLOROPHENOL IS 0.00344 µg/L.
- GROUNDWATER LOCATIONS THAT DO NOT HAVE A PRG HIGHLIGHT WERE NOT SAMPLED FOR THIS COMPOUND.
- SOURCES OF DATA USED TO PREPARE THIS FIGURE ARE DESCRIBED IN SECTION 2.3.2 OF THE CMS WORK PLAN.

NAPHTHALENE AND PENTACHLOROPHENOL CONCENTRATIONS IN GROUNDWATER AND POREWATER SAMPLES Former Rhone-Poulenc Site Tukwila, Washington

By: APS Date: 08/28/14 Project No. 08769




Figure 3-17

Plot Date: 08/27/14 - 11:02am, Plotted by: jeffrey.sanders
Drawing Path: G:\Seattle\8769 - Former Rhone-Poulenc Site\112_CMS Work Plan\ Drawing Name: FRP_SiteMap_081414.dwg

DUWAMISH WATERWAY

0 50 100
APPROXIMATE SCALE IN FEET



EXPLANATION

- APPROXIMATE LOCATION OF BARRIER WALL
- PROPERTY LINE
- FENCE LINE
- KING COUNTY 36" OUTFALL
- MONITORING WELL LOCATION
- EXTRACTION WELL LOCATION
- PIEZOMETER LOCATION
- GROUNDWATER SAMPLING LOCATION
- PORE WATER SAMPLING LOCATION
- ABANDONED WELL
- COPPER CONCENTRATION IS < PRELIMINARY REMEDIATION GOAL (PRG)
- COPPER CONCENTRATION IS < 10X PRG
- COPPER CONCENTRATION IS BETWEEN 10X AND 100X PRG
- COPPER CONCENTRATION IS > 100X PRG
- MONITORING WELL IS PART OF THE ACTIVE MONITORING NETWORK

- U UPPER ZONE MONITORING POINT
- L LOWER ZONE MONITORING POINT
- D DEEP AQUIFER MONITORING POINT

- UPLAND AREA
- HCIM AREA
- SEDIMENT AREA
- SHORELINE AREA
- SLIP 6 SHORELINE AREA OWNED BY THE BOEING COMPANY

NOTES:

- GROUNDWATER PRELIMINARY REMEDIATION GOAL FOR COPPER IS 8.0 µg/L.
- GROUNDWATER LOCATIONS THAT DO NOT HAVE A PRG HIGHLIGHT WERE NOT SAMPLED FOR THIS COMPOUND.
- SOURCES OF DATA USED TO PREPARE THIS FIGURE ARE DESCRIBED IN SECTION 2.3.2 OF THE CMS WORK PLAN.


COPPER CONCENTRATIONS IN GROUNDWATER AND POREWATER SAMPLES Former Rhone-Poulenc Site Tukwila, Washington

By: APS Date: 08/27/14 Project No. 08769




Figure 3-21


PLOT TIME: 3/16/2021 5:39 PM MOD TIME: 3/16/2021 5:38 PM USER: Kelley Bagley DWG: P:\Container Properties\CAD\Figures\2021-03\2021-03 Container Props Rhone-Poulenc Recent SVOC Data-2015-Present.dwg



PLOT TIME: 3/17/2021 9:52 AM MOD TIME: 3/17/2021 9:51 AM USER: Kelley Begley DWG: P:\Container Properties\CAD\Figures\2021-03\2021-03 Container Props Rhone-Poulenc Recent Toluene Data-2015-Present.dwg



PLOT TIME: 3/17/2021 9:48 AM MOD TIME: 3/17/2021 9:38 AM USER: Kelley Begley DWG: P:\Container Properties\CAD\Figures\2021-03\2021-03 Container Props Rhone-Poulenc Recent Copper Data-2015-Present.dwg



Attachment 2

List of Hazardous Constituents and Maximum Concentrations
(provided by EPA)

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1a: Water

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|-------------|------------------------|--|----------------------------|----------------------|---|---------------|---|---|--|---|--|
| 1 | | | | Groundwater to Protect Drinking Water* | | | | | | Groundwater to Protect Surface Water - Aquatic Life* | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER | CAS # | Chemical Data Group | MCL (µg/L) | Tap Water RSL (µg/L) | Tap Water RSL Key | Lowest of Groundwater to Protect Drinking Water Values (columns D-E) (µg/L) | Rationale | | Aquatic Life Fresh/Chronic CWA §304 (EPA AWQC) (µg/L) | Aquatic Life Marine/Chronic CWA §304 (EPA AWQC) (µg/L) | Aquatic Life Fresh/Chronic 173-201A WAC (WA State WQS) (µg/L) | Aquatic Life Marine/Chronic 173-201A WAC (WA State WQS) (µg/L) |
| 3 | acenaphthene | 83-32-9 | PAHs | | 5.3E+02 | noncancer | 5.3E+02 | RSL noncancer | | | | | |
| 4 | acenaphthylene | 208-96-8 | PAHs | | | | | | | | | | |
| 5 | acetone | 67-64-1 | VOCs | | 1.4E+04 | noncancer | 1.4E+04 | RSL noncancer | | | | | |
| 6 | aldrin (see notes re: aldrin and dieldrin) | 309-00-2 | Pesticides | | 9.2E-04 | cancer | 9.2E-04 | RSL cancer | | | | 1.9E-03 | 1.9E-03 |
| 7 | aluminum | 7429-90-5 | Metals | | 2.0E+04 | noncancer | 2.0E+04 | RSL noncancer | | | | | |
| 8 | anthracene | 120-12-7 | PAHs | | 1.8E+03 | noncancer | 1.8E+03 | RSL noncancer | | | | | |
| 9 | antimony (metallic) | 7440-36-0 | Metals | 6.0E+00 | 7.8E+00 | noncancer | 6.0E+00 | MCL | | | | | |
| 10 | aroclor 1254 | 11097-69-1 | PCBs | | 7.8E-03 | cancer | 7.8E-03 | RSL cancer | | | | | |
| 11 | aroclor 1260 | 11096-82-5 | PCBs | | 7.8E-03 | cancer | 7.8E-03 | RSL cancer | | | | | |
| 12 | arsenic, inorganic | 7440-38-2 | Metals | 1.0E+01 | 5.2E-02 | cancer | 5.2E-02 | RSL cancer | | 1.5E+02 | 3.6E+01 | 1.9E+02 | 3.6E+01 |
| 13 | barium and compounds | 7440-39-3 | Metals | 2.0E+03 | 3.8E+03 | noncancer | 2.0E+03 | MCL | | | | | |
| 14 | benzene | 71-43-2 | VOCs | 5.0E+00 | 4.6E-01 | cancer | 4.6E-01 | RSL cancer | | | | | |
| 15 | benzo[a]anthracene | 56-55-3 | cPAHs | | 3.0E-02 | cancer | 3.0E-02 | RSL cancer | | | | | |
| 16 | benzo[a]pyrene | 50-32-8 | cPAHs | 2.0E-01 | 2.5E-02 | cancer | 2.5E-02 | RSL cancer | | | | | |
| 17 | benzo[b]fluoranthene | 205-99-2 | cPAHs | | 2.5E-01 | cancer | 2.5E-01 | RSL cancer | | | | | |
| 18 | benzo[g,h,i]perylene | 191-24-2 | PAHs | | | | | | | | | | |
| 19 | benzo[k]fluoranthene | 207-08-9 | cPAHs | | 2.5E+00 | cancer | 2.5E+00 | RSL cancer | | | | | |
| 20 | benzoic acid | 65-85-0 | SVOCs | | 7.5E+04 | noncancer | 7.5E+04 | RSL noncancer | | | | | |
| 21 | benzyl alcohol | 100-51-6 | SVOCs | | 2.0E+03 | noncancer | 2.0E+03 | RSL noncancer | | | | | |
| 22 | beryllium | 7440-41-7 | Metals | 4.0E+00 | 2.5E+01 | noncancer | 4.0E+00 | MCL | | | | | |
| 23 | bis(2-ethylhexyl)-phthalate | 117-81-7 | Phthalates | 6.0E+00 | 5.6E+00 | cancer | 5.6E+00 | RSL cancer | | | | | |
| 24 | bromoform | 75-25-2 | VOCs | 8.0E+01 | 3.3E+00 | cancer | 3.3E+00 | RSL cancer | | | | | |
| 25 | butyl benzyl phthalate | 85-68-7 | Phthalates | | 1.6E+01 | cancer | 1.6E+01 | RSL cancer | | | | | |
| 26 | butylbenzene; sec- | 135-98-8 | VOCs | | 2.0E+03 | noncancer | 8.0E+02 | RSL noncancer | | | | | |
| 27 | cadmium (food/diet) | 7440-43-9 | Metals | | | | | | | | 7.9E+00 | | 9.3E+00 |
| 28 | cadmium (water) (see notes re: hardness) | 7440-43-9 | Metals | 5.0E+00 | 9.2E+00 | noncancer | 5.0E+00 | MCL | | 2.1E+00 | 7.9E+00 | 2.9E+00 | 9.3E+00 |
| 29 | calcium | 203863-17-6 | Metals | | | | | | | | | | |
| 30 | carbazole | 86-74-8 | PAHs | | | | | | | | | | |
| 31 | carbon disulfide | 75-15-0 | VOCs | | 8.1E+02 | noncancer | 8.1E+02 | RSL noncancer | | | | | |
| 32 | chlordane (technical) | 12789-03-6 | Pesticides | 2.0E+00 | 2.0E-02 | cancer | 2.0E-02 | RSL cancer | | 4.3E-03 | 4.0E-03 | | |
| 33 | chlordane | 57-74-9 | Pesticides | | | | | | | | | 4.3E-03 | 4.0E-03 |
| 34 | chromium (III), insoluble salts (see notes re: hardness) | 16065-83-1 | Metals | | 2.2E+04 | noncancer | 2.2E+04 | RSL noncancer | | 2.3E+02 | | 5.5E+02 | |
| 35 | chromium (total) | 7440-47-3 | Metals | 1.0E+02 | | | 1.0E+02 | MCL | | | | | |
| 36 | chromium (VI) | 18540-29-9 | Metals | | 3.5E-02 | cancer | 3.5E-02 | RSL cancer | | 1.1E+01 | 5.0E+01 | 1.0E+01 | 5.0E+01 |
| 37 | chrysene | 218-01-9 | cPAHs | | 2.5E+01 | cancer | 2.5E+01 | RSL cancer | | | | | |
| 38 | cobalt | 7440-48-4 | Metals | | 6.0E+00 | cancer | 6.0E+00 | RSL cancer | | | | | |
| 39 | copper (see notes re: hardness) | 7440-50-8 | Metals | 1.3E+03 | 8.0E+02 | noncancer | 8.0E+02 | RSL noncancer | | 2.9E+01 | 3.1E+00 | 3.7E+01 | 3.1E+00 |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1a: Water

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|------------|------------------------|--|----------------------------|----------------------|---|------------------|---|---|--|---|--|
| 1 | | | | Groundwater to Protect Drinking Water* | | | | | | Groundwater to Protect Surface Water - Aquatic Life* | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER | CAS # | Chemical Data Group | MCL (µg/L) | Tap Water RSL (µg/L) | Tap Water RSL Key | Lowest of Groundwater to Protect Drinking Water Values (columns D-E) (µg/L) | Rationale | | Aquatic Life Fresh/Chronic CWA §304 (EPA AWQC) (µg/L) | Aquatic Life Marine/Chronic CWA §304 (EPA AWQC) (µg/L) | Aquatic Life Fresh/Chronic 173-201A WAC (WA State WQS) (µg/L) | Aquatic Life Marine/Chronic 173-201A WAC (WA State WQS) (µg/L) |
| 40 | DDD, 4,4'- | 72-54-8 | Pesticides | | 3.2E-02 | cancer | 3.2E-02 | RSL cancer | | | | | |
| 41 | DDE, 4,4'- | 72-55-9 | Pesticides | | 4.6E-02 | cancer | 4.6E-02 | RSL cancer | | | | | |
| 42 | DDT, 4,4'- | 50-29-3 | Pesticides | | 2.3E-01 | cancer | 2.3E-01 | RSL cancer | | 1.0E-03 | 1.0E-03 | 1.0E-03 | 1.0E-03 |
| 43 | dibenz[a,h]anthracene | 53-70-3 | cPAHs | | 2.5E-02 | cancer | 2.5E-02 | RSL cancer | | | | | |
| 44 | dibenzofuran | 132-64-9 | PAHs | | 7.9E+00 | noncancer | 7.9E+00 | RSL noncancer | | | | | |
| 45 | dichlorobenzene; 1,2- | 95-50-1 | VOCs | 6.0E+02 | 3.0E+02 | noncancer | 3.0E+02 | RSL noncancer | | | | | |
| 46 | dichlorobenzene; 1,4- | 106-46-7 | VOCs | 7.5E+01 | 4.8E-01 | cancer | 4.8E-01 | RSL cancer | | | | | |
| 47 | dichloroethylene; 1,2-,cis | 156-59-2 | VOCs | 7.0E+01 | 3.6E+01 | noncancer | 3.6E+01 | RSL noncancer | | | | | |
| 48 | dieldrin (see notes re: aldrin and dieldrin) | 60-57-1 | Pesticides | | 1.8E-03 | cancer | 1.8E-03 | RSL cancer | | 5.6E-02 | 1.9E-03 | 1.9E-03 | 1.9E-03 |
| 49 | diethyl phthalate | 84-66-2 | Phthalates | | 1.5E+04 | noncancer | 1.5E+04 | RSL noncancer | | | | | |
| 50 | dimethylphenol; 2,4- | 105-67-9 | Phenols | | 3.6E+02 | noncancer | 3.6E+02 | RSL noncancer | | | | | |
| 51 | dimethyl phthalate | 131-11-3 | Phthalates | | | | | | | | | | |
| 52 | di-n-butyl-phthalate (dibutyl phthalate) | 84-74-2 | Phthalates | | 9.0E+02 | noncancer | 9.0E+02 | RSL noncancer | | | | | |
| 53 | di-n-octyl phthalate | 117-84-0 | Phthalates | | 2.0E+02 | noncancer | 2.0E+02 | RSL noncancer | | | | | |
| 54 | endosulfan | 115-29-7 | Pesticides | | 1.0E+02 | noncancer | 1.0E+02 | RSL noncancer | | | | 5.6E-02 | 8.7E-03 |
| 55 | endosulfan I (alpha) | 959-98-8 | Pesticides | | | | | | | 5.6E-02 | 8.7E-03 | | |
| 56 | endosulfan II (beta) | 33213-65-9 | Pesticides | | | | | | | 5.6E-02 | 8.7E-03 | | |
| 57 | endosulfan sulfate | 1031-07-8 | Pesticides | | 1.1E+02 | noncancer | 1.1E+02 | RSL noncancer | | | | | |
| 58 | endrin | 72-20-8 | Pesticides | 2.0E+00 | 2.3E+00 | noncancer | 2.0E+00 | MCL | | 3.6E-02 | 2.3E-03 | 2.3E-03 | 2.3E-03 |
| 59 | endrin aldehyde | 7421-93-4 | Pesticides | | | | | | | | | | |
| 60 | endrin ketone | 53494-70-5 | Pesticides | | | | | | | | | | |
| 61 | ethylbenzene | 100-41-4 | VOCs | 7.0E+02 | 1.5E+00 | cancer | 1.5E+00 | RSL cancer | | | | | |
| 62 | fluoranthene | 206-44-0 | PAHs | | 8.0E+02 | noncancer | 8.0E+02 | RSL noncancer | | | | | |
| 63 | fluorene | 86-73-7 | PAHs | | 2.9E+02 | noncancer | 2.9E+02 | RSL noncancer | | | | | |
| 64 | formaldehyde | 50-00-0 | VOCs | | 3.9E-01 | cancer | 3.9E-01 | RSL cancer | | | | | |
| 65 | hexachlorobenzene | 118-74-1 | Pesticides | 1.0E+00 | 9.8E-03 | cancer | 9.8E-03 | RSL cancer | | | | | |
| 66 | hexachlorocyclohexane, delta- (delta-BHC) | 319-86-8 | Pesticides | | | | | | | | | | |
| 67 | indeno[1,2,3-cd]pyrene | 193-39-5 | cPAHs | | 2.5E-01 | cancer | 2.5E-01 | RSL cancer | | | | | |
| 68 | iron | 7439-89-6 | Metals | | 1.4E+04 | noncancer | 1.4E+04 | RSL noncancer | | 1.0E+03 | | | |
| 69 | isopropyltoluene, 4- (cymene, p-) | 99-87-6 | VOCs | | | | | | | | | | |
| 70 | lead (see notes re: hardness) | 7439-92-1 | Metals | 1.5E+01 | 1.5E+01 | EPA action level | 1.5E+01 | EPA action level | | 1.1E+01 | 8.1E+00 | 1.1E+01 | 8.1E+00 |
| 71 | magnesium | 7439-95-4 | Metals | | | | | | | | | | |
| 72 | manganese (diet) | 7439-96-5 | Metals | | | | | | | | | | |
| 73 | manganese (non-diet) | 7439-96-5 | Metals | | 4.3E+02 | noncancer | 4.3E+02 | RSL noncancer | | | | | |
| 74 | mercury (elemental) | 7439-97-6 | Metals | 2.0E+00 | 6.3E-01 | noncancer | 6.3E-01 | RSL noncancer | | 7.7E-01 | 9.4E-01 | 1.2E-02 | 2.5E-02 |
| 75 | methoxychlor | 72-43-5 | Pesticides | 4.0E+01 | 3.7E+01 | noncancer | 3.7E+01 | RSL noncancer | | 3.0E-02 | 3.0E-02 | | |
| 76 | methyl ethyl ketone (butanone, 2-) | 78-93-3 | VOCs | | 5.6E+03 | noncancer | 5.6E+03 | RSL noncancer | | | | | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1a: Water

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|-----|---|------------|------------------------|--|----------------------------|----------------------|---|---------------|---|---|--|---|--|
| 1 | | | | Groundwater to Protect Drinking Water* | | | | | | Groundwater to Protect Surface Water - Aquatic Life* | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER | CAS # | Chemical Data Group | MCL (µg/L) | Tap Water RSL (µg/L) | Tap Water RSL Key | Lowest of Groundwater to Protect Drinking Water Values (columns D-E) (µg/L) | Rationale | | Aquatic Life Fresh/Chronic CWA §304 (EPA AWQC) (µg/L) | Aquatic Life Marine/Chronic CWA §304 (EPA AWQC) (µg/L) | Aquatic Life Fresh/Chronic 173-201A WAC (WA State WQS) (µg/L) | Aquatic Life Marine/Chronic 173-201A WAC (WA State WQS) (µg/L) |
| 77 | methyl naphthalene; 2- | 91-57-6 | PAHs | | 3.6E+01 | noncancer | 3.6E+01 | RSL noncancer | | | | | |
| 78 | methylene chloride | 75-09-2 | VOCs | 5.0E+00 | 1.1E+01 | cancer | 5.0E+00 | MCL | | | | | |
| 79 | methylphenol, 2- (cresol, o-) | 95-48-7 | Phenols | | 9.3E+02 | noncancer | 9.3E+02 | RSL noncancer | | | | | |
| 80 | methylphenol, 4- (cresol, p-) | 106-44-5 | Phenols | | 1.9E+03 | noncancer | 1.9E+03 | RSL noncancer | | | | | |
| 81 | naphthalene | 91-20-3 | PAHs | | 1.2E-01 | cancer | 1.2E-01 | RSL cancer | | | | | |
| 82 | nickel (soluble salts) (see notes re: hardness) | 7440-02-0 | Metals | | 3.9E+02 | noncancer | 3.9E+02 | RSL noncancer | | 1.7E+02 | 8.2E+00 | 5.1E+02 | 8.2E+00 |
| 83 | nitrosodiphenylamine, N- | 86-30-6 | SVOCs | | 1.2E+01 | cancer | 1.2E+01 | RSL cancer | | | | | |
| 84 | pentachlorophenol | 87-86-5 | SVOCs | 1.0E+00 | 4.1E-02 | cancer | 4.1E-02 | RSL cancer | | 1.5E+01 | 7.9E+00 | | 7.9E+00 |
| 85 | pH | | pH | | | | | | | 6.5-9 | 6.5-8.5 | | |
| 86 | phenanthrene | 85-01-8 | PAHs | | | | | | | | | | |
| 87 | phenol | 108-95-2 | Phenols | | 5.8E+03 | noncancer | 5.8E+03 | RSL noncancer | | | | | |
| 88 | phenylenediamine, 1,4- (phenylenediamine, p-) | 106-50-3 | SVOCs | | 2.0E+01 | noncancer | 2.0E+01 | RSL noncancer | | | | | |
| 89 | polychlorinated biphenyls; total PCBs | 1336-36-3 | PCBs | 5.0E-01 | 4.4E-02 | cancer | 4.4E-02 | RSL cancer | | 1.4E-02 | 3.0E-02 | 1.4E-02 | 3.0E-02 |
| 90 | potassium | 7440-09-7 | Metals | | | | | | | | | | |
| 91 | propanol, 2- (isopropanol) | 67-63-0 | VOCs | | 4.1E+02 | cancer | 4.1E+02 | RSL cancer | | | | | |
| 92 | pyrene | 129-00-0 | PAHs | | 1.2E+02 | noncancer | 1.2E+02 | RSL noncancer | | | | | |
| 93 | selenium and compounds | 7782-49-2 | Metals | 5.0E+01 | 1.0E+02 | noncancer | 5.0E+01 | MCL | | | 7.1E+01 | 5.0E+00 | 7.1E+01 |
| 94 | silver | 7440-22-4 | Metals | | 9.4E+01 | noncancer | 9.4E+01 | RSL noncancer | | | | | |
| 95 | sodium | 82115-62-6 | Metals | | | | | | | | | | |
| 96 | tetrachloroethylene | 127-18-4 | VOCs | 5.0E+00 | 1.1E+01 | cancer | 5.0E+00 | MCL | | | | | |
| 97 | tin | 7440-31-5 | Metals | | 1.2E+04 | noncancer | 1.2E+04 | RSL noncancer | | | | | |
| 98 | toluene | 108-88-3 | VOCs | 1.0E+03 | 1.1E+03 | noncancer | 1.0E+03 | MCL | | | | | |
| 99 | total petroleum hydrocarbons (aliphatic high) | E1790670 | TPH | | 6.0E+04 | noncancer | 6.0E+04 | RSL noncancer | | | | | |
| 100 | total petroleum hydrocarbons (aliphatic low) | E1790666 | TPH | | 1.3E+03 | noncancer | 1.3E+03 | RSL noncancer | | | | | |
| 101 | total petroleum hydrocarbons (aliphatic medium) | E1790668 | TPH | | 1.0E+02 | noncancer | 1.0E+02 | RSL noncancer | | | | | |
| 102 | total petroleum hydrocarbons (aromatic high) | E1790676 | TPH | | 8.0E+02 | noncancer | 8.0E+02 | RSL noncancer | | | | | |
| 103 | total petroleum hydrocarbons (aromatic low) | E1790672 | TPH | | 3.3E+01 | noncancer | 3.3E+01 | RSL noncancer | | | | | |
| 104 | total petroleum hydrocarbons (aromatic medium) | E1790674 | TPH | | 5.5E+00 | noncancer | 5.5E+00 | RSL noncancer | | | | | |
| 105 | trichlorobenzene, 1,2,4- | 120-82-1 | VOCs | 7.0E+01 | 1.2E+00 | cancer | 1.2E+00 | RSL cancer | | | | | |
| 106 | trichloroethylene (see notes) | 79-01-6 | VOCs | 5.0E+00 | 4.9E-01 | cancer | 4.9E-01 | RSL cancer | | | | | |
| 107 | trichlorophenol, 2,4,5- | 95-95-4 | Phenols | | 1.2E+03 | noncancer | 1.2E+03 | RSL noncancer | | | | | |
| 108 | trimethylbenzene; 1,2,4- | 95-63-6 | VOCs | | 5.6E+01 | noncancer | 5.6E+01 | RSL noncancer | | | | | |
| 109 | trimethylbenzene; 1,3,5- | 108-67-8 | VOCs | | 6.0E+01 | noncancer | 6.0E+01 | RSL noncancer | | | | | |
| 110 | vanadium and compounds | 7440-62-2 | Metals | | 8.6E+01 | noncancer | 8.6E+01 | RSL noncancer | | | | | |
| 111 | vanillin (4-hydroxy-3-methoxybenzaldehyde) | 121-33-5 | SVOCs | | | | | | | | | | |
| 112 | xylene; m- | 108-38-3 | VOCs | | 1.9E+02 | noncancer | 1.9E+02 | RSL noncancer | | | | | |
| 113 | xylene; o- | 95-47-6 | VOCs | | 1.9E+02 | noncancer | 1.9E+02 | RSL noncancer | | | | | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1a: Water

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|-----|---|-----------|------------------------|--|----------------------------|----------------------|---|---------------|---|---|--|---|--|
| 1 | | | | Groundwater to Protect Drinking Water* | | | | | | Groundwater to Protect Surface Water - Aquatic Life* | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER | CAS # | Chemical Data Group | MCL (µg/L) | Tap Water RSL (µg/L) | Tap Water RSL Key | Lowest of Groundwater to Protect Drinking Water Values (columns D-E) (µg/L) | Rationale | | Aquatic Life Fresh/Chronic CWA §304 (EPA AWQC) (µg/L) | Aquatic Life Marine/Chronic CWA §304 (EPA AWQC) (µg/L) | Aquatic Life Fresh/Chronic 173-201A WAC (WA State WQS) (µg/L) | Aquatic Life Marine/Chronic 173-201A WAC (WA State WQS) (µg/L) |
| 114 | xylene; p- | 106-42-3 | VOCs | | 1.9E+02 | noncancer | 1.9E+02 | RSL noncancer | | | | | |
| 115 | xlenes (total) | 1330-20-7 | VOCs | 1.0E+04 | 1.9E+02 | noncancer | 1.9E+02 | RSL noncancer | | | | | |
| 116 | zinc and compounds (see notes re: hardness) | 7440-66-6 | Metals | | 6.0E+03 | noncancer | 6.0E+03 | RSL noncancer | | 3.8E+02 | 8.1E+01 | 3.4E+02 | 8.1E+01 |
| 117 | | | | | | | | | | | | | |
| 118 | * - Groundwater to Protect Drinking Water values apply throughout the Facility and plume. Groundwater to Protect Surface Water and Sediment values apply at the monitoring well network located along the LDW and Slip 6. | | | | | | | | | | | | |
| 119 | Blank cells indicate a value is not available | | | | | | | | | | | | |
| 120 | ug/L - microgram per liter | | | | | | | | | | | | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1a: Water

| | A | B | C | N | O | P | Q | R | S | T | U |
|----|---|-------------|------------------------|---|---|--|------------------------------|---|--|--|------------------------------|
| 1 | | | | Groundwater to Protect Surface Water - Human Health Consumption of Organism Only* | | Groundwater to Protect Surface Water - Tribal Fish and Shellfish Consumption* | | Groundwater to Protect Sediment* | | Groundwater to Protect Surface Water and Sediment* | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER | CAS # | Chemical Data Group | Human Health (Organism Only) CWA §304 (EPA AWQC) (µg/L) | Human Health (Organism Only) 173-201A WAC (WA State WQS) (µg/L) | Lowest of Tribal Fish Consumption Values (from spreadsheet 1b) (µg/L) | Rationale | LDW PCUL GW-3 Groundwater to Protect Sediment (µg/L) | LDW Background (µg/L) (see notes) | Lowest of Surface Water Values (columns J-R or column S if higher) (µg/L) | Rationale |
| 3 | acenaphthene | 83-32-9 | PAHs | 9.0E+01 | 1.1E+02 | 1.1E+02 | Tribal consumption-noncancer | 5.3E+00 | | 5.3E+00 | LDW PCUL |
| 4 | acenaphthylene | 208-96-8 | PAHs | | | | | | | | |
| 5 | acetone | 67-64-1 | VOCs | | | 1.1E+05 | Tribal consumption-noncancer | | | 1.1E+05 | Tribal consumption-noncancer |
| 6 | aldrin (see notes re: aldrin and dieldrin) | 309-00-2 | Pesticides | 7.7E-07 | 5.8E-06 | 1.3E-05 | Tribal consumption-cancer | 1.1E-04 | | 7.7E-07 | EPA HH AWQC |
| 7 | aluminum | 7429-90-5 | Metals | | | | | | | | |
| 8 | anthracene | 120-12-7 | PAHs | 4.0E+02 | 4.6E+03 | 2.0E+02 | Tribal consumption-noncancer | 2.1E+00 | | 2.1E+00 | LDW PCUL |
| 9 | antimony (metallic) | 7440-36-0 | Metals | 6.4E+02 | 1.8E+02 | 3.8E+00 | Tribal consumption-noncancer | | | 3.8E+00 | Tribal consumption-noncancer |
| 10 | aroclor 1254 | 11097-69-1 | PCBs | | | 4.5E-06 | Tribal consumption-cancer | | | 4.5E-06 | Tribal consumption-cancer |
| 11 | aroclor 1260 | 11096-82-5 | PCBs | | | 4.5E-06 | Tribal consumption-cancer | | | 4.5E-06 | Tribal consumption-cancer |
| 12 | arsenic, inorganic | 7440-38-2 | Metals | 1.4E-01 | | 4.4E-03 | Tribal consumption-cancer | 2.2E+02 | 8.0E+00 | 8.0E+00 | LDW Background |
| 13 | barium and compounds | 7440-39-3 | Metals | | | 7.7E+02 | Tribal consumption-noncancer | 9.3E+05 | | 7.7E+02 | Tribal consumption-noncancer |
| 14 | benzene | 71-43-2 | VOCs | 1.6E+01 | 1.6E+00 | 1.7E+00 | Tribal consumption-cancer | | | 1.6E+00 | WA State HH WQS |
| 15 | benzo[a]anthracene | 56-55-3 | cPAHs | 1.3E-03 | 2.1E-02 | 7.8E-04 | Tribal consumption-cancer | 1.9E-01 | | 7.8E-04 | Tribal consumption-cancer |
| 16 | benzo[a]pyrene | 50-32-8 | cPAHs | 1.3E-04 | 2.1E-03 | 4.6E-05 | Tribal consumption-cancer | 8.7E-02 | | 4.6E-05 | Tribal consumption-cancer |
| 17 | benzo[b]fluoranthene | 205-99-2 | cPAHs | 1.3E-03 | 2.1E-02 | 3.7E-04 | Tribal consumption-cancer | | | 3.7E-04 | Tribal consumption-cancer |
| 18 | benzo[g,h,i]perylene | 191-24-2 | PAHs | | | | | | | | |
| 19 | benzo[k]fluoranthene | 207-08-9 | cPAHs | 1.3E-02 | 2.1E-01 | 3.8E-03 | Tribal consumption-cancer | | | 3.8E-03 | Tribal consumption-cancer |
| 20 | benzoic acid | 65-85-0 | SVOCs | | | 4.9E+05 | Tribal consumption-noncancer | 5.9E+02 | | 5.9E+02 | LDW PCUL |
| 21 | benzyl alcohol | 100-51-6 | SVOCs | | | 1.2E+05 | Tribal consumption-noncancer | | | 1.2E+05 | Tribal consumption-noncancer |
| 22 | beryllium | 7440-41-7 | Metals | | | 1.2E+01 | Tribal consumption-noncancer | 4.9E+00 | | 4.9E+00 | LDW PCUL |
| 23 | bis(2-ethylhexyl)-phthalate | 117-81-7 | Phthalates | 3.7E-01 | 2.5E-01 | 1.0E+00 | Tribal consumption-cancer | 6.2E-01 | | 2.5E-01 | WA State HH WQS |
| 24 | bromoform | 75-25-2 | VOCs | 1.2E+02 | 2.7E+01 | 7.2E+00 | Tribal consumption-cancer | | | 7.2E+00 | Tribal consumption-cancer |
| 25 | butyl benzyl phthalate | 85-68-7 | Phthalates | 1.0E-01 | 5.8E-01 | 3.4E-01 | Tribal consumption-cancer | 2.4E-01 | | 1.0E-01 | EPA HH AWQC |
| 26 | butylbenzene; sec- | 135-98-8 | VOCs | | | | | | | | |
| 27 | cadmium (food/diet) | 7440-43-9 | Metals | | | 4.2E-01 | Tribal consumption-noncancer | 1.2E+00 | | 4.2E-01 | Tribal consumption-noncancer |
| 28 | cadmium (water) (see notes re: hardness) | 7440-43-9 | Metals | | | 2.1E-01 | Tribal consumption-noncancer | | | 2.1E-01 | Tribal consumption-noncancer |
| 29 | calcium | 203863-17-6 | Metals | | | | | | | | |
| 30 | carbazole | 86-74-8 | PAHs | | | | | | | | |
| 31 | carbon disulfide | 75-15-0 | VOCs | | | 3.9E+03 | Tribal consumption-noncancer | | | 3.9E+03 | Tribal consumption-noncancer |
| 32 | chlordane (technical) | 12789-03-6 | Pesticides | 3.2E-04 | | | | | | 3.2E-04 | EPA HH AWQC |
| 33 | chlordane | 57-74-9 | Pesticides | 3.2E-04 | 9.3E-05 | | | | | 9.3E-05 | WA State HH WQS |
| 34 | chromium (III), insoluble salts (see notes re: hardness) | 16065-83-1 | Metals | | | | | 8.5E+01 | | 8.5E+01 | LDW PCUL |
| 35 | chromium (total) | 7440-47-3 | Metals | | | | | | | | |
| 36 | chromium (VI) | 18540-29-9 | Metals | | | 4.8E-01 | Tribal consumption-cancer | 5.0E+04 | | 4.8E-01 | Tribal consumption-cancer |
| 37 | chrysene | 218-01-9 | cPAHs | 1.3E-01 | 2.1E+00 | 7.8E-02 | Tribal consumption-cancer | 1.9E-01 | | 7.8E-02 | Tribal consumption-cancer |
| 38 | cobalt | 7440-48-4 | Metals | | | | | | | | |
| 39 | copper (see notes re: hardness) | 7440-50-8 | Metals | | | 4.3E+02 | Tribal consumption-noncancer | 1.4E+01 | 8.0E+00 | 8.0E+00 | LDW Background |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1a: Water

| | A | B | C | N | O | P | Q | R | S | T | U |
|----|---|------------|------------------------|---|---|--|------------------------------|---|--|--|------------------------------|
| 1 | | | | Groundwater to Protect Surface Water - Human Health Consumption of Organism Only* | | Groundwater to Protect Surface Water - Tribal Fish and Shellfish Consumption* | | Groundwater to Protect Sediment* | | Groundwater to Protect Surface Water and Sediment* | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER | CAS # | Chemical Data Group | Human Health (Organism Only) CWA §304 (EPA AWQC) (µg/L) | Human Health (Organism Only) 173-201A WAC (WA State WQS) (µg/L) | Lowest of Tribal Fish Consumption Values (from spreadsheet 1b) (µg/L) | Rationale | LDW PCUL GW-3 Groundwater to Protect Sediment (µg/L) | LDW Background (µg/L) (see notes) | Lowest of Surface Water Values (columns J-R or column S if higher) (µg/L) | Rationale |
| 40 | DDD, 4,4'- | 72-54-8 | Pesticides | 1.2E-04 | 3.6E-05 | 3.8E-04 | Tribal consumption-cancer | 7.9E+00 | | 3.6E-05 | WA State HH WQS |
| 41 | DDE, 4,4'- | 72-55-9 | Pesticides | 1.8E-05 | 5.1E-05 | 4.6E-04 | Tribal consumption-cancer | 3.8E+00 | | 1.8E-05 | EPA HH AWQC |
| 42 | DDT, 4,4'- | 50-29-3 | Pesticides | 3.0E-05 | 2.5E-05 | 1.3E-04 | Tribal consumption-cancer | 7.8E-06 | | 7.8E-06 | LDW PCUL |
| 43 | dibenz[a,h]anthracene | 53-70-3 | cPAHs | 1.3E-04 | 2.1E-03 | 1.9E-05 | Tribal consumption-cancer | 6.8E-03 | | 1.9E-05 | Tribal consumption-cancer |
| 44 | dibenzofuran | 132-64-9 | PAHs | | | | | | | | |
| 45 | dichlorobenzene; 1,2- | 95-50-1 | VOCs | 3.0E+03 | 2.5E+03 | 4.3E+02 | Tribal consumption-noncancer | 4.6E+00 | | 4.6E+00 | LDW PCUL |
| 46 | dichlorobenzene; 1,4- | 106-46-7 | VOCs | 9.0E+02 | 5.8E+02 | 1.4E+00 | Tribal consumption-cancer | 8.9E+00 | | 1.4E+00 | Tribal consumption-cancer |
| 47 | dichloroethylene; 1,2-,cis | 156-59-2 | VOCs | | | 1.3E+02 | Tribal consumption-noncancer | | | 1.3E+02 | Tribal consumption-noncancer |
| 48 | dieldrin (see notes re: aldrin and dieldrin) | 60-57-1 | Pesticides | 1.2E-06 | 6.1E-06 | 8.1E-05 | Tribal consumption-cancer | 2.1E-04 | | 1.2E-06 | EPA HH AWQC |
| 49 | diethyl phthalate | 84-66-2 | Phthalates | 6.0E+02 | 5.0E+03 | 1.8E+04 | Tribal consumption-noncancer | 9.3E+01 | | 9.3E+01 | LDW PCUL |
| 50 | dimethylphenol; 2,4- | 105-67-9 | Phenols | 3.0E+03 | 9.7E+01 | 6.5E+02 | Tribal consumption-noncancer | 6.3E+00 | | 6.3E+00 | LDW PCUL |
| 51 | dimethyl phthalate | 131-11-3 | Phthalates | 2.0E+03 | 1.3E+05 | | | | | 2.0E+03 | EPA HH AWQC |
| 52 | di-n-butyl-phthalate (dibutyl phthalate) | 84-74-2 | Phthalates | 3.0E+01 | 5.1E+02 | 4.6E+01 | Tribal consumption-noncancer | 4.6E+01 | | 3.0E+01 | EPA HH AWQC |
| 53 | di-n-octyl phthalate | 117-84-0 | Phthalates | | | 6.1E+01 | Tribal consumption-noncancer | 3.9E-03 | | 3.9E-03 | LDW PCUL |
| 54 | endosulfan | 115-29-7 | Pesticides | | | 1.4E+01 | Tribal consumption-noncancer | | | 8.7E-03 | WA State Marine WQS |
| 55 | endosulfan I (alpha) | 959-98-8 | Pesticides | 3.0E+01 | | | | 3.0E+04 | | 8.7E-03 | EPA Marine AWQC |
| 56 | endosulfan II (beta) | 33213-65-9 | Pesticides | 4.0E+01 | | | | 3.0E+04 | | 8.7E-03 | EPA Marine AWQC |
| 57 | endosulfan sulfate | 1031-07-8 | Pesticides | 4.0E+01 | 1.0E+01 | | | | | 1.0E+01 | WA State HH WQS |
| 58 | endrin | 72-20-8 | Pesticides | 3.0E-02 | 3.5E-02 | 1.7E-01 | Tribal consumption-noncancer | 2.9E+02 | | 2.3E-03 | EPA Marine AWQC |
| 59 | endrin aldehyde | 7421-93-4 | Pesticides | 1.0E+00 | 3.5E-02 | | | | | 3.5E-02 | WA State HH WQS |
| 60 | endrin ketone | 53494-70-5 | Pesticides | | | | | | | | |
| 61 | ethylbenzene | 100-41-4 | VOCs | 1.3E+02 | 2.7E+02 | 1.4E+00 | Tribal consumption-cancer | | | 1.4E+00 | Tribal consumption-cancer |
| 62 | fluoranthene | 206-44-0 | PAHs | 2.0E+01 | 1.6E+01 | 1.1E+01 | Tribal consumption-noncancer | 1.8E+00 | | 1.8E+00 | LDW PCUL |
| 63 | fluorene | 86-73-7 | PAHs | 7.0E+01 | 6.1E+02 | 4.5E+01 | Tribal consumption-noncancer | 3.7E+00 | | 3.7E+00 | LDW PCUL |
| 64 | formaldehyde | 50-00-0 | VOCs | | | 1.1E+01 | Tribal consumption-cancer | | | 1.1E+01 | Tribal consumption-cancer |
| 65 | hexachlorobenzene | 118-74-1 | Pesticides | 7.9E-05 | 5.2E-05 | 2.0E-04 | Tribal consumption-cancer | 1.4E-02 | | 5.2E-05 | WA State HH WQS |
| 66 | hexachlorocyclohexane, delta- (delta-BHC) | 319-86-8 | Pesticides | | | | | | | | |
| 67 | indeno[1,2,3-cd]pyrene | 193-39-5 | cPAHs | 1.3E-03 | 2.1E-02 | 1.6E-04 | Tribal consumption-cancer | 9.1E-03 | | 1.6E-04 | Tribal consumption-cancer |
| 68 | iron | 7439-89-6 | Metals | | | | | | | 1.0E+03 | EPA FW AWQC |
| 69 | isopropyltoluene, 4- (cymene, p-) | 99-87-6 | VOCs | | | | | | | | |
| 70 | lead (see notes re: hardness) | 7439-92-1 | Metals | | | | | 1.9E+01 | | 8.1E+00 | EPA Marine AWQC |
| 71 | magnesium | 7439-95-4 | Metals | | | | | | | | |
| 72 | manganese (diet) | 7439-96-5 | Metals | 1.0E+02 | | | | | 2.0E+03 | 2.0E+03 | LDW Background |
| 73 | manganese (non-diet) | 7439-96-5 | Metals | | | | | | 2.0E+03 | | |
| 74 | mercury (elemental) | 7439-97-6 | Metals | | | | | 2.0E+00 | | 1.2E-02 | WA State FW WQS |
| 75 | methoxychlor | 72-43-5 | Pesticides | 2.0E-02 | | 1.9E+00 | Tribal consumption-noncancer | 6.6E+02 | | 2.0E-02 | EPA HH AWQC |
| 76 | methyl ethyl ketone (butanone, 2-) | 78-93-3 | VOCs | | | 7.3E+04 | Tribal consumption-noncancer | | | 7.3E+04 | Tribal consumption-noncancer |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1a: Water

| | A | B | C | N | O | P | Q | R | S | T | U |
|-----|---|------------|------------------------|---|---|--|------------------------------|---|--|--|------------------------------|
| 1 | | | | Groundwater to Protect Surface Water - Human Health Consumption of Organism Only* | | Groundwater to Protect Surface Water - Tribal Fish and Shellfish Consumption* | | Groundwater to Protect Sediment* | | Groundwater to Protect Surface Water and Sediment* | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER | CAS # | Chemical Data Group | Human Health (Organism Only) CWA §304 (EPA AWQC) (µg/L) | Human Health (Organism Only) 173-201A WAC (WA State WQS) (µg/L) | Lowest of Tribal Fish Consumption Values (from spreadsheet 1b) (µg/L) | Rationale | LDW PCUL GW-3 Groundwater to Protect Sediment (µg/L) | LDW Background (µg/L) (see notes) | Lowest of Surface Water Values (columns J-R or column S if higher) (µg/L) | Rationale |
| 77 | methyl naphthalene; 2- | 91-57-6 | PAHs | | | | | | | | |
| 78 | methylene chloride | 75-09-2 | VOCs | 1.0E+03 | 2.5E+02 | 1.9E+02 | Tribal consumption-cancer | | | 1.9E+02 | Tribal consumption-cancer |
| 79 | methylphenol, 2- (cresol, o-) | 95-48-7 | Phenols | | | 3.0E+03 | Tribal consumption-noncancer | 2.7E+01 | | 2.7E+01 | LDW PCUL |
| 80 | methylphenol, 4- (cresol, p-) | 106-44-5 | Phenols | | | 6.6E+03 | Tribal consumption-noncancer | | | 6.6E+03 | Tribal consumption-noncancer |
| 81 | naphthalene | 91-20-3 | PAHs | | | 9.1E-02 | Tribal consumption-cancer | 9.0E+01 | | 9.1E-02 | Tribal consumption-cancer |
| 82 | nickel (soluble salts) (see notes re: hardness) | 7440-02-0 | Metals | 4.6E+03 | 1.9E+02 | 9.9E+01 | Tribal consumption-noncancer | 2.6E+03 | | 8.2E+00 | EPA Marine AWQC |
| 83 | nitrosodiphenylamine, N- | 86-30-6 | SVOCs | | 6.9E-01 | 3.2E+00 | Tribal consumption-cancer | 1.1E+00 | | 6.9E-01 | WA State HH WQS |
| 84 | pentachlorophenol | 87-86-5 | SVOCs | 4.0E-02 | 1.0E-01 | 2.8E-03 | Tribal consumption-cancer | 8.8E-01 | | 2.8E-03 | Tribal consumption-cancer |
| 85 | pH | | pH | | | | | | | | |
| 86 | phenanthrene | 85-01-8 | PAHs | | | | | | | | |
| 87 | phenol | 108-95-2 | Phenols | 3.0E+05 | 2.0E+05 | 4.0E+04 | Tribal consumption-noncancer | 3.7E+02 | | 3.7E+02 | LDW PCUL |
| 88 | phenylenediamine, 1,4- (phenylenediamine, p-) | 106-50-3 | SVOCs | | | | | | | | |
| 89 | polychlorinated biphenyls; total PCBs | 1336-36-3 | PCBs | 6.4E-05 | 1.7E-04 | | | 2.2E-02 | | 6.4E-05 | EPA HH AWQC |
| 90 | potassium | 7440-09 7 | Metals | | | | | | | | |
| 91 | propanol, 2- (isopropanol) | 67-63-0 | VOCs | | | | | | | | |
| 92 | pyrene | 129-00-0 | PAHs | 3.0E+01 | 4.6E+02 | 9.8E+00 | Tribal consumption-noncancer | 2.0E+00 | | 2.0E+00 | LDW PCUL |
| 93 | selenium and compounds | 7782-49-2 | Metals | 4.2E+03 | 4.8E+02 | 1.5E+01 | Tribal consumption-noncancer | 4.3E+05 | | 5.0E+00 | WA State FW WQS |
| 94 | silver | 7440-22-4 | Metals | | | 2.2E+01 | Tribal consumption-noncancer | 5.5E+01 | | 2.2E+01 | Tribal consumption-noncancer |
| 95 | sodium | 82115-62-6 | Metals | | | | | | | | |
| 96 | tetrachloroethylene | 127-18-4 | VOCs | 2.9E+01 | 7.1E+00 | 4.4E+00 | Tribal consumption-cancer | | | 4.4E+00 | Tribal consumption-cancer |
| 97 | tin | 7440-31-5 | Metals | | | | | | | | |
| 98 | toluene | 108-88-3 | VOCs | 5.2E+02 | 4.1E+02 | 1.3E+03 | Tribal consumption-noncancer | | | 4.1E+02 | WA State HH WQS |
| 99 | total petroleum hydrocarbons (aliphatic high) | E1790670 | TPH | | | | | | | | |
| 100 | total petroleum hydrocarbons (aliphatic low) | E1790666 | TPH | | | | | | | | |
| 101 | total petroleum hydrocarbons (aliphatic medium) | E1790668 | TPH | | | | | | | | |
| 102 | total petroleum hydrocarbons (aromatic high) | E1790676 | TPH | | | | | | | | |
| 103 | total petroleum hydrocarbons (aromatic low) | E1790672 | TPH | | | | | | | | |
| 104 | total petroleum hydrocarbons (aromatic medium) | E1790674 | TPH | | | | | | | | |
| 105 | trichlorobenzene, 1,2,4- | 120-82-1 | VOCs | 7.6E-02 | 1.4E-01 | 1.1E-01 | Tribal consumption-cancer | 9.6E-01 | | 7.6E-02 | EPA HH AWQC |
| 106 | trichloroethylene (see notes) | 79-01-6 | VOCs | 7.0E+00 | 8.6E-01 | 1.2E+00 | Tribal consumption-cancer | | | 8.6E-01 | WA State HH WQS |
| 107 | trichlorophenol, 2,4,5- | 95-95-4 | Phenols | 6.0E+02 | | 6.6E+02 | Tribal consumption-noncancer | 6.7E+04 | | 6.0E+02 | EPA HH AWQC |
| 108 | trimethylbenzene; 1,2,4- | 95-63-6 | VOCs | | | | | | | | |
| 109 | trimethylbenzene; 1,3,5- | 108-67-8 | VOCs | | | 4.5E+01 | Tribal consumption-noncancer | | | 4.5E+01 | Tribal consumption-noncancer |
| 110 | vanadium and compounds | 7440-62-2 | Metals | | | | | | | | |
| 111 | vanillin (4-hydroxy-3-methoxybenzaldehyde) | 121-33-5 | SVOCs | | | | | | | | |
| 112 | xylene; m- | 108-38-3 | VOCs | | | 1.3E+03 | Tribal consumption-noncancer | | | 1.3E+03 | Tribal consumption-noncancer |
| 113 | xylene; o- | 95-47-6 | VOCs | | | 1.6E+03 | Tribal consumption-noncancer | | | 1.6E+03 | Tribal consumption-noncancer |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1a: Water

| | A | B | C | N | O | P | Q | R | S | T | U |
|-----|---|-----------|------------------------|---|---|--|------------------------------|---|--|--|------------------------------|
| 1 | | | | Groundwater to Protect Surface Water - Human Health Consumption of Organism Only* | | Groundwater to Protect Surface Water - Tribal Fish and Shellfish Consumption* | | Groundwater to Protect Sediment* | | Groundwater to Protect Surface Water and Sediment* | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER | CAS # | Chemical Data Group | Human Health (Organism Only) CWA §304 (EPA AWQC) (µg/L) | Human Health (Organism Only) 173-201A WAC (WA State WQS) (µg/L) | Lowest of Tribal Fish Consumption Values (from spreadsheet 1b) (µg/L) | Rationale | LDW PCUL GW-3 Groundwater to Protect Sediment (µg/L) | LDW Background (µg/L) (see notes) | Lowest of Surface Water Values (columns J-R or column S if higher) (µg/L) | Rationale |
| 114 | xylene; p- | 106-42-3 | VOCs | | | 1.6E+03 | Tribal consumption-noncancer | | | 1.6E+03 | Tribal consumption-noncancer |
| 115 | xlenes (total) | 1330-20-7 | VOCs | | | | | | | | |
| 116 | zinc and compounds (see notes re: hardness) | 7440-66-6 | Metals | 2.6E+04 | 2.9E+03 | 5.6E+01 | Tribal consumption-noncancer | 7.7E+02 | | 5.6E+01 | Tribal consumption-noncancer |
| 117 | | | | | | | | | | | |
| 118 | * - Groundwater to Protect Drinking Water values apply throughout the Facility and p | | | | | | | | | | |
| 119 | Blank cells indicate a value is not available | | | | | | | | | | |
| 120 | ug/L - microgram per liter | | | | | | | | | | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1b: Tribal Fish and Shellfish Calculations

| | A | B | C | D | E | F | G | H | I | J |
|----|--|--------------|--------------------------------|---|--|--|--|--|--|------------------------------|
| 1 | | | | | | | Groundwater to Protect Surface Water - Tribal Fish and Shellfish Consumption | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER TO PROTECT SURFACE WATER: TRIBAL FISH AND SHELLFISH CONSUMPTION | CAS # | Chemical Data Group | Bioconcentration Factor (BCF) fish fresh weight (L/kg FW) (see notes) | Oral Cancer Slope Factor (SFO) (mg/kg-day) ⁻¹ (see notes) | Oral Reference Dose (RfD _o) (mg/kg-day) (see notes) | EPA Tribal fish consumption, cancer (µg/L) | EPA Tribal fish consumption child, noncancer (µg/L) | Lowest of Tribal Fish and Shellfish Consumption values (columns G-H) (µg/L) | Rationale |
| 3 | acenaphthene | 83-32-9 | PAHs | 2.01E+02 | | 6.0E-02 | | 1.1E+02 | 1.1E+02 | Tribal consumption-noncancer |
| 4 | acenaphthylene | 208-96-8 | PAHs | not in HHRAP | | | | | | |
| 5 | acetone | 67-64-1 | VOCs | 3.16E+00 | | 9.0E-01 | | 1.1E+05 | 1.1E+05 | Tribal consumption-noncancer |
| 6 | aldrin (see notes re: aldrin and dieldrin) | 309-00-2 | Pesticides | 3.43E+03 | 1.7E+01 | 3.0E-05 | 1.3E-05 | 3.4E-03 | 1.3E-05 | Tribal consumption-cancer |
| 7 | aluminum | 7429-90-5 | Metals | not in HHRAP | | 1.0E+00 | | | | |
| 8 | anthracene | 120-12-7 | PAHs | 5.82E+02 | | 3.0E-01 | | 2.0E+02 | 2.0E+02 | Tribal consumption-noncancer |
| 9 | antimony (metallic) | 7440-36-0 | Metals | 4.00E+01 | | 4.0E-04 | | 3.8E+00 | 3.8E+00 | Tribal consumption-noncancer |
| 10 | aroclor 1254 | 11097-69-1 | PCBs | 8.41E+04 | 2.0E+00 | 2.0E-05 | 4.5E-06 | 9.1E-05 | 4.5E-06 | Tribal consumption-cancer |
| 11 | aroclor 1260 | 11096-82-5 | PCBs | 8.41E+04 | 2.0E+00 | | 4.5E-06 | | 4.5E-06 | Tribal consumption-cancer |
| 12 | arsenic, inorganic | 7440-38-2 | Metals | 1.14E+02 | 1.5E+00 | 3.0E-04 | 4.4E-03 | 1.0E+00 | 4.4E-03 | Tribal consumption-cancer |
| 13 | barium and compounds | 7440-39-3 | Metals | 1.00E+02 | | 2.0E-01 | | 7.7E+02 | 7.7E+02 | Tribal consumption-noncancer |
| 14 | benzene | 71-43-2 | VOCs | 8.26E+00 | 5.5E-02 | 4.0E-03 | 1.7E+00 | 1.9E+02 | 1.7E+00 | Tribal consumption-cancer |
| 15 | benzo[a]anthracene | 56-55-3 | cPAHs | 4.89E+03 | 1.0E-01 | | 7.8E-04 | | 7.8E-04 | Tribal consumption-cancer |
| 16 | benzo[a]pyrene | 50-32-8 | cPAHs | 8.32E+03 | 1.0E+00 | 3.0E-04 | 4.6E-05 | 1.4E-02 | 4.6E-05 | Tribal consumption-cancer |
| 17 | benzo[b]fluoranthene | 205-99-2 | cPAHs | 1.04E+04 | 1.0E-01 | | 3.7E-04 | | 3.7E-04 | Tribal consumption-cancer |
| 18 | benzo[g,h,i]perylene | 191-24-2 | PAHs | not in HHRAP | | | | | | |
| 19 | benzo[k]fluoranthene | 207-08-9 | cPAHs | 9.93E+03 | 1.0E-02 | | 3.8E-03 | | 3.8E-03 | Tribal consumption-cancer |
| 20 | benzoic acid | 65-85-0 | SVOCs | 3.16E+00 | | 4.0E+00 | | 4.9E+05 | 4.9E+05 | Tribal consumption-noncancer |
| 21 | benzyl alcohol | 100-51-6 | SVOCs | 3.14E-01 | | 1.0E-01 | | 1.2E+05 | 1.2E+05 | Tribal consumption-noncancer |
| 22 | beryllium | 7440-41-7 | Metals | 6.20E+01 | | 2.0E-03 | | 1.2E+01 | 1.2E+01 | Tribal consumption-noncancer |
| 23 | bis(2-ethylhexyl)-phthalate | 117-81-7 | Phthalates | 5.33E+01 | 1.4E-02 | 2.0E-02 | 1.0E+00 | 1.4E+02 | 1.0E+00 | Tribal consumption-cancer |
| 24 | bromoform | 75-25-2 | VOCs | 1.33E+01 | 7.9E-03 | 2.0E-02 | 7.2E+00 | 5.8E+02 | 7.2E+00 | Tribal consumption-cancer |
| 25 | butyl benzyl phthalate | 85-68-7 | Phthalates | 1.18E+03 | 1.9E-03 | 2.0E-01 | 3.4E-01 | 6.5E+01 | 3.4E-01 | Tribal consumption-cancer |
| 26 | butylbenzene; sec- | 135-98-8 | VOCs | not in HHRAP | | 1.0E-01 | | | | |
| 27 | cadmium (food/diet) | 7440-43-9 | Metals | 9.07E+02 | | 1.0E-03 | | 4.2E-01 | 4.2E-01 | Tribal consumption-noncancer |
| 28 | cadmium (water) (see notes re: hardness) | 7440-43-9 | Metals | 9.07E+02 | | 5.0E-04 | | 2.1E-01 | 2.1E-01 | Tribal consumption-noncancer |
| 29 | calcium | 203863-17-6 | Metals | not in HHRAP | | | | | | |
| 30 | carbazole | 86-74-8 | PAHs | not in HHRAP | | | | | | |
| 31 | carbon disulfide | 75-15-0 | VOCs | 9.86E+00 | | 1.0E-01 | | 3.9E+03 | 3.9E+03 | Tribal consumption-noncancer |
| 32 | chlordane (technical) | 12789-03-6 | Pesticides | not in HHRAP | 3.5E-01 | 5.0E-04 | | | | |
| 33 | chlordane | 57-74-9 | Pesticides | 3.43E+03 | | | | | | |
| 34 | chromium (III), insoluble salts (see notes re: hardness) | 16065-83-1 | Metals | not in HHRAP | | 1.5E+00 | | | | |
| 35 | chromium (total) | 7440-47-3 | Metals | 1.90E+01 | | | | | | |
| 36 | chromium (VI) | 18540-29-9 | Metals | 3.16E+00 | 5.0E-01 | 3.0E-03 | 4.8E-01 | 3.7E+02 | 4.8E-01 | Tribal consumption-cancer |
| 37 | chrysene | 218-01-9 | cPAHs | 4.89E+03 | 1.0E-03 | | 7.8E-02 | | 7.8E-02 | Tribal consumption-cancer |
| 38 | cobalt | 7440-48-4 | Metals | not in HHRAP | | 3.0E-04 | | | | |
| 39 | copper (see notes re: hardness) | 7440-50-8 | Metals | 3.60E+01 | | 4.0E-02 | | 4.3E+02 | 4.3E+02 | Tribal consumption-noncancer |
| 40 | DDD, 4,4'- | 72-54-8 | Pesticides | 8.32E+03 | 2.4E-01 | 3.0E-05 | 3.8E-04 | 1.4E-03 | 3.8E-04 | Tribal consumption-cancer |
| 41 | DDE, 4,4'- | 72-55-9 | Pesticides | 4.89E+03 | 3.4E-01 | 3.0E-04 | 4.6E-04 | 2.4E-02 | 4.6E-04 | Tribal consumption-cancer |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1b: Tribal Fish and Shellfish Calculations

| | A | B | C | D | E | F | G | H | I | J |
|----|--|--------------|--------------------------------|---|--|--|--|--|--|------------------------------|
| 1 | | | | | | | Groundwater to Protect Surface Water - Tribal Fish and Shellfish Consumption | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER TO PROTECT SURFACE WATER: TRIBAL FISH AND SHELLFISH CONSUMPTION | CAS # | Chemical Data Group | Bioconcentration Factor (BCF) fish fresh weight (L/kg FW) (see notes) | Oral Cancer Slope Factor (SFO) (mg/kg-day) ⁻¹ (see notes) | Oral Reference Dose (RfD _o) (mg/kg-day) (see notes) | EPA Tribal fish consumption, cancer (µg/L) | EPA Tribal fish consumption child, noncancer (µg/L) | Lowest of Tribal Fish and Shellfish Consumption values (columns G-H) (µg/L) | Rationale |
| 42 | DDT, 4,4'- | 50-29-3 | Pesticides | 1.69E+04 | 3.4E-01 | 5.0E-04 | 1.3E-04 | 1.1E-02 | 1.3E-04 | Tribal consumption-cancer |
| 43 | dibenz[a,h]anthracene | 53-70-3 | cPAHs | 2.02E+04 | 1.0E+00 | | 1.9E-05 | | 1.9E-05 | Tribal consumption-cancer |
| 44 | dibenzofuran | 132-64-9 | PAHs | not in HHRAP | | 1.0E-03 | | | | |
| 45 | dichlorobenzene; 1,2- | 95-50-1 | VOCs | 7.99E+01 | | 9.0E-02 | | 4.3E+02 | 4.3E+02 | Tribal consumption-noncancer |
| 46 | dichlorobenzene; 1,4- | 106-46-7 | VOCs | 9.89E+01 | 5.4E-03 | 7.0E-02 | 1.4E+00 | 2.7E+02 | 1.4E+00 | Tribal consumption-cancer |
| 47 | dichloroethylene; 1,2-,cis | 156-59-2 | VOCs | 5.79E+00 | | 2.0E-03 | | 1.3E+02 | 1.3E+02 | Tribal consumption-noncancer |
| 48 | dieldrin (see notes re: aldrin and dieldrin) | 60-57-1 | Pesticides | 5.82E+02 | 1.6E+01 | 5.0E-05 | 8.1E-05 | 3.3E-02 | 8.1E-05 | Tribal consumption-cancer |
| 49 | diethyl phthalate | 84-66-2 | Phthalates | 1.68E+01 | | 8.0E-01 | | 1.8E+04 | 1.8E+04 | Tribal consumption-noncancer |
| 50 | dimethylphenol; 2,4- | 105-67-9 | Phenols | 1.18E+01 | | 2.0E-02 | | 6.5E+02 | 6.5E+02 | Tribal consumption-noncancer |
| 51 | dimethyl phthalate | 131-11-3 | Phthalates | 3.17E+00 | | | | | | |
| 52 | di-n-butyl-phthalate (dibutyl phthalate) | 84-74-2 | Phthalates | 8.30E+02 | | 1.0E-01 | | 4.6E+01 | 4.6E+01 | Tribal consumption-noncancer |
| 53 | di-n-octyl phthalate | 117-84-0 | Phthalates | 6.35E+01 | | 1.0E-02 | | 6.1E+01 | 6.1E+01 | Tribal consumption-noncancer |
| 54 | endosulfan | 115-29-7 | Pesticides | 1.68E+02 | | 6.0E-03 | | 1.4E+01 | 1.4E+01 | Tribal consumption-noncancer |
| 55 | endosulfan I (alpha) | 959-98-8 | Pesticides | not in HHRAP | | | | | | |
| 56 | endosulfan II (beta) | 33213-65-9 | Pesticides | not in HHRAP | | | | | | |
| 57 | endosulfan sulfate | 1031-07-8 | Pesticides | not in HHRAP | | 6.0E-03 | | | | |
| 58 | endrin | 72-20-8 | Pesticides | 6.95E+02 | | 3.0E-04 | | 1.7E-01 | 1.7E-01 | Tribal consumption-noncancer |
| 59 | endrin aldehyde | 7421-93-4 | Pesticides | not in HHRAP | | | | | | |
| 60 | endrin ketone | 53494-70-5 | Pesticides | not in HHRAP | | | | | | |
| 61 | ethylbenzene | 100-41-4 | VOCs | 4.86E+01 | 1.1E-02 | 1.0E-01 | 1.4E+00 | 7.9E+02 | 1.4E+00 | Tribal consumption-cancer |
| 62 | fluoranthene | 206-44-0 | PAHs | 1.41E+03 | | 4.0E-02 | | 1.1E+01 | 1.1E+01 | Tribal consumption-noncancer |
| 63 | fluorene | 86-73-7 | PAHs | 3.42E+02 | | 4.0E-02 | | 4.5E+01 | 4.5E+01 | Tribal consumption-noncancer |
| 64 | formaldehyde | 50-00-0 | VOCs | 3.16E+00 | 2.1E-02 | 2.0E-01 | 1.1E+01 | 2.4E+04 | 1.1E+01 | Tribal consumption-cancer |
| 65 | hexachlorobenzene | 118-74-1 | Pesticides | 2.40E+03 | 1.6E+00 | 8.0E-04 | 2.0E-04 | 1.3E-01 | 2.0E-04 | Tribal consumption-cancer |
| 66 | hexachlorocyclohexane, delta- (delta-BHC) | 319-86-8 | Pesticides | not in HHRAP | | | | | | |
| 67 | indeno[1,2,3-cd]pyrene | 193-39-5 | cPAHs | 2.41E+04 | 1.0E-01 | | 1.6E-04 | | 1.6E-04 | Tribal consumption-cancer |
| 68 | iron | 7439-89-6 | Metals | not in HHRAP | | 7.0E-01 | | | | |
| 69 | isopropyltoluene, 4- (cymene, p-) | 99-87-6 | VOCs | not in HHRAP | | | | | | |
| 70 | lead (see notes re: hardness) | 7439-92-1 | Metals | 9.00E-02 | | | | | | |
| 71 | magnesium | 7439-95-4 | Metals | not in HHRAP | | | | | | |
| 72 | manganese (diet) | 7439-96-5 | Metals | not in HHRAP | | 1.4E-01 | | | | |
| 73 | manganese (non-diet) | 7439-96-5 | Metals | not in HHRAP | | 2.4E-02 | | | | |
| 74 | mercury (elemental) | 7439-97-6 | Metals | not in HHRAP | | | | | | |
| 75 | methoxychlor | 72-43-5 | Pesticides | 9.91E+02 | | 5.0E-03 | | 1.9E+00 | 1.9E+00 | Tribal consumption-noncancer |
| 76 | methyl ethyl ketone (butanone, 2-) | 78-93-3 | VOCs | 3.16E+00 | | 6.0E-01 | | 7.3E+04 | 7.3E+04 | Tribal consumption-noncancer |
| 77 | methyl naphthalene; 2- | 91-57-6 | PAHs | not in HHRAP | | 4.0E-03 | | | | |
| 78 | methylene chloride | 75-09-2 | VOCs | 2.00E+00 | 2.0E-03 | 6.0E-03 | 1.9E+02 | 1.2E+03 | 1.9E+02 | Tribal consumption-cancer |
| 79 | methylphenol, 2- (cresol, o-) | 95-48-7 | Phenols | 6.33E+00 | | 5.0E-02 | | 3.0E+03 | 3.0E+03 | Tribal consumption-noncancer |
| 80 | methylphenol, 4- (cresol, p-) | 106-44-5 | Phenols | 5.79E+00 | | 1.0E-01 | | 6.6E+03 | 6.6E+03 | Tribal consumption-noncancer |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1b: Tribal Fish and Shellfish Calculations

| | A | B | C | D | E | F | G | H | I | J |
|-----|--|--------------|--------------------------------|---|--|--|--|--|--|------------------------------|
| 1 | | | | | | | Groundwater to Protect Surface Water - Tribal Fish and Shellfish Consumption | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER TO PROTECT SURFACE WATER: TRIBAL FISH AND SHELLFISH CONSUMPTION | CAS # | Chemical Data Group | Bioconcentration Factor (BCF) fish fresh weight (L/kg FW) (see notes) | Oral Cancer Slope Factor (SFO) (mg/kg-day) ⁻¹ (see notes) | Oral Reference Dose (RfD _o) (mg/kg-day) (see notes) | EPA Tribal fish consumption, cancer (µg/L) | EPA Tribal fish consumption child, noncancer (µg/L) | Lowest of Tribal Fish and Shellfish Consumption values (columns G-H) (µg/L) | Rationale |
| 81 | naphthalene | 91-20-3 | PAHs | 6.93E+01 | 1.2E-01 | 2.0E-02 | 9.1E-02 | 1.1E+02 | 9.1E-02 | Tribal consumption-cancer |
| 82 | nickel (soluble salts) (see notes re: hardness) | 7440-02-0 | Metals | 7.80E+01 | | 2.0E-02 | | 9.9E+01 | 9.9E+01 | Tribal consumption-noncancer |
| 83 | nitrosodiphenylamine, N- | 86-30-6 | SVOCs | 4.86E+01 | 4.9E-03 | | 3.2E+00 | | 3.2E+00 | Tribal consumption-cancer |
| 84 | pentachlorophenol | 87-86-5 | SVOCs | 6.71E+02 | 4.0E-01 | 5.0E-03 | 2.8E-03 | 2.9E+00 | 2.8E-03 | Tribal consumption-cancer |
| 85 | pH | | pH | not in HHRAP | | | | | | |
| 86 | phenanthrene | 85-01-8 | PAHs | 5.82E+02 | | | | | | |
| 87 | phenol | 108-95-2 | Phenols | 2.85E+00 | | 3.0E-01 | | 4.0E+04 | 4.0E+04 | Tribal consumption-noncancer |
| 88 | phenylenediamine, 1,4- (phenylenediamine, p-) | 106-50-3 | SVOCs | not in HHRAP | | 1.0E-03 | | | | |
| 89 | polychlorinated biphenyls; total PCBs | 1336-36-3 | PCBs | not in HHRAP | 2.0E+00 | | | | | |
| 90 | potassium | 7440-09 7 | Metals | not in HHRAP | | | | | | |
| 91 | propanol, 2- (isopropanol) | 67-63-0 | VOCs | not in HHRAP | | 2.0E+00 | | | | |
| 92 | pyrene | 129-00-0 | PAHs | 1.18E+03 | | 3.0E-02 | | 9.8E+00 | 9.8E+00 | Tribal consumption-noncancer |
| 93 | selenium and compounds | 7782-49-2 | Metals | 1.29E+02 | | 5.0E-03 | | 1.5E+01 | 1.5E+01 | Tribal consumption-noncancer |
| 94 | silver | 7440-22-4 | Metals | 8.77E+01 | | 5.0E-03 | | 2.2E+01 | 2.2E+01 | Tribal consumption-noncancer |
| 95 | sodium | 82115-62-6 | Metals | not in HHRAP | | | | | | |
| 96 | tetrachloroethylene | 127-18-4 | VOCs | 8.28E+01 | 2.1E-03 | 6.0E-03 | 4.4E+00 | 2.8E+01 | 4.4E+00 | Tribal consumption-cancer |
| 97 | tin | 7440-31-5 | Metals | not in HHRAP | | 6.0E-01 | | | | |
| 98 | toluene | 108-88-3 | VOCs | 2.39E+01 | | 8.0E-02 | | 1.3E+03 | 1.3E+03 | Tribal consumption-noncancer |
| 99 | total petroleum hydrocarbons (aliphatic high) | E1790670 | TPH | not in HHRAP | | 3.0E+00 | | | | |
| 100 | total petroleum hydrocarbons (aliphatic low) | E1790666 | TPH | not in HHRAP | | | | | | |
| 101 | total petroleum hydrocarbons (aliphatic medium) | E1790668 | TPH | not in HHRAP | | 1.0E-02 | | | | |
| 102 | total petroleum hydrocarbons (aromatic high) | E1790676 | TPH | not in HHRAP | | 4.0E-02 | | | | |
| 103 | total petroleum hydrocarbons (aromatic low) | E1790672 | TPH | not in HHRAP | | 4.0E-03 | | | | |
| 104 | total petroleum hydrocarbons (aromatic medium) | E1790674 | TPH | not in HHRAP | | 4.0E-03 | | | | |
| 105 | trichlorobenzene, 1,2,4- | 120-82-1 | VOCs | 2.40E+02 | 2.9E-02 | 1.0E-02 | 1.1E-01 | 1.6E+01 | 1.1E-01 | Tribal consumption-cancer |
| 106 | trichloroethylene (see notes) | 79-01-6 | VOCs | 1.41E+01 | 4.6E-02 | 5.0E-04 | 1.2E+00 | 1.4E+01 | 1.2E+00 | Tribal consumption-cancer |
| 107 | trichlorophenol, 2,4,5- | 95-95-4 | Phenols | 5.81E+01 | | 1.0E-01 | | 6.6E+02 | 6.6E+02 | Tribal consumption-noncancer |
| 108 | trimethylbenzene; 1,2,4- | 95-63-6 | VOCs | not in HHRAP | | 1.0E-02 | | | | |
| 109 | trimethylbenzene; 1,3,5- | 108-67-8 | VOCs | 8.58E+01 | | 1.0E-02 | | 4.5E+01 | 4.5E+01 | Tribal consumption-noncancer |
| 110 | vanadium and compounds | 7440-62-2 | Metals | not in HHRAP | | 5.0E-03 | | | | |
| 111 | vanillin (4-hydroxy-3-methoxybenzaldehyde) | 121-33-5 | SVOCs | not in HHRAP | | | | | | |
| 112 | xylene; m- | 108-38-3 | VOCs | 5.81E+01 | | 2.0E-01 | | 1.3E+03 | 1.3E+03 | Tribal consumption-noncancer |
| 113 | xylene; o- | 95-47-6 | VOCs | 4.86E+01 | | 2.0E-01 | | 1.6E+03 | 1.6E+03 | Tribal consumption-noncancer |
| 114 | xylene; p- | 106-42-3 | VOCs | 4.86E+01 | | 2.0E-01 | | 1.6E+03 | 1.6E+03 | Tribal consumption-noncancer |
| 115 | xylenes (total) | 1330-20-7 | VOCs | not in HHRAP | | 2.0E-01 | | | | |
| 116 | zinc and compounds (see notes re: hardness) | 7440-66-6 | Metals | 2.06E+03 | | 3.0E-01 | | 5.6E+01 | 5.6E+01 | Tribal consumption-noncancer |
| 117 | | | | | | | | | | |
| 118 | Blank cells indicate a value is not available | | | | | | | | | |
| 119 | L/kg FW - liter per kilogram fresh weight | | | | | | | | | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1b: Tribal Fish and Shellfish Calculations

| | A | B | C | D | E | F | G | H | I | J |
|-----|--|-------|------------------------|---|--|--|--|--|---|-----------|
| 1 | | | | | | | Groundwater to Protect Surface Water - Tribal Fish and Shellfish Consumption | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals GROUNDWATER TO PROTECT SURFACE WATER: TRIBAL FISH AND SHELLFISH CONSUMPTION | CAS # | Chemical Data Group | Bioconcentration Factor (BCF) fish fresh weight (L/kg FW) (see notes) | Oral Cancer Slope Factor (SFO) (mg/kg-day) ⁻¹ (see notes) | Oral Reference Dose (RfD _o) (mg/kg-day) (see notes) | EPA Tribal fish consumption, cancer (µg/L) | EPA Tribal fish consumption child, noncancer (µg/L) | Lowest of Tribal Fish and Shellfish Consumption values (columns G-H) (µg/L) | Rationale |
| 120 | mg/kg-day - milligram per kilogram day | | | | | | | | | |
| 121 | ug/L - microgram per liter | | | | | | | | | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1c. Inputs, Notes, and Equations for Tribal Calculations

| | A | B | C | D | E | F | G | H | I | J |
|----|--|---|---|---|---|---|---------------------|---------------------|---|---|
| 1 | Following are inputs, notes, and equations associated with spreadsheet 1b. Tribal Calculations | | | | | | | | | |
| 2 | | | | | | | | | | |
| 3 | Tribal fish and shellfish consumption scenario for calculating surface water cleanup levels: | | | | | | | | | |
| 4 | | | | | | | | | | |
| 5 | | | | | | | <u>Tribal adult</u> | <u>Tribal child</u> | | |
| 6 | | | | | Body weight, kg | | 81.8 | 15 | | |
| 7 | | | | | Averaging time, years (cancer) | | 70 | 70 | | |
| 8 | | | | | Averaging time, years (noncancer) | | 64 | 6 | | |
| 9 | | | | | CF1 - kg/g | | 0.001 | | | |
| 10 | | | | | CF2 - mg/μg | | 0.001 | | | |
| 11 | | | | | Target hazard quotient | | 1 | 1 | | |
| 12 | | | | | Target risk | | 1.00E-06 | 1.00E-06 | | |
| 13 | | | | | Fish consumption rate - g/day | | 98 | 39 | | |
| 14 | | | | | Diet fraction | | 1 | 1 | | |
| 15 | | | | | Exposure frequency - days/yr | | 365 | 365 | | |
| 16 | | | | | Exposure duration - years | | 64 | 6 | | |
| 17 | | | | | Exposure duration - 0 - 2 yrs | | 2 | | | |
| 18 | | | | | Exposure duration - 2 - 6 yrs | | 4 | | | |
| 19 | | | | | Exposure duration - 6 - 16 yrs | | 10 | | | |
| 20 | | | | | Exposure duration - 16 - 70 yrs | | 54 | | | |
| 21 | | | | | Adjusted early-life exposure consumption rate - (g-yr/kg-day) | | 184 | | | |
| 22 | | | | | Age-adjusted consumption rate (g-yr/kg-day) | | 92 | | | |
| 23 | | | | | | | | | | |
| 24 | Bioconcentration Factors: BCFs are for the most part from EPA Human Health Risk Assessment Protocol (HHRAP) for Hazardous Waste Combustion Facilities, Companion Database, https://archive.epa.gov/epawaste/hazard/tsd/td/web/html/risk.html <i>Barium:</i> BCF of 100 L/kg based on average of USEPA RAIS values of 4 L/kg, an ATSDR value of 100 L/kg for marine animals, and a study value for freshwater fish of 129 L/kg, as proposed by nearby facility on Lower Duwamish, Boeing Plant 2. <i>Copper:</i> BCF from the 1980 EPA Ambient Water Quality Criteria document for copper, page C-18: If the values of zero and 290 are used with the consumption data, the weighted average bioconcentration factor for copper and the edible portion of all freshwater and estuarine aquatic organisms consumed by Americans is calculated to be 36. <i>Aroclor:</i> Aroclor 1260 uses the BCF for Aroclor 1254 as a surrogate, as there is no BCF for Aroclor 1260 in the HHRAP. | | | | | | | | | |
| 25 | | | | | | | | | | |
| 26 | Oral cancer slope factor and oral reference dose values were obtained from EPA Regional Screening Levels (RSLs) tables, updated May 2020: https://www.epa.gov/risk/regional-screening-levels-rsls | | | | | | | | | |
| 27 | | | | | | | | | | |
| 28 | Equations: | | | | | | | | | |
| 29 | | | | | | | | | | |
| 30 | Risk-based PRGs associated with consumption of fish and shellfish are calculated as: | | | | | | | | | |
| 31 | | | | | | | | | | |
| 32 | $PRG_{water} = \frac{THQ \times BW_c \times AT_{nc}}{ED_c \times EF \times \frac{1}{RfD} \times CR_c \times BCF \times 0.001 \text{ mg}/\mu\text{g} \times 0.001 \text{ kg} / \text{g}}$ | | | | | | | | | |
| 33 | | | | | | | | | | |
| 34 | | | | | | | | | | |
| 35 | | | | | | | | | | |
| 36 | | | | | | | | | | |
| 37 | | | | | | | | | | |
| 38 | PRGs based on a cancer endpoint are calculated by averaging child and adult exposures: | | | | | | | | | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1c. Inputs, Notes, and Equations for Tribal Calculations

| | A | B | C | D | E | F | G | H | I | J |
|----|---|---|---|---|---|---|---|---|---|---|
| 39 | | | | | | | | | | |
| 40 | $PRG_{water} = \frac{TR \times AT_c}{EF \times CR_{adj} \times CSF \times BCF \times 0.001 \text{ mg} / \mu\text{g} \times 0.001 \text{ kg} / \text{g}}$ | | | | | | | | | |
| 41 | | | | | | | | | | |
| 42 | | | | | | | | | | |
| 43 | where: | | | | | | | | | |
| 44 | | | | | | | | | | |
| 45 | $CR_{adj} = \frac{ED_c \times CR_c}{BW_c} + \frac{ED_a \times CR_a}{BW_a}$ | | | | | | | | | |
| 46 | | | | | | | | | | |
| 47 | | | | | | | | | | |
| 48 | and: | | | | | | | | | |
| 49 | | | | | | | | | | |
| 50 | PRG _{water} | = | concentration in water (µg/L) | | | | | | | |
| 51 | CR _c | = | consumption rate of fish or shellfish – child (g/day, wet-weight) | | | | | | | |
| 52 | CR _a | = | consumption rate of fish or shellfish – adult (g/day, wet-weight) | | | | | | | |
| 53 | CR _{f-adj} | = | consumption rate of fish or shellfish – age-adjusted (g/day – wet weight) | | | | | | | |
| 54 | EF | = | exposure frequency (days/year) | | | | | | | |
| 55 | ED _c | = | exposure duration – child (years) | | | | | | | |
| 56 | ED _a | = | exposure duration – adult (years) | | | | | | | |
| 57 | BW _c | = | body weight – child (kg) | | | | | | | |
| 58 | BW _a | = | body weight – adult (kg) | | | | | | | |
| 59 | AT _{nc} | = | averaging time, noncancer (days) | | | | | | | |
| 60 | AT _c | = | averaging time, cancer (days) | | | | | | | |
| 61 | BCF | = | bioconcentration factor (L/kg) | | | | | | | |
| 62 | CSF | = | cancer slope factor (mg/kg-day) ⁻¹ | | | | | | | |
| 63 | RfD | = | reference dose (mg/kg-day) | | | | | | | |
| 64 | THQ | = | target hazard quotient | | | | | | | |
| 65 | TR | = | target cancer risk | | | | | | | |
| 66 | | | | | | | | | | |
| 67 | | | | | | | | | | |
| 68 | | | | | | | | | | |
| 69 | Risk-based PRGs for contaminants known to be mutagenic (cPAHs) incorporate the age-dependent | | | | | | | | | |
| 70 | adjustment factors (ADAFs) of 10 and 3, respectively, for exposures occurring before 2 years of age and | | | | | | | | | |
| 71 | | | | | | | | | | |
| 72 | $PRG_{water} = \frac{TR \times AT_c}{EF \times CSF \times CR_{adj-m} \times BCF \times 10^{-3} \text{ kg} / \text{g} \times 10^{-3} \text{ mg} / \mu\text{g}}$ | | | | | | | | | |
| 73 | | | | | | | | | | |
| 74 | | | | | | | | | | |
| 75 | where: | | | | | | | | | |
| 76 | | | | | | | | | | |
| 77 | $CR_{adj-m} = \left(\frac{(ED_{0-2} \times CR_c) \times 10}{BW_c} + \frac{(ED_{2-6} \times CR_c) \times 3}{BW_c} + \frac{(ED_{6-16} \times CR_a) \times 3}{BW_a} + \frac{(ED_{16-30} \times CR_a) \times 1}{BW_a} \right)$ | | | | | | | | | |
| 78 | | | | | | | | | | |
| 79 | | | | | | | | | | |
| 80 | | | | | | | | | | |
| 81 | | | | | | | | | | |
| 82 | | | | | | | | | | |
| 83 | and: | | | | | | | | | |
| 84 | | | | | | | | | | |
| 85 | PRG _{water} | = | concentration in water (µg/L) | | | | | | | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 1c. Inputs, Notes, and Equations for Tribal Calculations

| | A | B | C | D | E | F | G | H | I | J |
|-----|---|---------------------|---|--|---|---|---|---|---|---|
| 86 | | CR _a | = | adult consumption rate (g/day) | | | | | | |
| 87 | | CR _c | = | child consumption rate (g/day) | | | | | | |
| 88 | | CR _{adj-m} | = | age-adjusted consumption rate - mutagens (g-yr/kg-day) | | | | | | |
| 89 | | EF | = | exposure frequency (days/year) | | | | | | |
| 90 | | ED ₀₋₂ | = | exposure duration ages 0-2 (years) | | | | | | |
| 91 | | ED ₂₋₆ | = | exposure duration ages 2-6 (years) | | | | | | |
| 92 | | ED ₆₋₁₆ | = | exposure duration ages 6-16 (years) | | | | | | |
| 93 | | ED ₁₆₋₃₀ | = | exposure duration ages 16-30 (years) | | | | | | |
| 94 | | BW _a | = | adult body weight (kg) | | | | | | |
| 95 | | BW _c | = | child body weight (kg) | | | | | | |
| 96 | | AT _c | = | averaging time, carcinogens (days) | | | | | | |
| 97 | | CSF | = | cancer slope factor (mg/kg-day) ⁻¹ | | | | | | |
| 98 | | TR | = | target cancer risk | | | | | | |
| 99 | | | | | | | | | | |
| 100 | | | | | | | | | | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 2: Soil

| | A | B | C | D | E | F | G | H |
|----|---|--------------|--------------------------------|--|--|--|--|------------------------|
| 1 | | | | Residential Soil* | | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals SOIL | CAS # | Chemical Data Group | EPA Regional Screening Level (RSL) cancer risk=1E-6 (mg/kg) | EPA Regional Screening Level (RSL) noncancer HQ=1 (mg/kg) | Washington State (Puget Sound) Background (mg/kg) | Lowest of Residential Soil RSL Values (or Background if Higher) (mg/kg) | Rationale |
| 3 | acenaphthene | 83-32-9 | PAHs | | 3.6E+03 | | 3.6E+03 | RSL noncancer |
| 4 | acenaphthylene | 208-96-8 | PAHs | | | | | |
| 5 | acetone | 67-64-1 | VOCs | | 6.1E+04 | | 6.1E+04 | RSL noncancer |
| 6 | aldrin (see notes re: aldrin and dieldrin) | 309-00-2 | Pesticides | 3.9E-02 | 2.3E+00 | | 3.9E-02 | RSL cancer |
| 7 | aluminum | 7429-90-5 | Metals | | 7.7E+04 | 3.3E+04 | 7.7E+04 | RSL noncancer |
| 8 | anthracene | 120-12-7 | PAHs | | 1.8E+04 | | 1.8E+04 | RSL noncancer |
| 9 | antimony (metallic) | 7440-36-0 | Metals | | 3.1E+01 | | 3.1E+01 | RSL noncancer |
| 10 | aroclor 1254 | 11097-69-1 | PCBs | 2.4E-01 | 1.2E+00 | | 2.4E-01 | RSL cancer |
| 11 | aroclor 1260 | 11096-82-5 | PCBs | 2.4E-01 | | | 2.4E-01 | RSL cancer |
| 12 | arsenic, inorganic | 7440-38-2 | Metals | 6.8E-01 | 3.5E+01 | 7.3E+00 | 7.3E+00 | Puget Sound Background |
| 13 | barium and compounds | 7440-39-3 | Metals | | 1.5E+04 | | 1.5E+04 | RSL noncancer |
| 14 | benzene | 71-43-2 | VOCs | 1.2E+00 | 8.2E+01 | | 1.2E+00 | RSL cancer |
| 15 | benzo[a]anthracene | 56-55-3 | cPAHs | 1.1E+00 | | | 1.1E+00 | RSL cancer |
| 16 | benzo[a]pyrene | 50-32-8 | cPAHs | 1.1E-01 | 1.8E+01 | | 1.1E-01 | RSL cancer |
| 17 | benzo[b]fluoranthene | 205-99-2 | cPAHs | 1.1E+00 | | | 1.1E+00 | RSL cancer |
| 18 | benzo[g,h,i]perylene | 191-24-2 | PAHs | | | | | |
| 19 | benzo[k]fluoranthene | 207-08-9 | cPAHs | 1.1E+01 | | | 1.1E+01 | RSL cancer |
| 20 | benzoic acid | 65-85-0 | SVOCs | | 2.5E+05 | | 2.5E+05 | RSL noncancer |
| 21 | benzyl alcohol | 100-51-6 | SVOCs | | 6.3E+03 | | 6.3E+03 | RSL noncancer |
| 22 | beryllium | 7440-41-7 | Metals | 1.6E+03 | 1.6E+02 | 6.1E-01 | 1.6E+02 | RSL noncancer |
| 23 | bis(2-ethylhexyl)-phthalate | 117-81-7 | Phthalates | 3.9E+01 | 1.3E+03 | | 3.9E+01 | RSL cancer |
| 24 | bromoform | 75-25-2 | VOCs | 1.9E+01 | 1.6E+03 | | 1.9E+01 | RSL cancer |
| 25 | butyl benzyl phthalate | 85-68-7 | Phthalates | 2.9E+02 | 1.3E+04 | | 2.9E+02 | RSL cancer |
| 26 | butylbenzene; sec- | 135-98-8 | VOCs | | 7.8E+03 | | 7.8E+03 | RSL noncancer |
| 27 | cadmium (food/diet) | 7440-43-9 | Metals | 2.1E+03 | 7.1E+01 | 7.7E-01 | 7.1E+01 | RSL noncancer |
| 28 | cadmium (water) (see notes re: hardness) | 7440-43-9 | Metals | | | | | |
| 29 | calcium | 203863-17-6 | Metals | | | | | |
| 30 | carbazole | 86-74-8 | PAHs | | | | | |
| 31 | carbon disulfide | 75-15-0 | VOCs | | 7.7E+02 | | 7.7E+02 | RSL noncancer |
| 32 | chlordane (technical) | 12789-03-6 | Pesticides | 1.7E+00 | 3.5E+01 | | 1.7E+00 | RSL cancer |
| 33 | chlordane | 57-74-9 | Pesticides | | | | | |
| 34 | chromium (III), insoluble salts (see notes re: hardness) | 16065-83-1 | Metals | | 1.2E+05 | | 1.2E+05 | RSL noncancer |
| 35 | chromium (total) | 7440-47-3 | Metals | | | 4.8E+01 | 4.8E+01 | Puget Sound Background |
| 36 | chromium (VI) | 18540-29-9 | Metals | 3.0E-01 | 2.3E+02 | | 3.0E-01 | RSL cancer |
| 37 | chrysene | 218-01-9 | cPAHs | 1.1E+02 | | | 1.1E+02 | RSL cancer |
| 38 | cobalt | 7440-48-4 | Metals | 4.2E+02 | 2.3E+01 | | 2.3E+01 | RSL noncancer |
| 39 | copper (see notes re: hardness) | 7440-50-8 | Metals | | 3.1E+03 | 3.6E+01 | 3.1E+03 | RSL noncancer |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 2: Soil

| | A | B | C | D | E | F | G | H |
|----|--|------------|------------------------|---|---|---|--|---------------|
| 1 | | | | Residential Soil* | | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals SOIL | CAS # | Chemical Data Group | EPA Regional Screening Level (RSL) cancer risk=1E-6 (mg/kg) | EPA Regional Screening Level (RSL) noncancer HQ=1 (mg/kg) | Washington State (Puget Sound) Background (mg/kg) | Lowest of Residential Soil RSL Values (or Background if Higher) (mg/kg) | Rationale |
| 40 | DDD, 4,4'- | 72-54-8 | Pesticides | 2.3E+00 | 1.9E+00 | | 1.9E+00 | RSL noncancer |
| 41 | DDE, 4,4'- | 72-55-9 | Pesticides | 2.0E+00 | 2.3E+01 | | 2.0E+00 | RSL cancer |
| 42 | DDT, 4,4'- | 50-29-3 | Pesticides | 1.9E+00 | 3.7E+01 | | 1.9E+00 | RSL cancer |
| 43 | dibenz[a,h]anthracene | 53-70-3 | cPAHs | 1.1E-01 | | | 1.1E-01 | RSL cancer |
| 44 | dibenzofuran | 132-64-9 | PAHs | | 7.3E+01 | | 7.3E+01 | RSL noncancer |
| 45 | dichlorobenzene; 1,2- | 95-50-1 | VOCs | | 1.8E+03 | | 1.8E+03 | RSL noncancer |
| 46 | dichlorobenzene; 1,4- | 106-46-7 | VOCs | 2.6E+00 | 3.4E+03 | | 2.6E+00 | RSL cancer |
| 47 | dichloroethylene; 1,2-,cis | 156-59-2 | VOCs | | 1.6E+02 | | 1.6E+02 | RSL noncancer |
| 48 | dieldrin (see notes re: aldrin and dieldrin) | 60-57-1 | Pesticides | 3.4E-02 | 3.2E+00 | | 3.4E-02 | RSL cancer |
| 49 | diethyl phthalate | 84-66-2 | Phthalates | | 5.1E+04 | | 5.1E+04 | RSL noncancer |
| 50 | dimethylphenol; 2,4- | 105-67-9 | Phenols | | 1.3E+03 | | 1.3E+03 | RSL noncancer |
| 51 | dimethyl phthalate | 131-11-3 | Phthalates | | | | | |
| 52 | di-n-butyl-phthalate (dibutyl phthalate) | 84-74-2 | Phthalates | | 6.3E+03 | | 6.3E+03 | RSL noncancer |
| 53 | di-n-octyl phthalate | 117-84-0 | Phthalates | | 6.3E+02 | | 6.3E+02 | RSL noncancer |
| 54 | endosulfan | 115-29-7 | Pesticides | | 4.7E+02 | | 4.7E+02 | RSL noncancer |
| 55 | endosulfan I (alpha) | 959-98-8 | Pesticides | | | | | |
| 56 | endosulfan II (beta) | 33213-65-9 | Pesticides | | | | | |
| 57 | endosulfan sulfate | 1031-07-8 | Pesticides | | 3.8E+02 | | 3.8E+02 | RSL noncancer |
| 58 | endrin | 72-20-8 | Pesticides | | 1.9E+01 | | 1.9E+01 | RSL noncancer |
| 59 | endrin aldehyde | 7421-93-4 | Pesticides | | | | | |
| 60 | endrin ketone | 53494-70-5 | Pesticides | | | | | |
| 61 | ethylbenzene | 100-41-4 | VOCs | 5.8E+00 | 3.4E+03 | | 5.8E+00 | RSL cancer |
| 62 | fluoranthene | 206-44-0 | PAHs | | 2.4E+03 | | 2.4E+03 | RSL noncancer |
| 63 | fluorene | 86-73-7 | PAHs | | 2.4E+03 | | 2.4E+03 | RSL noncancer |
| 64 | formaldehyde | 50-00-0 | VOCs | 1.1E+01 | 7.6E+02 | | 1.1E+01 | RSL cancer |
| 65 | hexachlorobenzene | 118-74-1 | Pesticides | 2.1E-01 | 6.3E+01 | | 2.1E-01 | RSL cancer |
| 66 | hexachlorocyclohexane, delta- (delta-BHC) | 319-86-8 | Pesticides | | | | | |
| 67 | indeno[1,2,3-cd]pyrene | 193-39-5 | cPAHs | 1.1E+00 | | | 1.1E+00 | RSL cancer |
| 68 | iron | 7439-89-6 | Metals | | 5.5E+04 | 3.6E+04 | 5.5E+04 | RSL noncancer |
| 69 | isopropyltoluene, 4- (cymene, p-) | 99-87-6 | VOCs | | | | | |
| 70 | lead (see notes re: hardness) | 7439-92-1 | Metals | | 4.0E+02 | 1.7E+01 | 4.0E+02 | RSL noncancer |
| 71 | magnesium | 7439-95-4 | Metals | | | | | |
| 72 | manganese (diet) | 7439-96-5 | Metals | | | | | |
| 73 | manganese (non-diet) | 7439-96-5 | Metals | | 1.8E+03 | 1.1E+03 | 1.8E+03 | RSL noncancer |
| 74 | mercury (elemental) | 7439-97-6 | Metals | | 1.1E+01 | 7.0E-02 | 1.1E+01 | RSL noncancer |
| 75 | methoxychlor | 72-43-5 | Pesticides | | 3.2E+02 | | 3.2E+02 | RSL noncancer |
| 76 | methyl ethyl ketone (butanone, 2-) | 78-93-3 | VOCs | | 2.7E+04 | | 2.7E+04 | RSL noncancer |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 2: Soil

| | A | B | C | D | E | F | G | H |
|-----|--|------------|------------------------|---|---|---|--|---------------|
| 1 | | | | Residential Soil* | | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals SOIL | CAS # | Chemical Data Group | EPA Regional Screening Level (RSL) cancer risk=1E-6 (mg/kg) | EPA Regional Screening Level (RSL) noncancer HQ=1 (mg/kg) | Washington State (Puget Sound) Background (mg/kg) | Lowest of Residential Soil RSL Values (or Background if Higher) (mg/kg) | Rationale |
| 77 | methyl naphthalene; 2- | 91-57-6 | PAHs | | 2.4E+02 | | 2.4E+02 | RSL noncancer |
| 78 | methylene chloride | 75-09-2 | VOCs | 5.7E+01 | 3.5E+02 | | 5.7E+01 | RSL cancer |
| 79 | methylphenol, 2- (cresol, o-) | 95-48-7 | Phenols | | 3.2E+03 | | 3.2E+03 | RSL noncancer |
| 80 | methylphenol, 4- (cresol, p-) | 106-44-5 | Phenols | | 6.3E+03 | | 6.3E+03 | RSL noncancer |
| 81 | naphthalene | 91-20-3 | PAHs | 2.0E+00 | 1.3E+02 | | 2.0E+00 | RSL cancer |
| 82 | nickel (soluble salts) (see notes re: hardness) | 7440-02-0 | Metals | 1.5E+04 | 1.5E+03 | 3.8E+01 | 1.5E+03 | RSL noncancer |
| 83 | nitrosodiphenylamine, N- | 86-30-6 | SVOCs | 1.1E+02 | | | 1.1E+02 | RSL cancer |
| 84 | pentachlorophenol | 87-86-5 | SVOCs | 1.0E+00 | 2.5E+02 | | 1.0E+00 | RSL cancer |
| 85 | pH | -- | pH | | | | | |
| 86 | phenanthrene | 85-01-8 | PAHs | | | | | |
| 87 | phenol | 108-95-2 | Phenols | | 1.9E+04 | | 1.9E+04 | RSL noncancer |
| 88 | phenylenediamine, 1,4- (phenylenediamine, p-) | 106-50-3 | SVOCs | | 6.3E+01 | | 6.3E+01 | RSL noncancer |
| 89 | polychlorinated biphenyls; total PCBs | 1336-36-3 | PCBs | 2.3E-01 | | | 2.3E-01 | RSL cancer |
| 90 | potassium | 7440-09-7 | Metals | | | | | |
| 91 | propanol, 2- (isopropanol) | 67-63-0 | VOCs | | 5.6E+03 | | 5.6E+03 | RSL noncancer |
| 92 | pyrene | 129-00-0 | PAHs | | 1.8E+03 | | 1.8E+03 | RSL noncancer |
| 93 | selenium and compounds | 7782-49-2 | Metals | | 3.9E+02 | | 3.9E+02 | RSL noncancer |
| 94 | silver | 7440-22-4 | Metals | | 3.9E+02 | | 3.9E+02 | RSL noncancer |
| 95 | sodium | 82115-62-6 | Metals | | | | | |
| 96 | tetrachloroethylene | 127-18-4 | VOCs | 2.4E+01 | 8.1E+01 | | 2.4E+01 | RSL cancer |
| 97 | tin | 7440-31-5 | Metals | | 4.7E+04 | | 4.7E+04 | RSL noncancer |
| 98 | toluene | 108-88-3 | VOCs | | 4.9E+03 | | 4.9E+03 | RSL noncancer |
| 99 | total petroleum hydrocarbons (aliphatic high) | E1790670 | TPH | | 2.3E+05 | | 2.3E+05 | RSL noncancer |
| 100 | total petroleum hydrocarbons (aliphatic low) | E1790666 | TPH | | 5.2E+02 | | 5.2E+02 | RSL noncancer |
| 101 | total petroleum hydrocarbons (aliphatic medium) | E1790668 | TPH | | 9.6E+01 | | 9.6E+01 | RSL noncancer |
| 102 | total petroleum hydrocarbons (aromatic high) | E1790676 | TPH | | 2.4E+03 | | 2.4E+03 | RSL noncancer |
| 103 | total petroleum hydrocarbons (aromatic low) | E1790672 | TPH | | 8.2E+01 | | 8.2E+01 | RSL noncancer |
| 104 | total petroleum hydrocarbons (aromatic medium) | E1790674 | TPH | | 9.7E+01 | | 9.7E+01 | RSL noncancer |
| 105 | trichlorobenzene, 1,2,4- | 120-82-1 | VOCs | 2.4E+01 | 5.8E+01 | | 2.4E+01 | RSL cancer |
| 106 | trichloroethylene (see notes) | 79-01-6 | VOCs | 9.4E-01 | 4.1E+00 | | 9.4E-01 | RSL cancer |
| 107 | trichlorophenol, 2,4,5- | 95-95-4 | Phenols | | 6.3E+03 | | 6.3E+03 | RSL noncancer |
| 108 | trimethylbenzene; 1,2,4- | 95-63-6 | VOCs | | 3.0E+02 | | 3.0E+02 | RSL noncancer |
| 109 | trimethylbenzene; 1,3,5- | 108-67-8 | VOCs | | 2.7E+02 | | 2.7E+02 | RSL noncancer |
| 110 | vanadium and compounds | 7440-62-2 | Metals | | 3.9E+02 | | 3.9E+02 | RSL noncancer |
| 111 | vanillin (4-hydroxy-3-methoxybenzaldehyde) | 121-33-5 | SVOCs | | | | | |
| 112 | xylene; m- | 108-38-3 | VOCs | | 5.5E+02 | | 5.5E+02 | RSL noncancer |
| 113 | xylene; o- | 95-47-6 | VOCs | | 6.5E+02 | | 6.5E+02 | RSL noncancer |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 2: Soil

| | A | B | C | D | E | F | G | H |
|-----|---|-----------|------------------------|---|---|---|--|---------------|
| 1 | | | | Residential Soil* | | | | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals SOIL | CAS # | Chemical Data Group | EPA Regional Screening Level (RSL) cancer risk=1E-6 (mg/kg) | EPA Regional Screening Level (RSL) noncancer HQ=1 (mg/kg) | Washington State (Puget Sound) Background (mg/kg) | Lowest of Residential Soil RSL Values (or Background if Higher) (mg/kg) | Rationale |
| 114 | xylene; p- | 106-42-3 | VOCs | | 5.6E+02 | | 5.6E+02 | RSL noncancer |
| 115 | xlenes (total) | 1330-20-7 | VOCs | | 5.8E+02 | | 5.8E+02 | RSL noncancer |
| 116 | zinc and compounds (see notes re: hardness) | 7440-66-6 | Metals | | 2.3E+04 | 8.5E+01 | 2.3E+04 | RSL noncancer |
| 117 | | | | | | | | |
| 118 | * - Residential and Composite Worker Soil values apply throughout the vadose zone. Soil to Protect Sediment values apply throughout the vadose zone from the barrier wall to the tideflats. | | | | | | | |
| 119 | Blank cells indicate a value is not available | | | | | | | |
| 120 | mg/kg - milligram per kilogram | | | | | | | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 2: Soil

| | A | B | C | I | J | K | L | M | N | O | P | Q | R | S |
|----|--|-------------|------------------------|---|---|---|---|--|------------------------|---|--|---|--|---|
| 1 | | | | | Composite Worker Soil* | | | | | | Soil to Protect Sediment* | | Residential Soil to Protect Groundwater* | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals SOIL | CAS # | Chemical Data Group | | EPA Regional Screening Level (RSL) cancer risk=1E-6 (mg/kg) | EPA Regional Screening Level (RSL) noncancer HQ=1 (mg/kg) | Washington State (Puget Sound) Background (mg/kg) | Lowest of Composite Worker Soil RSL Values (or Background if Higher) (mg/kg) | Rationale | | LDW PCUL SL-8 Protect Sediment via Bank Erosion (mg/kg) | | EPA Regional Screening Level (RSL) Soil Screening Level to Protect Groundwater (Risk-based) (mg/kg) | EPA Regional Screening Level (RSL) Soil Screening Level to Protect Groundwater (MCL-based) (mg/kg) |
| 3 | acenaphthene | 83-32-9 | PAHs | | | 4.5E+04 | | 4.5E+04 | RSL noncancer | | 5.0E-01 | | 5.5E+00 | |
| 4 | acenaphthylene | 208-96-8 | PAHs | | | | | | | | 1.3E+00 | | | |
| 5 | acetone | 67-64-1 | VOCs | | | 6.7E+05 | | 6.7E+05 | RSL noncancer | | | | 2.9E+00 | |
| 6 | aldrin (see notes re: aldrin and dieldrin) | 309-00-2 | Pesticides | | 1.8E-01 | 3.5E+01 | | 1.8E-01 | RSL cancer | | 1.0E-04 | | 1.5E-04 | |
| 7 | aluminum | 7429-90-5 | Metals | | | 1.1E+06 | 3.3E+04 | 1.1E+06 | RSL noncancer | | 2.4E+05 | | 3.0E+04 | |
| 8 | anthracene | 120-12-7 | PAHs | | | 2.3E+05 | | 2.3E+05 | RSL noncancer | | 9.6E-01 | | 5.8E+01 | |
| 9 | antimony (metallic) | 7440-36-0 | Metals | | | 4.7E+02 | | 4.7E+02 | RSL noncancer | | 9.7E+01 | | 3.5E-01 | 2.7E-01 |
| 10 | aroclor 1254 | 11097-69-1 | PCBs | | 9.7E-01 | 1.5E+01 | | 9.7E-01 | RSL cancer | | | | 2.1E-03 | |
| 11 | aroclor 1260 | 11096-82-5 | PCBs | | 9.9E-01 | | | 9.9E-01 | RSL cancer | | | | 5.5E-03 | |
| 12 | arsenic, inorganic | 7440-38-2 | Metals | | 3.0E+00 | 4.8E+02 | 7.3E+00 | 7.3E+00 | Puget Sound background | | 7.0E+00 | | 1.5E-03 | 2.9E-01 |
| 13 | barium and compounds | 7440-39-3 | Metals | | | 2.2E+05 | | 2.2E+05 | RSL noncancer | | 4.9E+04 | | 1.6E+02 | 8.2E+01 |
| 14 | benzene | 71-43-2 | VOCs | | 5.1E+00 | 4.2E+02 | | 5.1E+00 | RSL cancer | | | | 2.3E-04 | 2.6E-03 |
| 15 | benzo[a]anthracene | 56-55-3 | cPAHs | | 2.1E+01 | | | 2.1E+01 | RSL cancer | | 1.3E+00 | | 1.1E-02 | |
| 16 | benzo[a]pyrene | 50-32-8 | cPAHs | | 2.1E+00 | 2.2E+02 | | 2.1E+00 | RSL cancer | | 1.6E+00 | | 2.9E-02 | 2.4E-01 |
| 17 | benzo[b]fluoranthene | 205-99-2 | cPAHs | | 2.1E+01 | | | 2.1E+01 | RSL cancer | | | | 3.0E-01 | |
| 18 | benzo[g,h,i]perylene | 191-24-2 | PAHs | | | | | | | | 6.7E-01 | | | |
| 19 | benzo[k]fluoranthene | 207-08-9 | cPAHs | | 2.1E+02 | | | 2.1E+02 | RSL cancer | | | | 2.9E+00 | |
| 20 | benzoic acid | 65-85-0 | SVOCs | | | 3.3E+06 | | 3.3E+06 | RSL noncancer | | 6.5E-01 | | 1.5E+01 | |
| 21 | benzyl alcohol | 100-51-6 | SVOCs | | | 8.2E+04 | | 8.2E+04 | RSL noncancer | | 5.7E-02 | | 4.8E-01 | |
| 22 | beryllium | 7440-41-7 | Metals | | 6.9E+03 | 2.3E+03 | 6.1E-01 | 2.3E+03 | RSL noncancer | | 4.9E+02 | | 2.0E+01 | 3.2E+00 |
| 23 | bis(2-ethylhexyl)-phthalate | 117-81-7 | Phthalates | | 1.6E+02 | 1.6E+04 | | 1.6E+02 | RSL cancer | | 1.3E+00 | | 1.3E+00 | 1.4E+00 |
| 24 | bromoform | 75-25-2 | VOCs | | 8.6E+01 | 2.3E+04 | | 8.6E+01 | RSL cancer | | | | 8.7E-04 | 2.1E-02 |
| 25 | butyl benzyl phthalate | 85-68-7 | Phthalates | | 1.2E+03 | 1.6E+05 | | 1.2E+03 | RSL cancer | | 6.3E-02 | | 2.4E-01 | |
| 26 | butylbenzene; sec- | 135-98-8 | VOCs | | | 1.2E+05 | | 1.2E+05 | RSL noncancer | | | | 5.9E+00 | |
| 27 | cadmium (food/diet) | 7440-43-9 | Metals | | 9.3E+03 | 9.8E+02 | 7.7E-01 | 9.8E+02 | RSL noncancer | | 5.1E+00 | | | |
| 28 | cadmium (water) (see notes re: hardness) | 7440-43-9 | Metals | | | | | | | | | | 6.9E-01 | 3.8E-01 |
| 29 | calcium | 203863-17-6 | Metals | | | | | | | | | | | |
| 30 | carbazole | 86-74-8 | PAHs | | | | | | | | | | | |
| 31 | carbon disulfide | 75-15-0 | VOCs | | | 3.5E+03 | | 3.5E+03 | RSL noncancer | | | | 2.4E-01 | |
| 32 | chlordan (technical) | 12789-03-6 | Pesticides | | 7.7E+00 | 4.5E+02 | | 7.7E+00 | RSL cancer | | | | 2.7E-03 | 2.7E-01 |
| 33 | chlordan | 57-74-9 | Pesticides | | | | | | | | | | | |
| 34 | chromium (III), insoluble salts (see notes re: hardness) | 16065-83-1 | Metals | | | 1.8E+06 | | 1.8E+06 | RSL noncancer | | 3.7E+05 | | 4.0E+07 | |
| 35 | chromium (total) | 7440-47-3 | Metals | | | | 4.8E+01 | 4.8E+01 | Puget Sound background | | 2.6E+02 | | | 1.8E+05 |
| 36 | chromium (VI) | 18540-29-9 | Metals | | 6.3E+00 | 3.5E+03 | | 6.3E+00 | RSL cancer | | 7.3E+02 | | 6.7E-04 | |
| 37 | chrysene | 218-01-9 | cPAHs | | 2.1E+03 | | | 2.1E+03 | RSL cancer | | 1.4E+00 | | 9.1E+00 | |
| 38 | cobalt | 7440-48-4 | Metals | | 1.9E+03 | 3.5E+02 | | 3.5E+02 | RSL noncancer | | 7.3E+01 | | 2.7E-01 | |
| 39 | copper (see notes re: hardness) | 7440-50-8 | Metals | | | 4.7E+04 | 3.6E+01 | 4.7E+04 | RSL noncancer | | 3.9E+02 | | 2.8E+01 | 4.6E+01 |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 2: Soil

| | A | B | C | I | J | K | L | M | N | O | P | Q | R | S |
|----|--|------------|------------------------|---|---|---|---|--|---------------|---|--|---|--|---|
| 1 | | | | | Composite Worker Soil* | | | | | | Soil to Protect Sediment* | | Residential Soil to Protect Groundwater* | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals SOIL | CAS # | Chemical Data Group | | EPA Regional Screening Level (RSL) cancer risk=1E-6 (mg/kg) | EPA Regional Screening Level (RSL) noncancer HQ=1 (mg/kg) | Washington State (Puget Sound) Background (mg/kg) | Lowest of Composite Worker Soil RSL Values (or Background if Higher) (mg/kg) | Rationale | | LDW PCUL SL-8 Protect Sediment via Bank Erosion (mg/kg) | | EPA Regional Screening Level (RSL) Soil Screening Level to Protect Groundwater (Risk-based) (mg/kg) | EPA Regional Screening Level (RSL) Soil Screening Level to Protect Groundwater (MCL-based) (mg/kg) |
| 40 | DDD, 4,4'- | 72-54-8 | Pesticides | | 9.6E+00 | 2.5E+01 | | 9.6E+00 | RSL cancer | | 6.8E+00 | | 7.5E-03 | |
| 41 | DDE, 4,4'- | 72-55-9 | Pesticides | | 9.3E+00 | 3.5E+02 | | 9.3E+00 | RSL cancer | | 6.3E+00 | | 1.1E-02 | |
| 42 | DDT, 4,4'- | 50-29-3 | Pesticides | | 8.5E+00 | 5.2E+02 | | 8.5E+00 | RSL cancer | | 1.0E-04 | | 7.7E-02 | |
| 43 | dibenz[a,h]anthracene | 53-70-3 | cPAHs | | | | | | | | 2.3E-01 | | 9.6E-02 | |
| 44 | dibenzofuran | 132-64-9 | PAHs | | | 1.0E+03 | | 1.0E+03 | RSL noncancer | | 5.4E-01 | | 1.5E-01 | |
| 45 | dichlorobenzene; 1,2- | 95-50-1 | VOCs | | | 9.3E+03 | | 9.3E+03 | RSL noncancer | | 3.6E-02 | | 3.0E-01 | 5.8E-01 |
| 46 | dichlorobenzene; 1,4- | 106-46-7 | VOCs | | 1.1E+01 | 2.5E+04 | | 1.1E+01 | RSL cancer | | 1.1E-01 | | 4.6E-04 | 7.2E-02 |
| 47 | dichloroethylene; 1,2-,cis | 156-59-2 | VOCs | | | 2.3E+03 | | 2.3E+03 | RSL noncancer | | | | 1.1E-02 | 2.1E-02 |
| 48 | dieldrin (see notes re: aldrin and dieldrin) | 60-57-1 | Pesticides | | 1.4E-01 | 4.1E+01 | | 1.4E-01 | RSL cancer | | 1.0E-04 | | 7.1E-05 | |
| 49 | diethyl phthalate | 84-66-2 | Phthalates | | | 6.6E+05 | | 6.6E+05 | RSL noncancer | | 2.0E-01 | | 6.1E+00 | |
| 50 | dimethylphenol; 2,4- | 105-67-9 | Phenols | | | 1.6E+04 | | 1.6E+04 | RSL noncancer | | 2.9E-02 | | 4.2E-01 | |
| 51 | dimethyl phthalate | 131-11-3 | Phthalates | | | | | | | | 7.1E-02 | | | |
| 52 | di-n-butyl-phthalate (dibutyl phthalate) | 84-74-2 | Phthalates | | | 8.2E+04 | | 8.2E+04 | RSL noncancer | | 1.4E+00 | | 2.3E+00 | |
| 53 | di-n-octyl phthalate | 117-84-0 | Phthalates | | | 8.2E+03 | | 8.2E+03 | RSL noncancer | | 6.2E+00 | | 5.7E+01 | |
| 54 | endosulfan | 115-29-7 | Pesticides | | | 7.0E+03 | | 7.0E+03 | RSL noncancer | | | | 1.4E+00 | |
| 55 | endosulfan I (alpha) | 959-98-8 | Pesticides | | | | | | | | 1.2E+03 | | | |
| 56 | endosulfan II (beta) | 33213-65-9 | Pesticides | | | | | | | | 1.2E+03 | | | |
| 57 | endosulfan sulfate | 1031-07-8 | Pesticides | | | 4.9E+03 | | 4.9E+03 | RSL noncancer | | 1.2E+03 | | 2.1E+00 | |
| 58 | endrin | 72-20-8 | Pesticides | | | 2.5E+02 | | 2.5E+02 | RSL noncancer | | 6.0E+01 | | 9.2E-02 | 8.1E-02 |
| 59 | endrin aldehyde | 7421-93-4 | Pesticides | | | | | | | | | | | |
| 60 | endrin ketone | 53494-70-5 | Pesticides | | | | | | | | | | | |
| 61 | ethylbenzene | 100-41-4 | VOCs | | 2.5E+01 | 2.0E+04 | | 2.5E+01 | RSL cancer | | | | 1.7E-03 | 7.9E-01 |
| 62 | fluoranthene | 206-44-0 | PAHs | | | 3.0E+04 | | 3.0E+04 | RSL noncancer | | 1.7E+00 | | 8.9E+01 | |
| 63 | fluorene | 86-73-7 | PAHs | | | 3.0E+04 | | 3.0E+04 | RSL noncancer | | 5.4E-01 | | 5.5E+00 | |
| 64 | formaldehyde | 50-00-0 | VOCs | | 5.0E+01 | 3.3E+03 | | 5.0E+01 | RSL cancer | | | | 7.8E-05 | |
| 65 | hexachlorobenzene | 118-74-1 | Pesticides | | 9.6E-01 | 9.3E+02 | | 9.6E-01 | RSL cancer | | 2.2E-02 | | 1.2E-04 | 1.3E-02 |
| 66 | hexachlorocyclohexane, delta- (delta-BHC) | 319-86-8 | Pesticides | | | | | | | | | | | |
| 67 | indeno[1,2,3-cd]pyrene | 193-39-5 | cPAHs | | 2.1E+01 | | | 2.1E+01 | RSL cancer | | 6.0E-01 | | 9.8E-01 | |
| 68 | iron | 7439-89-6 | Metals | | | 8.2E+05 | 3.6E+04 | 8.2E+05 | RSL noncancer | | 1.7E+05 | | 3.5E+02 | |
| 69 | isopropyltoluene, 4- (cymene, p-) | 99-87-6 | VOCs | | | | | | | | | | | |
| 70 | lead (see notes re: hardness) | 7439-92-1 | Metals | | | 8.0E+02 | 1.7E+01 | 8.0E+02 | RSL noncancer | | 4.5E+02 | | | 1.4E+01 |
| 71 | magnesium | 7439-95-4 | Metals | | | | | | | | | | | |
| 72 | manganese (diet) | 7439-96-5 | Metals | | | | | | | | 1.1E+04 | | | |
| 73 | manganese (non-diet) | 7439-96-5 | Metals | | | 2.6E+04 | 1.1E+03 | 2.6E+04 | RSL noncancer | | | | 2.8E+01 | |
| 74 | mercury (elemental) | 7439-97-6 | Metals | | | 4.6E+01 | 7.0E-02 | 4.6E+01 | RSL noncancer | | 4.1E-01 | | 3.3E-02 | 1.0E-01 |
| 75 | methoxychlor | 72-43-5 | Pesticides | | | 4.1E+03 | | 4.1E+03 | RSL noncancer | | 1.0E+03 | | 2.0E+00 | 2.2E+00 |
| 76 | methyl ethyl ketone (butanone, 2-) | 78-93-3 | VOCs | | | 1.9E+05 | | 1.9E+05 | RSL noncancer | | | | 1.2E+00 | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 2: Soil

| | A | B | C | I | J | K | L | M | N | O | P | Q | R | S |
|-----|--|------------|------------------------|---|---|---|---|--|---------------|---|--|---|--|---|
| 1 | | | | | Composite Worker Soil* | | | | | | Soil to Protect Sediment* | | Residential Soil to Protect Groundwater* | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals SOIL | CAS # | Chemical Data Group | | EPA Regional Screening Level (RSL) cancer risk=1E-6 (mg/kg) | EPA Regional Screening Level (RSL) noncancer HQ=1 (mg/kg) | Washington State (Puget Sound) Background (mg/kg) | Lowest of Composite Worker Soil RSL Values (or Background if Higher) (mg/kg) | Rationale | | LDW PCUL SL-8 Protect Sediment via Bank Erosion (mg/kg) | | EPA Regional Screening Level (RSL) Soil Screening Level to Protect Groundwater (Risk-based) (mg/kg) | EPA Regional Screening Level (RSL) Soil Screening Level to Protect Groundwater (MCL-based) (mg/kg) |
| 77 | methyl naphthalene; 2- | 91-57-6 | PAHs | | | 3.0E+03 | | 3.0E+03 | RSL noncancer | | 6.7E-01 | | 1.9E-01 | |
| 78 | methylene chloride | 75-09-2 | VOCs | | 1.0E+03 | 3.2E+03 | | 1.0E+03 | RSL cancer | | | | 2.9E-03 | 1.3E-03 |
| 79 | methylphenol, 2- (cresol, o-) | 95-48-7 | Phenols | | | 4.1E+04 | | 4.1E+04 | RSL noncancer | | 6.3E-02 | | 7.5E-01 | |
| 80 | methylphenol, 4- (cresol, p-) | 106-44-5 | Phenols | | | 8.2E+04 | | 8.2E+04 | RSL noncancer | | 6.7E-01 | | 1.5E+00 | |
| 81 | naphthalene | 91-20-3 | PAHs | | 8.6E+00 | 5.9E+02 | | 8.6E+00 | RSL cancer | | 2.1E+00 | | 3.8E-04 | |
| 82 | nickel (soluble salts) (see notes re: hardness) | 7440-02-0 | Metals | | 6.4E+04 | 2.2E+04 | 3.8E+01 | 2.2E+04 | RSL noncancer | | 4.9E+03 | | 2.6E+01 | |
| 83 | nitrosodiphenylamine, N- | 86-30-6 | SVOCs | | 4.7E+02 | | | 4.7E+02 | RSL cancer | | 2.8E-02 | | 6.7E-02 | |
| 84 | pentachlorophenol | 87-86-5 | SVOCs | | 4.0E+00 | 2.8E+03 | | 4.0E+00 | RSL cancer | | 3.6E-01 | | 5.7E-05 | 1.4E-03 |
| 85 | pH | -- | pH | | | | | | | | | | | |
| 86 | phenanthrene | 85-01-8 | PAHs | | | | | | | | 1.5E+00 | | | |
| 87 | phenol | 108-95-2 | Phenols | | | 2.5E+05 | | 2.5E+05 | RSL noncancer | | 4.2E-01 | | 3.3E+00 | |
| 88 | phenylenediamine, 1,4- (phenylenediamine, p-) | 106-50-3 | SVOCs | | | 8.2E+02 | | 8.2E+02 | RSL noncancer | | | | 5.4E-03 | |
| 89 | polychlorinated biphenyls; total PCBs | 1336-36-3 | PCBs | | 9.4E-01 | | | 9.4E-01 | RSL cancer | | 1.3E-01 | | 6.8E-03 | 7.8E-02 |
| 90 | potassium | 7440-09 7 | Metals | | | | | | | | | | | |
| 91 | propanol, 2- (isopropanol) | 67-63-0 | VOCs | | | 2.4E+04 | | 2.4E+04 | RSL noncancer | | | | 8.4E-02 | |
| 92 | pyrene | 129-00-0 | PAHs | | | 2.3E+04 | | 2.3E+04 | RSL noncancer | | 2.6E+00 | | 1.3E+01 | |
| 93 | selenium and compounds | 7782-49-2 | Metals | | | 5.8E+03 | | 5.8E+03 | RSL noncancer | | 1.2E+03 | | 5.2E-01 | 2.6E-01 |
| 94 | silver | 7440-22-4 | Metals | | | 5.8E+03 | | 5.8E+03 | RSL noncancer | | 6.1E+00 | | 8.0E-01 | |
| 95 | sodium | 82115-62-6 | Metals | | | | | | | | | | | |
| 96 | tetrachloroethylene | 127-18-4 | VOCs | | 1.0E+02 | 3.9E+02 | | 1.0E+02 | RSL cancer | | | | 5.1E-03 | 2.3E-03 |
| 97 | tin | 7440-31-5 | Metals | | | 7.0E+05 | | 7.0E+05 | RSL noncancer | | 1.5E+05 | | 3.0E+03 | |
| 98 | toluene | 108-88-3 | VOCs | | | 4.7E+04 | | 4.7E+04 | RSL noncancer | | | | 7.6E-01 | 6.9E-01 |
| 99 | total petroleum hydrocarbons (aliphatic high) | E1790670 | TPH | | | 3.5E+06 | | 3.5E+06 | RSL noncancer | | | | 2.4E+03 | |
| 100 | total petroleum hydrocarbons (aliphatic low) | E1790666 | TPH | | | 2.2E+03 | | 2.2E+03 | RSL noncancer | | | | 8.8E+00 | |
| 101 | total petroleum hydrocarbons (aliphatic medium) | E1790668 | TPH | | | 4.4E+02 | | 4.4E+02 | RSL noncancer | | | | 1.5E+00 | |
| 102 | total petroleum hydrocarbons (aromatic high) | E1790676 | TPH | | | 3.0E+04 | | 3.0E+04 | RSL noncancer | | | | 8.9E+01 | |
| 103 | total petroleum hydrocarbons (aromatic low) | E1790672 | TPH | | | 4.2E+02 | | 4.2E+02 | RSL noncancer | | | | 1.7E-02 | |
| 104 | total petroleum hydrocarbons (aromatic medium) | E1790674 | TPH | | | 5.6E+02 | | 5.6E+02 | RSL noncancer | | | | 2.3E-02 | |
| 105 | trichlorobenzene, 1,2,4- | 120-82-1 | VOCs | | 1.1E+02 | 2.6E+02 | | 1.1E+02 | RSL cancer | | 3.1E-02 | | 3.4E-03 | 2.0E-01 |
| 106 | trichloroethylene (see notes) | 79-01-6 | VOCs | | 6.0E+00 | 1.9E+01 | | 6.0E+00 | RSL cancer | | | | 1.8E-04 | 1.8E-03 |
| 107 | trichlorophenol, 2,4,5- | 95-95-4 | Phenols | | | 8.2E+04 | | 8.2E+04 | RSL noncancer | | 2.0E+04 | | 4.0E+00 | |
| 108 | trimethylbenzene; 1,2,4- | 95-63-6 | VOCs | | | 1.8E+03 | | 1.8E+03 | RSL noncancer | | | | 8.1E-02 | |
| 109 | trimethylbenzene; 1,3,5- | 108-67-8 | VOCs | | | 1.5E+03 | | 1.5E+03 | RSL noncancer | | | | 8.7E-02 | |
| 110 | vanadium and compounds | 7440-62-2 | Metals | | | 5.8E+03 | | 5.8E+03 | RSL noncancer | | 2.2E+03 | | 8.6E+01 | |
| 111 | vanillin (4-hydroxy-3-methoxybenzaldehyde) | 121-33-5 | SVOCs | | | | | | | | | | | |
| 112 | xylene; m- | 108-38-3 | VOCs | | | 2.4E+03 | | 2.4E+03 | RSL noncancer | | | | 1.9E-01 | |
| 113 | xylene; o- | 95-47-6 | VOCs | | | 2.8E+03 | | 2.8E+03 | RSL noncancer | | | | 1.9E-01 | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 2: Soil

| | A | B | C | I | J | K | L | M | N | O | P | Q | R | S |
|-----|--|-----------|------------------------|---|---|---|---|--|---------------|---|--|---|--|---|
| 1 | | | | | Composite Worker Soil* | | | | | | Soil to Protect Sediment* | | Residential Soil to Protect Groundwater* | |
| 2 | Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals SOIL | CAS # | Chemical Data Group | | EPA Regional Screening Level (RSL) cancer risk=1E-6 (mg/kg) | EPA Regional Screening Level (RSL) noncancer HQ=1 (mg/kg) | Washington State (Puget Sound) Background (mg/kg) | Lowest of Composite Worker Soil RSL Values (or Background if Higher) (mg/kg) | Rationale | | LDW PCUL SL-8 Protect Sediment via Bank Erosion (mg/kg) | | EPA Regional Screening Level (RSL) Soil Screening Level to Protect Groundwater (Risk-based) (mg/kg) | EPA Regional Screening Level (RSL) Soil Screening Level to Protect Groundwater (MCL-based) (mg/kg) |
| 114 | xylene; p- | 106-42-3 | VOCs | | | 2.4E+03 | | 2.4E+03 | RSL noncancer | | | | 1.9E-01 | |
| 115 | xlenes (total) | 1330-20-7 | VOCs | | | 2.5E+03 | | 2.5E+03 | RSL noncancer | | | | 1.9E-01 | 9.9E+00 |
| 116 | zinc and compounds (see notes re: hardness) | 7440-66-6 | Metals | | | 3.5E+05 | 8.5E+01 | 3.5E+05 | RSL noncancer | | 4.1E+02 | | 3.7E+02 | |
| 117 | | | | | | | | | | | | | | |
| 118 | * - Residential and Composite Worker Soil values apply throughout the vadose zone. Soil to Protect Groundwater values apply to areas of contaminated soil. | | | | | | | | | | | | | |
| 119 | Blank cells indicate a value is not available | | | | | | | | | | | | | |
| 120 | mg/kg - milligram per kilogram | | | | | | | | | | | | | |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 3: Sediment

| Former Rhone-Poulenc Facility Updated Preliminary Remediation Goals SEDIMENT | Sediment Cleanup Objectives, Benthic Community ¹ | Sediment Cleanup Levels, LDW ROD, Benthic Invertebrates ² | Sediment Cleanup Levels, LDW ROD, Human Health and Ecological ³ |
|--|--|--|--|
| | mg/kg Dry Weight | mg/kg Dry Weight | mg/kg Dry Weight |
| Arsenic | 57 | 57 | 7 |
| Cadmium | 5.1 | 5.1 | |
| Chromium | 260 | 260 | |
| Copper | 390 | 390 | |
| Lead | 450 | 450 | |
| Mercury | 0.41 | 0.41 | |
| Silver | 6.1 | 6.1 | |
| Zinc | 410 | 410 | |
| | mg/kg Organic Carbon normalized | mg/kg Organic Carbon normalized | |
| 1,2 Dichlorobenzene | 2.3 | 2.3 | |
| 1,2,4 Trichlorobenzene | 0.81 | 0.81 | |
| 1,4 Dichlorobenzene | 3.1 | 3.1 | |
| 2-Methylnaphthalene | 38 | 38 | |
| Acenaphthene | 16 | 16 | |
| Acenaphthylene | 66 | | |
| Anthracene | 220 | 220 | |
| Benz(a)anthracene | 110 | 110 | |
| Benzo (g,h,i) Perylene | 31 | 31 | |
| Benzo(a)pyrene | 99 | 99 | |
| Bis (2-ethylhexyl) Phthalate | 47 | 47 | |
| Butyl Benzyl Phthalate | 4.9 | 4.9 | |
| Chrysene | 110 | 110 | |
| Dibenzo (a,h) Anthracene | 12 | 12 | |
| Dibenzofuran | 15 | | |
| Diethyl Phthalate | 61 | | |
| Dimethyl Phthalate | 53 | 53 | |
| Di-n-butyl Phthalate | 220 | | |
| Di-n-octyl Phthalate | 58 | | |
| Fluoranthene | 160 | 160 | |
| Fluorene | 23 | 23 | |
| Hexachlorobenzene | 0.38 | 0.38 | |
| Hexachlorobutadiene | 3.9 | | |
| HPAH | 960 | | |
| Indeno(1,2,3 c,d) Pyrene | 34 | 34 | |
| LPAH | 370 | | |
| Naphthalene | 99 | 99 | |
| N-Nitrosodiphenylamine | 11 | 11 | |
| Phenanthrene | 100 | 100 | |
| Pyrene | 1000 | 1000 | |
| Total Benzofluoranthenes | 230 | 230 | |
| Total PCBs | 12 | 12 | |
| | ug/kg Dry Weight | ug/kg Dry Weight | ug/kg Dry Weight |
| 2,4 Dimethyl Phenol | 29 | 29 | |
| 2-Methylphenol | 63 | | |
| 4-Methylphenol | 670 | 670 | |
| Benzoic Acid | 650 | 650 | |
| Benzyl Alcohol | 57 | 57 | |
| Pentachlorophenol | 360 | 360 | |
| Phenol | 420 | 420 | |
| Total PCBs | | | 2 |

1 - From: WAC 173-204-562, Table III, Marine Sediment, Sediment Cleanup Objectives and Cleanup Screening Levels Chemical Criteria; Benthic Community

2 - From: Table 20, Ecological (Benthic Invertebrate) Sediment Cleanup Levels; Record of Decision Lower Duwamish Waterway, November 2014

3 - From: Table 19, Human Health and Ecological Sediment Cleanup Levels; Record of Decision Lower Duwamish Waterway, November 2014

LPAH per WAC 173-204-562: The LPAH criterion in Table III represents the sum of the following "low molecular weight polycyclic aromatic hydrocarbon" compounds: Naphthalene, Acenaphthylene, Acenaphthene, Fluorene, Phenanthrene, and Anthracene. The LPAH criterion is not the sum of the criteria values for the individual LPAH compounds as listed.

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 3: Sediment

HPAH per WAC 173-204-562: The HPAH criterion in Table III represents the sum of the following "high molecular weight polycyclic aromatic hydrocarbon" compounds: Fluoranthene, Pyrene, Benz(a)anthracene, Chrysene, Total Benzofluoranthenes, Benzo(a)pyrene, Indeno(1,2,3,-c,d)pyrene, Dibenzo(a,h)anthracene, and Benzo(g,h,i)perylene. The HPAH criterion is not the sum of the criteria values for the individual HPAH compounds as listed.

ug/kg - microgram per kilogram

mg/kg - milligram per kilogram

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 4: Vapor Intrusion

| Former Rhone-Poulenc Facility Vapor Intrusion Screening Level Calculator Outputs November 2019 | CAS # | Chemical Data Group | RESIDENTIAL | | | | COMMERCIAL | | | |
|--|------------|---------------------------|---|--|---|--|---|--|---|--|
| | | | Target Sub-Slab and Near-source Soil Gas Concentration (TCR=1E-06 or THQ=1) C _{sg,Target} (µg/m ³) | Target Groundwater Concentration (TCR=1E-06 or THQ=1) C _{gw,Target} (µg/L) | Carcinogenic VISL TCR=1E-06 C _{ia,c} (µg/m ³) | Non- carcinogenic VISL THQ=1 C _{ia,nc} (µg/m ³) | Target Sub-Slab and Near-source Soil Gas Concentration (TCR=1E-06 or THQ=1) C _{sg,Target} (µg/m ³) | Target Groundwater Concentration (TCR=1E-06 or THQ=1) C _{gw,Target} (µg/L) | Carcinogenic VISL TCR=1E-06 C _{ia,c} (µg/m ³) | Non- carcinogenic VISL THQ=1 C _{ia,nc} (µg/m ³) |
| acetone | 67-64-1 | VOCs | 1.07E+06 | 2.3E+07 | - | 3.2E+04 | 4.51E+06 | 9.5E+07 | - | 1.4E+05 |
| aldrin (see notes re: aldrin and dieldrin) | 309-00-2 | Pesticides | 1.91E-02 | 3.2E-01 | 5.7E-04 | - | 8.34E-02 | 1.4E+00 | 2.5E-03 | - |
| aroclor 1254 | 11097-69-1 | PCBs | 1.64E-01 | 4.3E-01 | 4.9E-03 | - | 7.15E-01 | 1.9E+00 | 2.2E-02 | - |
| aroclor 1260 | 11096-82-5 | PCBs | 1.64E-01 | 3.6E-01 | 4.9E-03 | - | 7.15E-01 | 1.6E+00 | 2.2E-02 | - |
| benzene | 71-43-2 | VOCs | 1.20E+01 | 1.6E+00 | 3.6E-01 | 3.1E+01 | 5.24E+01 | 6.9E+00 | 1.6E+00 | 1.3E+02 |
| bromoform | 75-25-2 | VOCs | 8.51E+01 | 1.2E+02 | 2.6E+00 | - | 3.72E+02 | 5.1E+02 | 1.1E+01 | - |
| carbon disulfide | 75-15-0 | VOCs | 2.43E+04 | 1.2E+03 | - | 7.3E+02 | 1.02E+05 | 5.2E+03 | - | 3.1E+03 |
| chlordane (technical) | 12789-03-6 | Pesticides | 9.36E-01 | 1.4E+01 | 2.8E-02 | 7.3E-01 | 4.09E+00 | 6.2E+01 | 1.2E-01 | 3.1E+00 |
| DDE, 4,4'- | 72-55-9 | Pesticides | 9.65E-01 | 1.7E+01 | 2.9E-02 | - | 4.21E+00 | 7.4E+01 | 1.3E-01 | - |
| dichlorobenzene, 1,2- | 95-50-1 | VOCs | 6.95E+03 | 2.7E+03 | - | 2.1E+02 | 2.92E+04 | 1.1E+04 | - | 8.8E+02 |
| dichlorobenzene; 1,4- | 106-46-7 | VOCs | 8.51E+00 | 2.6E+00 | 2.6E-01 | 8.3E+02 | 3.72E+01 | 1.1E+01 | 1.1E+00 | 3.5E+03 |
| ethylbenzene | 100-41-4 | VOCs | 3.74E+01 | 3.5E+00 | 1.1E+00 | 1.0E+03 | 1.64E+02 | 1.5E+01 | 4.9E+00 | 4.4E+03 |
| formaldehyde | 50-00-0 | VOCs | 7.20E+00 | 1.6E+04 | 2.2E-01 | 1.0E+01 | 3.14E+01 | 6.9E+04 | 9.4E-01 | 4.3E+01 |
| hexachlorobenzene | 118-74-1 | SVOCs | 2.03E-01 | 8.8E-02 | 6.1E-03 | - | 8.89E-01 | 3.8E-01 | 2.7E-02 | - |
| mercury (elemental) | 7439-97-6 | Metals | 1.04E+01 | 8.9E-01 | - | 3.1E-01 | 4.38E+01 | 3.7E+00 | - | 1.3E+00 |
| methyl ethyl ketone (butanone, 2-) | 78-93-3 | VOCs | 1.74E+05 | 2.2E+06 | - | 5.2E+03 | 7.30E+05 | 9.4E+06 | - | 2.2E+04 |
| methylene chloride | 75-09-2 | VOCs | 3.38E+03 | 7.6E+02 | 1.0E+02 | 6.3E+02 | 4.09E+04 | 9.2E+03 | 1.2E+03 | 2.6E+03 |
| naphthalene | 91-20-3 | PAHs | 2.75E+00 | 4.6E+00 | 8.3E-02 | 3.1E+00 | 1.20E+01 | 2.0E+01 | 3.6E-01 | 1.3E+01 |
| polychlorinated biphenyls; total PCBs (high risk) | 1336-36-3 | PCBs | 1.64E-01 | 2.9E-01 | 4.9E-03 | - | 7.15E-01 | 1.3E+00 | 2.2E-02 | - |
| polychlorinated biphenyls; total PCBs (low risk) | 1336-36-4 | PCBs | 9.36E-01 | 1.7E+00 | 2.8E-02 | - | 4.09E+00 | 7.2E+00 | 1.2E-01 | - |
| polychlorinated biphenyls; total PCBs (lowest risk) | 1336-36-5 | PCBs | 4.68E+00 | 8.3E+00 | 1.4E-01 | - | 2.04E+01 | 3.6E+01 | 6.1E-01 | - |
| propanol, 2- (isopropanol) | 67-63-0 | VOCs | 6.95E+03 | 6.3E+05 | - | 2.1E+02 | 2.92E+04 | 2.7E+06 | - | 8.8E+02 |
| tetrachloroethylene | 127-18-4 | VOCs | 3.60E+02 | 1.5E+01 | 1.1E+01 | 4.2E+01 | 1.57E+03 | 6.5E+01 | 4.7E+01 | 1.8E+02 |
| toluene | 108-88-3 | VOCs | 1.74E+05 | 1.9E+04 | - | 5.2E+03 | 7.30E+05 | 8.1E+04 | - | 2.2E+04 |
| total petroleum hydrocarbons (aliphatic low) | - | TPH | 6.95E+01 | 8.5E+00 | - | 6.3E+02 | 2.92E+02 | 3.6E+01 | - | 2.6E+03 |
| total petroleum hydrocarbons (aliphatic medium) | - | TPH | 1.59E+01 | 7.5E-01 | - | 1.0E+02 | 9.97E+01 | 3.2E+00 | - | 4.4E+02 |
| total petroleum hydrocarbons (aromatic low) | - | TPH | 2.09E+03 | 1.4E+02 | - | 3.1E+01 | 8.76E+03 | 5.8E+02 | - | 1.3E+02 |
| total petroleum hydrocarbons (aromatic medium) | - | TPH | 2.09E+03 | 1.6E+02 | - | 3.1E+00 | 8.76E+03 | 6.7E+02 | - | 1.3E+01 |
| trichlorobenzene, 1,2,4- | 120-82-1 | VOCs | 3.48E+03 | 3.6E+01 | - | 2.1E+00 | 1.46E+04 | 1.5E+02 | - | 8.8E+00 |
| trichloroethylene (see notes) | 79-01-6 | VOCs | 3.48E+03 | 1.2E+00 | 4.8E-01 | 2.1E+00 | 1.46E+04 | 7.4E+00 | 3.0E+00 | 8.8E+00 |
| trimethylbenzene; 1,2,4- | 95-63-6 | VOCs | 3.48E+03 | 2.5E+02 | - | 6.3E+01 | 1.46E+04 | 1.0E+03 | - | 2.6E+02 |
| trimethylbenzene; 1,3,5- | 108-67-8 | VOCs | 3.48E+03 | 1.8E+02 | - | 6.3E+01 | 1.46E+04 | 7.3E+02 | - | 2.6E+02 |
| xylene; m- | 108-38-3 | VOCs | 2.09E+04 | 3.6E+02 | - | 1.0E+02 | 8.76E+04 | 1.5E+03 | - | 4.4E+02 |
| xylene; o- | 95-47-6 | VOCs | 3.48E+03 | 4.9E+02 | - | 1.0E+02 | 1.46E+04 | 2.1E+03 | - | 4.4E+02 |
| xylene; p- | 106-42-3 | VOCs | 1.04E+03 | 3.7E+02 | - | 1.0E+02 | 4.38E+03 | 1.6E+03 | - | 4.4E+02 |
| xylenes (total) | 1330-20-7 | VOCs | 1.04E+02 | 3.9E+02 | - | 1.0E+02 | 4.38E+02 | 1.6E+03 | - | 4.4E+02 |

ug/L - microgram per liter
(µg/m³) - microgram per cubic meter

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 5a: Notes

| | |
|----|--|
| | A |
| 1 | <u>Following are notes related to all spreadsheets</u> |
| 2 | |
| 3 | Soil and Groundwater: MTCA values are not included in the Soil spreadsheet because MTCA includes only ingestion exposure, not dermal or inhalation, as EPA does, which results in consistently higher cleanup levels for MTCA than RSLs for EPA. For consistency, MTCA values also are not included in the Groundwater spreadsheet. |
| 4 | Significant Figures: To consistently use two significant figures across all spreadsheets, the aquatic life and human health WQS values are shown as two significant figures instead of three per the original sources. |
| 5 | Background Values: |
| | Surface Water -- Background concentrations for surface water via groundwater for three metals (As, Cu, Mn) were obtained from work on Boeing Plant 2 adjacent to the Lower Duwamish River Superfund site. (Environmental Partners, Inc., FLOYD SNIDER, Golder Associates Inc., 2006, Boeing Plant 2, Seattle/Tukwila, Washington, Technical Memorandum: Development and Use of |
| 6 | Background Values: Prepared for The Boeing Company, March 30) |
| 7 | Soil -- Background values were obtained from Puget Sound values provided in Table 7 in Ecology's October 1994 publication, "Natural Background Soil Metals Concentrations in Washington State" -- https://fortress.wa.gov/ecy/publications/summarypages/94115.html . |
| 8 | Aldrin and Dieldrin, Water: WAC 173-201A-240, Table 240 footnote e, states: "Aldrin is metabolically converted to Dieldrin. Therefore, the sum of the Aldrin and Dieldrin concentrations are compared with the Dieldrin criteria." |
| 9 | Hardness: For certain inorganic constituents (Cadmium, Chromium III, Copper, Lead, Nickel, and Zinc), aquatic fresh water acute surface water criteria (WAC and EPA AWQC) are hardness dependent and have been adjusted to the maximum hardness of 400 mg/L. See Chapter 173-201A WAC and EPA AWQC for calculations, and the following quote. |
| 10 | <i>"The WAC and EPA fresh water surface water criteria have been adjusted to hardness of 400 mg/L as CaCO3. The hardness of groundwater at R-P is as much as 1500 mg/L, while surface water criteria for hardness-based inorganics can be adjusted only up to 400 mg/L. Using values based on 400 mg/L runs the risk of overestimating these inorganics to aquatic species, as they are less toxic to aquatic life in harder water than they are in softer water. This tendency may be countered by a possible underestimation of total toxicity of the groundwater. This is because at such a high hardness as 1500 mg/L, the high calcium and magnesium concentrations may themselves begin to elicit toxicity. The higher anion concentrations in water of 1500 mg/L hardness, such as elevated carbonate and bicarbonate concentrations, combined with the elevated Ca and Mg concentrations, may result in an ionic strength of groundwater that is closer to that of estuarine water instead of fresh water. Such an elevated ionic strength in itself can adversely affect fresh water species, regardless of the concentration of metals such as Cd, Cu, Pb, etc."</i> [Courtesy of Burt Shephard, EPA R10 Risk Evaluation Branch, 02/10/2016] |
| 11 | Values are not available for certain compounds that have been reported analytically for this site, such as: |
| 12 | individual chlordane isomers (e.g., alpha-, gamma-); total cPAHs and total benzofluoranthenes; endosulfan I (alpha) and endosulfan II (beta) |
| 13 | Trichloroethylene (TCE): EPA Region 10 developed a guidance for addressing exposure to women of reproductive age, based on information in the IRIS documentation. https://ecology.wa.gov/DOE/files/33/33a04283-94c4-402d-a6be-220f05f32f7a.pdf Not-to-be-exceeded TCE concentrations are for average 21-day exposures to women of reproductive age and are to be evaluated separately from longer-term exposures to other populations. TCE concentrations for all media based on this exposure are not used as PRGs; rather, they should be considered for engineering and/or institutional controls. Groundwater: 3.4 ug/L; Residential Soil: 4.7 mg/kg HQ=1; Composite Worker Soil: 19.2 mg/kg HQ=1 |
| 14 | Vapor Intrusion: The Vapor Intrusion worksheet contains key outputs from EPA's Vapor Intrusion Screening Level Calculator for chemicals previously detected in soil and groundwater at the Former Rhone-Poulenc Facility. Only those chemicals available in the calculator and considered to be "sufficiently volatile and toxic to pose inhalation risk via vapor intrusion" were retained in this spreadsheet. https://www.epa.gov/vaporintrusion/vapor-intrusion-screening-level-calculator |
| 15 | <u>ONLINE SOURCES</u> |
| 16 | Water: |
| 17 | EPA Regional Screening Levels (RSLs), updated May 2020: https://www.epa.gov/risk/regional-screening-levels-rsls |
| 18 | Federal Maximum Contaminant Levels (MCLs): https://www.epa.gov/ground-water-and-drinking-water/table-regulated-drinking-water-contaminants |
| 19 | EPA National Recommended Water Quality Criteria (Aquatic Life and Human Health Organism Only) (aka Ambient Water Quality Criteria - AWQC) per Section 304(a) of Clean Water Act (CWA): https://www.epa.gov/wqc/national-recommended-water-quality-criteria |
| 20 | WA State Department of Ecology, Water Quality Standards applicable to surface waters in the State of WA for Aquatic Life and Human Health (Organism Only), WAC 173-201A, Table 240: https://apps.leg.wa.gov/WAC/default.aspx?cite=173-201A-240 https://www.epa.gov/sites/production/files/2014-12/documents/wawqs.pdf |
| 21 | EPA Region 10 Framework for Selecting and Using Tribal Fish and Shellfish Consumption Rates for Risk-Based Decision Making at CERCLA and RCRA Cleanup Sites in Puget Sound and the Strait of Georgia: https://www.epa.gov/guidance/framework-selecting-and-using-tribal-fish-and-shellfish-consumption-rates-risk-based |
| 22 | WA State Department of Ecology, Lower Duwamish Waterway Preliminary Cleanup Level Workbook (May 2020) and Supplemental Information (May 2020), available from Ecology's LDW webpage: https://apps.ecology.wa.gov/gsp/Sitepage.aspx?csid=1643 |
| 23 | Soil: |
| 24 | EPA Regional Screening Levels (RSLs), updated May 2020: https://www.epa.gov/risk/regional-screening-levels-rsls |
| 25 | WA State Department of Ecology, Lower Duwamish Waterway Preliminary Cleanup Level Workbook (May 2020) and Supplemental Information (May 2020), available from Ecology's LDW webpage: https://apps.ecology.wa.gov/gsp/Sitepage.aspx?csid=1643 |
| 26 | Vapor Intrusion: |
| 27 | EPA's Vapor Intrusion Screening Level Calculator: https://www.epa.gov/vaporintrusion/vapor-intrusion-screening-level-calculator |
| 28 | Sediment: |
| 29 | Record of Decision, Lower Duwamish Waterway Superfund Site, November 2014: https://semspub.epa.gov/work/10/715975.pdf |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 5a: Notes

| | |
|----|---|
| | A |
| 30 | Sediment cleanup levels based on protection of the benthic community in marine and low salinity sediment, WAC 173-204-562, Table III, Marine Sediment, Sediment Cleanup Objectives and Cleanup Screening Levels Chemical Criteria |

Updated Preliminary Remediation Goals for the Former Rhone-Poulenc Facility
Spreadsheet 5b: Acronyms

Acronyms

AWQC - Ambient Water Quality Criteria, EPA
CAS - Chemical Abstracts Service Registry Number
cPAH - carcinogenic polycyclic aromatic hydrocarbons
CWA - Clean Water Act
HHRAP - Human Health Risk Assessment Protocol, EPA
HPAH - high-molecular-weight PAH
HQ - hazard quotient
LDW - Lower Duwamish Waterway
LPAH - low-molecular-weight PAH
MCL - Federal Maximum Contaminant Level
MTCA - Model Toxics Control Act, WA State
PAH - polycyclic aromatic hydrocarbons
PCBs - polychlorinated biphenyls
PCUL - LDW Preliminary Cleanup Levels
RSL - Regional Screening Levels, EPA
SVOC - semivolatile organic compound
TCR - target cancer risk
THQ - target hazard quotient
TPH - total petroleum hydrocarbons
VISL - vapor intrusion screening level
VOC - volatile organic compound
WAC - WA Administrative Code
WQS - Water Quality Standards

Introduction

Corrective action is being conducted to clean up releases of hazardous waste and hazardous constituents at the former Rhone-Poulenc Facility (Facility) located at 9229 East Marginal Way South in Tukwila, Washington. This work is being performed by the current and former landowners under the oversight of the U.S. Environmental Protection Agency pursuant to Resource Conservation and Recovery Act (RCRA) Section 3008(h) Administrative Order on Consent No. 1091-11-20-3008(h) (Order), dated March 31, 1993, as amended.

This document establishes updated Preliminary Remediation Goals (PRGs) for the West Parcel of the Facility. The PRGs include preliminary cleanup levels for contaminants found in soil, groundwater, and sediment at the Facility. These values reflect up-to-date toxicity information and are consistent with the physical conditions and current and reasonably anticipated future exposure assumptions at the Facility. They are protective of human health and the environment. This document also identifies the points of compliance at which the PRGs must be met. This document supersedes PRGs previously published by the EPA in 2014 for this Facility.

Site History

The former Rhone-Poulenc Facility is located on about 750 feet of shoreline on the east side of the Lower Duwamish Waterway (LDW) just north of Slip 6, at approximately river mile 4.2. The West Parcel is bounded by the Museum of Flight and Raisbeck Aviation High School to the east, industrial property to the north, the LDW to the west, and Slip 6 to the south. Laucks Chemical Company began industrial operations at this site sometime prior to 1946. The Monsanto Industrial Chemicals Company purchased the property in 1946 and began operations at the plant, manufacturing a variety of chemical products including dry glues, resins, hardeners, and extenders. Monsanto also began producing vanillin (artificial vanilla) at the Facility in 1952. These manufacturing operations generated hazardous and nonhazardous byproducts. Rhone-Poulenc, Inc., purchased the Facility in 1986 and continued vanillin production until April of 1991, when chemical manufacturing operations ceased. In 1998, Container Properties, L.L.C. purchased the property for an intended use as a shipping center for ocean-going containers.

Investigation and cleanup of the Facility is being conducted under the above-referenced Order by former owners, including Solvay, Inc. (formerly Rhodia Inc.) and Bayer CropScience Inc. (corporate successors to the former Rhone-Poulenc company), and the current owner, Container Properties, L.L.C. These parties are collectively referred to as the Respondents. Investigations begun by the Respondents in 1985 detected releases of hazardous constituents to soil, groundwater, and sediments. Most of the contamination is located in the former processing and chemical storage areas.

Several interim cleanup measures have been conducted at the Facility. Polychlorinated biphenyls (PCBs) were removed from soils, process drains, and storm sewers at the Facility in 1995. A soil vapor extraction system was installed in 1999 and operated until 2002, removing an estimated 61,255 pounds of toluene and other volatile chemicals from the soil.

In July 2003, the Respondents constructed a subsurface barrier wall to prevent contaminated groundwater from continuing to discharge into the LDW. A groundwater pump-and-treat system provides additional groundwater control. The extracted groundwater is treated using granular activated carbon and discharged to the City of Tukwila sanitary sewer system. The barrier wall was designed to encircle the areas of historical releases to the extent possible but was constructed approximately 50 feet inland from the shoreline due to stability constraints and to allow for future shoreline habitat restoration. Contaminated soil and groundwater remain inside the barrier wall but contamination also is present in the soil, groundwater, and sediments outside the barrier wall along the LDW and Slip 6.

In 2006, the property underwent redevelopment and was split into two parcels. The East Parcel was extensively investigated. In December 2006, the EPA selected a final cleanup action for the East Parcel. The selected cleanup included removal of contaminated soils and installation of a biosparge/vent system to address an area where groundwater was contaminated with toluene above the cleanup standard. Soil removal was completed in 2006. The groundwater cleanup continued in a limited area in the southwest corner of the East Parcel. The EPA determined in 2017 that the East Parcel cleanup was fully complete with no controls required. This parcel was purchased and redeveloped by the Museum of Flight in 2006.

Manufacturing structures which remained on the West Parcel were demolished and removed from the site during the redevelopment in 2006. Several cleanup actions took place as part of this effort, including removal of areas of contaminated soil and waste materials in sumps and old pipelines. The West Parcel was regraded and paved as part of the redevelopment activities. It had been leased to Insurance Auto Auctions, Inc. for several years for the storage of wrecked cars but currently is vacant.

The PRGs established in this document provide the basis for evaluating and selecting a final comprehensive cleanup action for the West Parcel, including the uplands soil and groundwater, shoreline soils, and sediments.

Site Geology

The Rhone-Poulenc Facility was constructed on land that had been built up from the original tidal mudflat with about 10 feet of fill material. The fill materials consist generally of granular soil and sand with variable amounts of silt, gravel, and debris. Beneath the fill lies a fairly continuous unit of finer grained soils consisting of silt and silty sand. This finer grained unit has a thickness of approximately 8 to 15 feet and extends to a depth of 15 to 20 feet below ground surface. Beneath the finer grained unit is an interval of poorly graded sand. This layer dips gradually towards the southwest corner of the site and is located around 30 to 45 feet below ground surface. Beneath this lies a horizontally continuous unit of finer grained material consisting of silt, silty sands, and gravel to a depth of about 105 feet.

Two aquifers underlie the site: the Shallow Aquifer and the Deep Aquifer. The Shallow Aquifer is divided into upper and lower zones. The upper zone of the Shallow Aquifer is in the sandier layer and is found at approximately 15 to 40 feet below ground surface. The lower zone of the Shallow Aquifer is the siltier portion and is found at approximately 45 to 70 feet below ground surface. The Shallow Aquifer and Deep Aquifer are separated by a low-permeability silt aquitard. The top of the Deep Aquifer is approximately 83 feet below ground surface.

The Facility is bounded on two sides by the LDW and Slip 6 and includes several acres of tidal mudflats on the LDW side. The shorelines are armored with riprap. In this area, the LDW is a tidally-controlled marine embayment with a freshwater lens of outgoing river water on top of the denser marine water. The sediments have salinities consistent with the marine waters from Elliott Bay.

Tides influence water levels at the site in both the Shallow and Deep Aquifers. The response of water levels in the Shallow Aquifer to tidal cycles is evident in monitoring well DM-8, located outside the barrier wall, whereas water levels in monitoring wells located inside the barrier wall remain relatively constant. The water levels measured in DM-8 reflect the water levels in the LDW offshore of the Facility, even though the changes in water level in the well are not as large as those seen in the LDW.

Although the vertical gradients between the Shallow and Deep Aquifers are variable, the overall vertical gradients tend to be upwards. The groundwater elevations measured in the Deep Aquifer are typically 2 to 9 feet higher than the water levels in the Shallow Aquifer.

Before construction of the barrier wall, groundwater flowed across the site from east to west and discharged into the LDW through the sediments and seeps in the subtidal areas, with some groundwater discharging into Slip 6. The presence of the barrier wall now diverts the groundwater flow around the wall. The northern flow eventually enters the LDW while the southern flow enters Slip 6. Groundwater on the LDW side of the barrier wall is dominated by water level fluctuations in the LDW but is expected to be largely stagnant due to the barrier wall.

Site Investigations and Conclusions

Releases of hazardous waste and hazardous constituents have occurred at and from the Facility and are documented in the Order, the RCRA Facility Assessment (1990), and the RCRA Facility Investigation (1995). Recorded spills and materials disposed onto the ground between at least 1952 and 1980 included toluene, vanillin black liquor, autoclave solids, sulfite waste liquor, caustic soda, spent mineral oil containing phenolic compounds, compressor oil, lubricating oils, solvents, and copper-containing metals sludge used for weed control. At least 10 accidental spills and discharges to the LDW were documented between 1975 and 1989 as a result of loading/unloading of raw materials, byproducts, and waste liquids to and from barges, tank rail cars, and tank trucks. These spills involved contaminated surface and process waters, a paper sizing agent called Mersize, vanillin black liquor, sulfite waste liquor, and sodium hydroxide solution. Spills on the property may

have migrated through soils and plant drainage systems to river outfalls, groundwater, seeps, and sediments.

Monitoring and sampling investigations have documented the presence of hazardous constituents in the soils, groundwater, sediments, and pore water at the Facility. In addition to quarterly groundwater monitoring, investigations of the West Parcel include the following:

- 1986 – Site Screening Investigation, Dames and Moore
- 1990 – RCRA Facility Assessment, PRC Environmental for EPA
- 1991 – Site Assessment, Landau Associates
- 1995 – Final RCRA Facility Investigation Report, CH2M Hill
- 1996 – Round 3 Data and Sewer Sediment Technical Memorandum, RCRA Facility Investigation
- 1998 – Interim Measures Report, PCB Remediation & Sewer Cleaning, Rhodia, Inc.
- 2000 – Round 6 Groundwater Monitoring, AGI
- 2001 – Geoprobe Investigation Report, AGI
- 2006 – Revised Pre-Demolition Investigation Report, Geomatrix Consultants
- 2006 – Voluntary Interim Measure Report, Hazardous Waste Storage Area and Transformer A Area Cleanup, Geomatrix Consultants
- 2007 – West Parcel Redevelopment Report, Geomatrix Consultants
- 2007 – Northwest Corner Affected Soil Removal Report, Geomatrix Consultants
- 2012 – Sediment Characterization Data Report, AMEC Environment & Infrastructure, Inc.
- 2012 – Shoreline Soil and Groundwater Characterization Data Report, AMEC Environment & Infrastructure, Inc.

The primary hazardous constituents known to be present at the Facility include toluene, copper, and elevated pH due to release of caustic materials. Additional contaminants include PCBs, polycyclic aromatic hydrocarbons, semivolatile organic compounds, and several metals. A complete list of hazardous constituents and their maximum concentrations detected in soil, groundwater, and sediments at the Facility is provided in Attachment 1.

These hazardous constituents are present throughout the soil and groundwater at the Facility, including within and outside the barrier wall. Groundwater monitoring conducted at the Facility confirms that a number of metals and organic contaminants have discharged from the groundwater to the LDW and sediments. Sediments contaminated with PCBs, benzyl alcohol, and other constituents were shown to be present in historic sewers which discharged to the LDW. Sampling in 2012 confirmed that site-related contaminants of concern (COCs) at levels which exceed their respective PRGs are found in the pore water and sediments adjacent to the Facility.

Basis for PRGs

The EPA's policy is that "current and reasonable expected future land use and corresponding exposure scenarios should be considered in both the selection and timing of remedial actions" (61 Federal Register 19452, May 1, 1996). Specifically, the EPA expects to remediate contaminated

soils and sediments as necessary to prevent or limit direct exposure of humans and environmental receptors and prevent the transfer of unacceptable concentrations of contaminants (e.g., via leaching, runoff, or airborne emissions) from soils, including subsoils, to any media. The EPA also expects to return usable groundwater to its maximum beneficial use wherever practicable, within a time frame that is reasonable given the particular circumstances of the site. Highest beneficial use of groundwater is generally considered to be potable water (i.e., drinking water). Where groundwater is determined to be non-potable, an alternative highest beneficial use (e.g., protection of surface water) must be evaluated. When restoration of groundwater is not practicable, the EPA expects to prevent or minimize further migration of the plume, prevent exposure to the contaminated groundwater, and evaluate further risk reduction. The EPA also expects to control or eliminate surface and subsurface sources of groundwater contamination.

The EPA considered the following factors in developing these PRGs:

- The Facility is located in an industrial area along the LDW and includes contaminated soil, groundwater, pore water, and sediment. The Facility and immediate surroundings are zoned Manufacturing/Industrial.
- Tribes have fished from the Duwamish River for centuries and have Treaty-guaranteed fishing rights. Northwest tribal populations are known to consume locally harvested fish and shellfish at a higher rate than the general United States population.
- Commercial and recreational fishing occurs in the LDW.
- Recreational activities in the LDW include kayaking, canoeing, and motor boating.
- The LDW is not designated as a potential drinking-water source. Numerical surface water standards for protection of human health are based on consumption of fish and shellfish, and do not include drinking surface water.
- Salmon, ospreys, otters, and other wildlife live in, along, or migrate through the LDW. Ecological receptors include benthic organisms, fish, birds, and mammals. Potential exposure pathways for benthic organisms include direct contact with contaminated sediment and ingestion of contaminated sediment. The primary potential exposure pathway for fish, birds, and mammals is ingestion of other marine organisms and sediment particles. Bottomfish may have additional exposure due to direct contact with or ingestion of contaminated sediment. Risks to benthic organisms, fish, birds, and mammals from exposure to contaminated sediment, surface water, and prey will be reduced by reducing soil, water, and sediment contaminant concentrations.
- As the LDW has a thin freshwater lens of outgoing river water on top of the denser marine waters, both marine and freshwater aquatic standards were considered.
- There are currently no drinking water wells at the Facility and none are expected to be installed in the future, but there have been no determinations per the EPA's or the State of Washington's criteria to demonstrate that the groundwater is non-potable.
- Groundwater outside the barrier wall discharges to the surface waters and sediments of the LDW through seeps and pore water.
- Groundwater enclosed within the barrier wall could discharge to the surface waters and sediments of the LDW through seeps and pore water should the wall leak or be breached.
- Human and ecological exposures could occur to soils located between the security fence and the LDW.

- While most of the West Parcel is currently surrounded by a security fence and covered by asphalt pavement, workers could be exposed to contaminants in the soil while conducting trenching or other subsurface work.
- Surface soils outside the barrier wall can contribute contamination to the sediments or directly to the water column through surficial erosion or slumping.
- The site does not currently include any enclosed structures such as office buildings with a potential for exposure due to vapor intrusion from contaminated groundwater or soil.
- The LDW shoreline may be converted to habitat uses.

The spreadsheets in Attachment 2 present the PRGs for those constituents which have been detected in soil, groundwater, and sediments at the Facility. These PRGs will be used to refine the COCs to be evaluated in the upcoming Corrective Measures Study (CMS). Actual cleanup levels and points of compliance will be determined during the CMS process. It is possible that COCs may be added or removed for specific areas or throughout the facility as will be further determined in the CMS. In this document, the EPA has made an overall effort to develop PRGs that are consistent with the LDW Superfund cleanup and with EPA risk assessment and RCRA guidance and policy.

Preliminary Remediation Goals for Groundwater

Groundwater PRGs are presented for two scenarios: where groundwater is considered potentially potable for future drinking water purposes; and where protection of surface water (in this case, from groundwater discharge) is considered the highest beneficial use. Best professional judgment will be required for determining which of the two scenarios predominates from one area to another within the Facility. Generally, the PRGs for potable groundwater apply throughout the Facility and plume, and the PRGs for groundwater to protect surface water apply along the network of monitoring wells along Slip 6 and the LDW.

Groundwater to Protect Drinking Water

Groundwater PRGs must be protective of potential future use of the groundwater itself, i.e., for drinking water or industrial uses. PRGs for potable groundwater apply throughout the Facility and plume.

According to EPA policy as stated in “Guidelines for Ground-Water Classification Under the EPA Ground-Water Protection Strategy” (EPA 1988), all groundwaters are presumed to meet both the yield and quality criteria for a current or potential source of drinking water (Class II) unless a successful Class III demonstration is performed. Class III groundwater is determined to not be a potential source of drinking water or has limited beneficial use following the criteria in the guidelines. In addition, potability may be determined empirically using criteria in Washington Administrative Code (WAC) 173-340-720(2). There have been no determinations using the federal or state criteria to demonstrate that the groundwater is Class III or non-potable. Therefore, drinking water at the Facility is assumed to be the highest beneficial use of groundwater, and the drinking water criteria listed below have been included in the PRGs for this Facility.

The following water quality criteria were used to develop the PRGs for groundwater to protect drinking water:

- Federal Maximum Contaminant Levels.
- EPA Regional Screening Levels for tap water, updated May 2020.

Groundwater to Protect Surface Water

Although surface water is not a contaminated medium at the Facility, PRGs must be protective of surface water concentrations that are protective of human health and aquatic species. Groundwater PRGs for protection of surface water must be met at the monitoring well network located along the LDW and Slip 6.

The PRGs for three metals (arsenic, copper, and manganese) are values of “LDW background.” These metals occur naturally at levels which exceed the risk-based PRGs. These background levels are based on data that were approved by the EPA in 2006 for use along the LDW (Environmental Partners, Inc., 2006), developed in relation to the nearby Boeing Plant 2 RCRA corrective action facility.

The high pH of groundwater at this facility was taken into consideration as water hardness in calculating certain inorganic PRGs for groundwater discharging to surface water. See the Notes spreadsheet in Attachment 2 for more information.

The following surface water quality criteria protective of aquatic species were used to develop the PRGs for groundwater to protect surface water:

- EPA National Recommended Water Quality Criteria (aka Ambient Water Quality Criteria – AWQC) for protection of aquatic life in surface water per Section 304(a) of the Clean Water Act (CWA), updated in 2015 and 2016.
- Washington (WA) State Department of Ecology Water Quality Criteria applicable to surface waters in the State of WA for protection of aquatic life, WAC 173-201A, updated in 2016.

The following surface water quality criteria protective of human health consumption of organisms were used to develop the PRGs for groundwater to protect surface water:

- EPA National Recommended Water Quality Criteria (aka Ambient Water Quality Criteria - AWQC) for protection of human health (organism only) in surface water, Section 304(a) of the Clean Water Act (CWA), updated in 2015 and 2016.
- WA State Department of Ecology Water Quality Criteria applicable to surface waters in the State of WA for protection of human health (organism only), WAC 173-201A, updated in 2016.

- Tribal Fish and Shellfish Consumption per EPA Region 10's "Framework for Selecting and Using Tribal Fish and Shellfish Consumption Rates for Risk-Based Decision Making at CERCLA and RCRA Cleanup Sites in Puget Sound and the Strait of Georgia."

Tribal Fish and Shellfish Consumption

Surface water PRGs protective of human health based on consumption of fish and shellfish were calculated on a chemical-specific basis consistent with EPA risk assessment standard practice and guidance. The calculations are based on exposure assumptions for Tribal and Asian and Pacific Islander populations which consume higher rates of fish from the LDW than the general population. The calculated values, equations, and inputs for the calculations are presented in Attachment 2.

One exposure assumption in the equations is consumption rates for fish and shellfish. In 2007, the EPA published the document "Framework for Selecting and Using Tribal Fish and Shellfish Consumption Rates for Risk-Based Decision Making at CERCLA and RCRA Cleanup Sites in Puget Sound and the Strait of Georgia." The Framework provides a recommended approach to selecting tribal fish and shellfish consumption rates for purposes of estimating site-related risks and calculating site-specific cleanup levels at EPA hazardous waste cleanup sites.

These PRGs are calculated based on the Tulalip Tribes' consumption rate adjusted for resident fish and shellfish only. Using the Framework, this decision was based upon the following assumptions:

- The Tulalip Tribes' consumption rate is likely to be more appropriate for the LDW area than the Suquamish Tribe's higher rate, because the LDW is unlikely to have sufficient intertidal shellfish habitat to sustain the higher rate of shellfish consumption of the Suquamish Tribe.
- All fish and shellfish harvested from outside Puget Sound are assumed to not be contaminated by releases from the Facility.
- The chemicals present in the tissues of adult salmon in the LDW are assumed to result largely from exposures at remote locations in Puget Sound or the open ocean.

The total fish and shellfish consumption rate for the Tulalip Tribes, based on a 95th percentile consumer-only consumption rate for benthic fish, pelagic fish, shellfish and salmon is 243 g/day. Assuming consumption of resident-only fish and shellfish, the effective consumption rate used for the former Rhone-Poulenc Facility is 98 g/day. The tribal exposure duration is assumed to be 70 years to account for a lifetime of eating fish and shellfish from a specific harvesting area. The average body weight of the adult participants in the study, 81.8 kg, is also used. The consumption rate for children is estimated to be 39 g/day, which is 40 percent of the adult rate. EPA risk assessment practice calls for exposure to be time-weighted for different life phases, and the resulting risk from both childhood and adult exposure periods be averaged over a 70-year presumed lifetime.

Also accounted for are the seafood consumption rates of Asian and Pacific Islanders who harvest from the LDW and Elliott Bay and may be exposed to chemical releases from the Facility. The EPA funded and participated in a study (EPA, 1999) to estimate the amount and types of seafood consumed by the Asian and Pacific Islander population in King County. The 95th percentile total seafood Asian and Pacific Islander consumption rate is 305.7 g/day. The seafood harvested and

consumed by Asian and Pacific Islanders only from King County waters was estimated and assumed to be the amount of seafood potentially affected by the Facility releases. This amount, for adults, is 51.5 g/day, extrapolated to a child rate of 21 g/day based on 40 percent of the adult rate. The average adult study participant body weight of 63 kg was used. As the EPA had no information regarding exposure duration based on consistency in harvesting from certain areas over a lifetime, the standard exposure duration of 30 years was used for this population.

The EPA determined that the calculations result in more protective surface water concentrations when the tribal fish consumption numbers are used relative to the Asian and Pacific Islanders' consumption numbers. The tribal results are therefore considered protective for both populations.

Groundwater to Protect Sediment

The PRGs consider the partitioning of groundwater contamination to sediment. Like the Groundwater to Protect Surface Water scenario, groundwater PRGs for protection of sediment must be met at the monitoring well network located along the LDW and Slip 6. These groundwater PRGs include values from:

- Ecology's Lower Duwamish Waterway Preliminary Cleanup Level (PCUL) Workbook and Supplemental Information, dated December 2020.

The values in the LDW PCUL document were developed consistent with the cleanup levels in the LDW ROD. These groundwater-to-protect-sediment values are relevant to the Facility because of the environmental transport pathways to sediment in the LDW. Specifically, PCUL number GW-3 applies as the protection of sediment via groundwater transport pathway.

Preliminary Remediation Goals for Soil

Direct Exposure to Soil

The PRGs for soil apply throughout the vadose zone (approximately the upper 11 feet below ground surface). The PRGs address ingestion, inhalation, and dermal absorption for residential and industrial exposures. Also presented are values for protection of sediment and groundwater. If a corrective measure can achieve the PRGs provided for unrestricted use, restrictions on use of the property will not be needed. If a corrective measure cannot achieve the unrestricted use PRGs but can achieve the PRGs for restricted use, institutional or controls to restrict future uses of the property as appropriate will be required.

PRGs for direct contact with soils, including ingestion, dermal, and inhalation of dust, were developed from the following source:

- EPA Regional Screening Levels for residential soil and composite worker soil (cancer risk = $1E-6$, HQ = 1), updated May 2020.

Puget Sound Background

Several soil background values for metals in soil in Puget Sound were obtained from Ecology's October 1994 publication, "Natural Background Soil Metals Concentrations in Washington State."

Shoreline Soils to Protect Sediment

The PRGs for shoreline soils apply throughout the vadose zone (approximately the upper 11 feet below ground surface) from the barrier wall to the tideflats. In addition to being protective for direct contact, the soils along the shoreline must be protective of the sediment from contamination caused by erosion and sloughing of contaminated bank soils directly to the sediment. Therefore, the soil PRGs at the shoreline include values from:

- EPA Regional Screening Levels for residential soil and composite worker soil (cancer risk = $1E-6$, HQ = 1), updated May 2020.
- Ecology's Lower Duwamish Waterway Preliminary Cleanup Level (PCUL) Workbook and Supplemental Information, dated December 2020.

The values in the LDW PCUL document were developed consistent with the cleanup levels in the LDW ROD. These shoreline soils to protect sediment values apply to the Facility because of the environmental transport pathways from the upland portion of the Facility to sediment in the LDW. Specifically, PCUL number SL-8 applies as the protection of sediment via bank erosion transport pathway.

Soil to Protect Groundwater

A potential exposure pathway also exists in areas of contaminated soils for contaminants to leach from soil into the groundwater. Target cleanup concentrations of site-related contaminants in subsurface soils that are protective of groundwater must be considered based on specific conditions in the area of contamination. For example, these values would not apply to an area of contaminated soil if groundwater beneath or in contact with it is not impacted by that soil contaminant.

Soil concentrations that would be protective of groundwater directly beneath any soil contamination are presented in the soils PRG spreadsheet. No attempt has been made to attenuate contamination with groundwater migration or to account for the location of the shoreline relative to the location of the soil contamination. The soil to protect groundwater values were obtained from:

- EPA's Regional Screening Levels Residential Soil to Groundwater, updated May 2020.

Vapor Intrusion

Attachment 2 includes a spreadsheet of key outputs from EPA's Vapor Intrusion Screening Level Calculator for chemicals previously detected in soil, groundwater, and sediment at the former

Rhone-Poulenc Facility. Only those chemicals available in the calculator and demonstrated to be "sufficiently volatile and toxic to pose inhalation risk via vapor intrusion" from soil or groundwater sources per the calculator output were retained in this spreadsheet.

These outputs are for future consideration for vapor intrusion from soil gas or groundwater to indoor air in buildings that may be constructed in the future. These values are for use in making decisions regarding the potential need for additional studies to establish engineering or institutional controls if buildings are constructed at the Facility. Concentrations of site-related contaminants in subsurface media that are protective of indoor air concentrations must be determined or estimated based on building-specific and subsurface-specific conditions and may change as subsurface contaminant concentrations change over time.

Preliminary Remediation Goals for Sediments

Contamination in the LDW is being cleaned up under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA, 42 U.S.C. 9601 et seq. as amended). In November 2014 the EPA published the *Record of Decision, Lower Duwamish Waterway Superfund Site*, which presents the EPA's selected remedy for in-waterway cleanup in the LDW. The ROD includes an analysis of the human health and environmental risks posed by contaminants located in the LDW sediments.

The Facility includes an area of privately-owned tideflats. Contamination found on the Facility's property is subject to the requirements of the Order which requires cleanup of contaminants released or migrated from the Facility. However, the contaminants found in the tideflats and in-waterway sediments are not unique to this Facility. For this reason, cleanup of the privately-owned tideflats is being required under the Order, and any contribution the Facility may have made to the rest of the LDW will be managed through CERCLA.

The Facility's privately-owned tideflats contain contaminants that have been detected in the soil and groundwater at the Facility and therefore are known to be site-related contaminants. Sediment PRGs for protection of human health and the environment for PCBs, SVOCs, metals, and other contaminants detected at the Facility are presented in Attachment 2. These PRGs are from the LDW ROD Tables 19 and 20; and WAC 173-204-562, Table III, Marine Sediment, Sediment Cleanup Objectives and Cleanup Screening Levels Chemical Criteria.

References

AGI Technologies, 2000, Round 6 Groundwater Monitoring, Rhone-Poulenc Marginal Way Facility, Tukwila, Washington, January 14

AGI Technologies, 2001, Summer 2001 Geoprobe Investigation Report, Former Rhone-Poulenc East Marginal Way Facility, Tukwila, Washington, October 8

AMEC Environment & Infrastructure, Inc., 2012, Sediment Characterization Data Report, Former Rhone-Poulenc Site, Tukwila, Washington: Prepared for Container Properties, L.L.C., Kent, Washington, April 19

AMEC Environment & Infrastructure, Inc., 2012, Shoreline Soil and Groundwater Characterization Data Report, Former Rhone-Poulenc Site, Tukwila, Washington: Prepared for Container Properties, L.L.C., Kent, Washington, March 12

CH2M Hill, 1995, Final RCRA Facility Investigation Report, June 19

Dames & Moore, 1986, Report of Site Conditions and Waste Characterization for Monsanto Company, Seattle, Washington, July 2

Environmental Partners, Inc., FLOYD|SNIDER, Golder Associates Inc., 2006, Boeing Plant 2, Seattle/Tukwila, Washington, Technical Memorandum: Development and Use of Background Values: Prepared for The Boeing Company, March 30

Geomatrix Consultants, 2006, Revised Pre-Demolition Investigation Report, Former Rhone-Poulenc Site, Tukwila, Washington: Prepared for Davis Property & Investment, May 8

Geomatrix Consultants, 2006, Voluntary Interim Measure Report, Hazardous Waste Storage Area and Transformer A Area Cleanup, Former Rhone-Poulenc Site, Tukwila, Washington: Prepared for Davis Property & Investment, August 18

Geomatrix Consultants, 2007, West Parcel Redevelopment Report, Former Rhone-Poulenc Site, Tukwila, Washington: Prepared for Container Properties, L.L.C., Tukwila, Washington, January

Geomatrix Consultants, 2007, Northwest Corner Affected Soil Removal Report, Former Rhone-Poulenc Site, Tukwila, Washington: Prepared for Container Properties, L.L.C., May 23

Landau Associates, 1991, Site Assessment, Rhone-Poulenc Facility, Tukwila, Washington: Prepared for Boeing Environmental Affairs, September 10

PRC Environmental Management, 1990, Rhone-Poulenc, Inc. Marginal Way Facility, Seattle, Washington, RCRA Facility Assessment, March 19

Rhodia, 1998, Interim Measures Report, PCB Remediation & Sewer Cleaning, East Marginal Way Facility, Tukwila, Washington, April 1

Rhone-Poulenc, Inc., 1995, RCRA Facility Investigation (RFI) Report for the Marginal Way Facility, Tukwila, Washington, June 19

Rhone-Poulenc, Inc., 1996, RCRA Facility Investigation, Round 3 Data and Sewer Sediment Technical Memorandum, December 24

U.S. Environmental Protection Agency, 1988, Guidelines for Ground-Water Classification Under the EPA Ground-Water Protection Strategy

U.S. Environmental Protection Agency, 1999, Asian and Pacific Islander Seafood Consumption Study, EPA 910/R-99-003

U.S. Environmental Protection Agency, Region 10, 2007, Framework for Selecting and Using Tribal Fish and Shellfish Consumption Rates for Risk-Based Decision Making at CERCLA and RCRA Cleanup Sites in Puget Sound and the Strait of Georgia, August

U.S. Environmental Protection Agency, Region 10, 2014, Record of Decision, Lower Duwamish Waterway Superfund Site, November

Washington State Department of Ecology, 1994, Natural Background Soil Metals Concentrations in Washington State, October

Attachment 2

Hazardous Constituents Detected in Soil, Groundwater, and Sediments

- Table 1: Summary of Constituents Detected in Groundwater and Soil
- Table 2: Summary of Constituents Detected in Sediment
- Table 3: Sediment Characterization Data Report, 2012
- Table 4: Shoreline Soil and Groundwater Characterization Data Report, 2012
- Table 5: Northwest Corner Affected Soil Removal Report, 2007
- Table 6: Voluntary Interim Measure Report Hazardous Waste Storage Area and Transformer A Area Cleanup, 2006
- Table 7: Revised Pre-Demolition Investigation Report, 2006
- Table 8: Round 6 Groundwater Monitoring, 2000
- Table 9: Interim Measures Report, PCB Remediation & Sewer Cleaning, 1998
- Table 10: RCRA Facility Investigation, Round 3 Data and Sewer Sediment Technical Memorandum, 1996
- Table 11: RCRA Facility Investigation (RFI) Report, 1995

Table 1
Summary of Constituents Detected in Groundwater and Soil
Rhone-Poulenc, Inc., Marginal Way Facility, West Parcel

| Constituent | Maximum Groundwater Concentration | | | Maximum Soil Concentration | | |
|------------------------|-----------------------------------|-------|-----------|----------------------------|-------|---------------------|
| | | Units | Reference | | Units | Reference |
| Aluminum | 880,000 | µg/L | AMEC 2012 | 19,700 | mg/kg | Rhone-Poulenc, 1995 |
| Antimony | | | | 21.2 | mg/kg | Rhone-Poulenc, 1995 |
| Arsenic | 107 | µg/L | AMEC 2012 | 61.4 | mg/kg | Rhone-Poulenc, 1995 |
| Barium | 63 | µg/L | AGI, 2000 | 169 | mg/kg | Geomatrix, 2007 |
| Beryllium | | | | 1.10 | mg/kg | Rhone-Poulenc, 1995 |
| Cadmium | 6.0 | µg/L | AMEC 2012 | 5.0 | mg/kg | Rhone-Poulenc, 1995 |
| Calcium | | | | 34,400 | mg/kg | Rhone-Poulenc, 1995 |
| Chromium | 2,590 | µg/L | AMEC 2012 | 64.9 | mg/kg | Rhone-Poulenc, 1995 |
| Cobalt | | | | 28.7 | mg/kg | Rhone-Poulenc, 1995 |
| Copper | 1,880 | µg/L | AMEC 2012 | 18,200 | mg/kg | Geomatrix, 2007 |
| Iron | | | | 50,400 | mg/kg | Rhone-Poulenc, 1995 |
| Lead | 196 | µg/L | AMEC 2012 | 116 | mg/kg | Rhone-Poulenc, 1995 |
| Magnesium | | | | 15,100 | mg/kg | Rhone-Poulenc, 1995 |
| Manganese | | | | 941 | mg/kg | Rhone-Poulenc, 1995 |
| Mercury | 9.76J | µg/L | AMEC 2012 | 268 | mg/kg | Rhone-Poulenc, 1995 |
| Nickel | 610 | µg/L | AMEC 2012 | 65.7 | mg/kg | Rhone-Poulenc, 1995 |
| Potassium | | | | 902 | mg/kg | Rhone-Poulenc, 1995 |
| Selenium | | | | 0.8J | mg/kg | Geomatrix, 2007 |
| Silver | 0.4 | µg/L | AGI, 2000 | 3.5 | mg/kg | Rhone-Poulenc, 1995 |
| Sodium | | | | 4,200 | mg/kg | Rhone-Poulenc, 1995 |
| Tin | 60 | µg/L | AGI, 2000 | | | |
| Vanadium | 4,290 | µg/L | AMEC 2012 | 185 | mg/kg | Rhone-Poulenc, 1995 |
| Zinc | 2,770 | µg/L | AMEC 2012 | 1,990 | mg/kg | Rhone-Poulenc, 1995 |
| | | | | | | |
| Acetone | 120 | µg/L | AMEC 2012 | 13.0 | mg/kg | Rhone-Poulenc, 1995 |
| Benzene | 130 | µg/L | AGI 2000 | 0.23 | mg/kg | Rhone-Poulenc, 1995 |
| Bromoform | | | | 0.002 | mg/kg | Rhone-Poulenc, 1995 |
| 2-Butanone | | | | 1.1 | mg/kg | Rhone-Poulenc, 1995 |
| sec-Butylbenzene | | | | 0.0008J | mg/kg | AMEC 2012 |
| Carbon disulfide | 1.7 | µg/L | AMEC 2012 | 0.038 | mg/kg | AMEC 2012 |
| 1,4-Dichlorobenzene | 0.1J | µg/L | AMEC 2012 | | | |
| cis-1,2-Dichloroethene | 0.4 | µg/L | AMEC 2012 | 0.0025 | mg/kg | AMEC 2012 |
| Ethylbenzene | 100 | µg/L | AGI 2000 | 6.4 | mg/kg | Rhone-Poulenc, 1995 |
| Formaldehyde | | | | 3.4 | mg/kg | Rhone-Poulenc, 1995 |
| 4-Isopropyl toluene | 2.2 | µg/L | AMEC 2012 | 0.024 | mg/kg | AMEC 2012 |

Table 1, continued

**Summary of Constituents Detected in Groundwater and Soil
Rhone-Poulenc, Inc., Marginal Way Facility, West Parcel**

| Constituent | Maximum Groundwater Concentration | | | Maximum Soil Concentration | | |
|-----------------------------|-----------------------------------|-------|-----------|----------------------------|-------|---------------------|
| | | Units | Reference | | Units | Reference |
| Methylene chloride | 4.1 | µg/L | AMEC 2012 | 1.6 | mg/kg | Rhone-Poulenc, 1995 |
| Tetrachloroethene | | | | 0.0017J | mg/kg | AMEC 2012 |
| Toluene | 570,000 | µg/L | AGI 2000 | 4,900 | mg/kg | Rhone-Poulenc, 1995 |
| Trichloroethene | | | | 0.2 | mg/kg | Rhone-Poulenc, 1995 |
| 1,2,4-Trimethylbenzene | 1.1 | µg/L | AGI 2000 | | | |
| 1,3,5-Trimethylbenzene | 0.2J | µg/L | AMEC 2012 | | | |
| Xylene (total) | 92 | µg/L | AGI 2000 | 13 | mg/kg | Rhone-Poulenc, 1995 |
| m,p-Xylene | 1.8J | µg/L | AMEC 2012 | 0.0015 | mg/kg | AMEC 2012 |
| o-Xylene | 0.9J | µg/L | AMEC 2012 | | | AMEC 2012 |
| Acenaphthene | | | | 0.13 | mg/kg | Rhone-Poulenc 1995 |
| Acenaphthylene | | | | 0.0037 | mg/kg | Geomatrix 2007 |
| Anthracene | | | | 0.26 | mg/kg | Rhone-Poulenc 1995 |
| Benzo[a]anthracene | | | | 0.46 | mg/kg | Rhone-Poulenc 1995 |
| Total Benzo(a)fluoranthenes | | | | 0.10 | mg/kg | AMEC 2012 |
| Benzo(b)fluoranthene | | | | 0.72 | mg/kg | Rhone-Poulenc 1995 |
| Benzo(k)fluoranthene | | | | 0.59 | mg/kg | Rhone-Poulenc 1995 |
| Benzo[ghi]perylene | | | | 0.41 | mg/kg | Rhone-Poulenc 1995 |
| Benzo(a)pyrene | | | | 0.65 | mg/kg | Rhone-Poulenc 1995 |
| Benzoic acid | | | | 0.098J | mg/kg | AMEC 2012 |
| Benzyl alcohol | 17 | µg/L | AGI 2000 | 0.19 | mg/kg | Rhone-Poulenc 1995 |
| Bis(2-ethylhexyl)phthalate | | | | 6.8 | mg/kg | Rhone-Poulenc 1995 |
| Butyl benzyl phthalate | | | | 0.023 | mg/kg | Geomatrix 2007 |
| Carbazole | | | | 0.17 | mg/kg | Rhone-Poulenc 1995 |
| Chrysene | | | | 0.84 | mg/kg | Rhone-Poulenc 1995 |
| Dibenz(a,h)anthracene | | | | 0.016J | mg/kg | AMEC 2012 |
| Dibenzofuran | | | | 0.12 | mg/kg | AMEC 2012 |
| 2,4-Dimethylphenol | 0.8J | µg/L | AGI 2000 | 0.29 | mg/kg | Rhone-Poulenc 1995 |
| Di-n-butyl phthalate | | | | 0.43 | mg/kg | Rhone-Poulenc 1995 |
| Fluoranthene | | | | 1.8 | mg/kg | Rhone-Poulenc 1995 |
| Fluorene | | | | 0.15 | mg/kg | Rhone-Poulenc 1995 |
| Indeno(1,2,3-cd)pyrene | | | | 0.44 | mg/kg | Rhone-Poulenc 1995 |
| 2-Methylnaphthalene | | | | 0.1 | mg/kg | Rhone-Poulenc 1995 |
| 2-Methylphenol | 220E | µg/L | AGI 2000 | 7.5 | mg/kg | Rhone-Poulenc 1995 |
| 4-Methylphenol | 170E | µg/L | AGI 2000 | 5.1 | mg/kg | Rhone-Poulenc 1995 |

| Table 1, continued Summary of Constituents Detected in Groundwater and Soil Rhone-Poulenc, Inc., Marginal Way Facility, West Parcel | | | | | | |
|--|-----------------------------------|-------|-----------|----------------------------|-------|--------------------|
| Constituent | Maximum Groundwater Concentration | | | Maximum Soil Concentration | | |
| | | Units | Reference | | Units | Reference |
| Naphthalene | 0.3MJ | µg/L | AGI 2000 | 0.29 | mg/kg | Rhone-Poulenc 1995 |
| Pentachlorophenol | 3.2J | µg/L | AGI 2000 | 4.9 | mg/kg | Rhone-Poulenc 1995 |
| Phenanthrene | | | | 1.4 | mg/kg | Rhone-Poulenc 1995 |
| Phenol | | | | 6.2 | mg/kg | Rhone-Poulenc 1995 |
| 1,4-Phenylenediamine | 12Y | µg/L | AGI 2000 | | | |
| 2-Propanol | | | | 10 | mg/kg | Rhone-Poulenc 1995 |
| Pyrene | | | | 1.5 | mg/kg | Rhone-Poulenc 1995 |
| 2,4,5-Trichlorophenol | | | | 0.0079 | mg/kg | Geomatrix 2007 |
| Vanillin | | | | 450 | mg/kg | Rhone-Poulenc 1995 |
| Total cPAHs | | | | 0.106 | mg/kg | Geomatrix 2007 |
| | | | | | | |
| Alpha chlordane | | | | .018 | mg/kg | Rhone-Poulenc 1995 |
| 4,4'-DDD | | | | 0.2 | mg/kg | Rhone-Poulenc 1995 |
| 4,4'-DDE | | | | 0.62 | mg/kg | Rhone-Poulenc 1995 |
| 4,4'-DDT | | | | 2.6 | mg/kg | Rhone-Poulenc 1995 |
| Dieldrin | | | | 0.0095 | mg/kg | Rhone-Poulenc 1995 |
| Endosulfan I | | | | 0.0065 | mg/kg | Rhone-Poulenc 1995 |
| Endosulfan II | | | | 0.024 | mg/kg | Rhone-Poulenc 1995 |
| Endosulfan sulfate | | | | 0.0096 | mg/kg | Rhone-Poulenc 1995 |
| Endrin | | | | 0.022 | mg/kg | Rhone-Poulenc 1995 |
| Endrin aldehyde | | | | 0.11 | mg/kg | Rhone-Poulenc 1995 |
| Endrin ketone | | | | 0.019 | mg/kg | Rhone-Poulenc 1995 |
| Gamma-chlordane | | | | 0.026 | mg/kg | Rhone-Poulenc 1995 |
| Methoxychlor | | | | 0.04 | mg/kg | Rhone-Poulenc 1995 |
| PCBs (Arochlor 1254) | | | | 1,588.71 | mg/kg | Rhodia 1998 |
| | | | | | | |
| TPH-DRO | | | | 2,100 | mg/kg | Geomatrix 2007 |
| TPH-GRO | | | | 13,000 | mg/kg | Geomatrix 2007 |
| TPH-RRO | | | | 470 | mg/kg | Geomatrix 2007 |

Table 2
Summary of Constituents Detected in Sediment
Rhone-Poulenc, Inc., Marginal Way Facility, West Parcel

| Constituent | AMEC 2012 Sampling | | Rhone-Poulenc 1995 Sampling | |
|----------------------|-----------------------|--------------|-----------------------------|-------|
| | Maximum Concentration | Units | Maximum Concentration | Units |
| Aluminum | | | 22,600 | mg/kg |
| Arsenic | 28.9 | mg/kg | 9.9 | mg/kg |
| Barium | | | 56.1 | mg/kg |
| Beryllium | | | 0.81 | mg/kg |
| Cadmium | 2.9 | mg/kg | 0.4 | mg/kg |
| Calcium | | | 5,700 | mg/kg |
| Chromium | 38.9 | mg/kg | 25.0 | mg/kg |
| Cobalt | | | 13.9 | mg/kg |
| Copper | 330 | mg/kg | 57.4 | mg/kg |
| Iron | | | 25,400 | mg/kg |
| Lead | 52 | mg/kg | 26.0 | mg/kg |
| Magnesium | | | 6,450 | mg/kg |
| Manganese | | | 320.0 | mg/kg |
| Mercury | 0.5 | mg/kg | 0.09 | mg/kg |
| Nickel | | | 23.4 | mg/kg |
| Silver | 0.9 | mg/kg | 0.19 | mg/kg |
| Sodium | | | 3,940 | mg/kg |
| Vanadium | 83.9 | mg/kg | 71.2 | mg/kg |
| Zinc | 134 | mg/kg | 92.5 | mg/kg |
| | | | | |
| Total LPAH | 192.58 | mg/kg carbon | | |
| Naphthalene | 104.80 | mg/kg carbon | | |
| Acenaphthylene | 7.58 | mg/kg carbon | | |
| Acenaphthene | 29.69 | mg/kg carbon | | |
| Fluorene | 22.62 | mg/kg carbon | 15.0 | µg/kg |
| Phenathrene | 56.39 | mg/kg carbon | 470.0 | µg/kg |
| Anthracene | 91.27 | mg/kg carbon | 26.0 | µg/kg |
| 2-Methylnaphthalene | 21 | mg/kg carbon | 17.0 | µg/kg |
| Total HPAH | 607.20 | mg/kg carbon | | |
| Fluoranthene | 232.80 | mg/kg carbon | 1,200 | µg/kg |
| Pyrene | 190.48 | mg/kg carbon | 890.0 | µg/kg |
| Benzo(a)anthracene | 21.03 | mg/kg carbon | 220.0 | µg/kg |
| Chrysene | 68.78 | mg/kg carbon | 410.0 | µg/kg |
| Benzo(b)fluoranthene | | | 240.0 | µg/kg |
| Benzo(k)fluoranthene | | | 250.0 | µg/kg |

Table 2, continued
Summary of Constituents Detected in Sediment
Rhone-Poulenc, Inc., Marginal Way Facility, West Parcel

| Constituent | AMEC 2012 Sampling | | Rhone-Poulenc 1995 Sampling | |
|-----------------------------|-----------------------|--------------|-----------------------------|-------|
| | Maximum Concentration | Units | Maximum Concentration | Units |
| Total Benzofluoranthenes | 63.49 | mg/kg carbon | | |
| Benzo(a)pyrene | 21.43 | mg/kg carbon | 170.0 | µg/kg |
| Indeno(1,2,3-cd)pyrene | 11.11 | mg/kg carbon | 120.0 | µg/kg |
| Dibenz(a,h)anthracene | 4.44 | mg/kg carbon | 26.0 | µg/kg |
| Benzo(g,h,i)perylene | 11.9 | mg/kg carbon | 91.0 | µg/kg |
| 1,2-Dichlorobenzene | 0.18J | mg/kg carbon | | |
| 1,4-Dichlorobenzene | 2.6J | mg/kg carbon | | |
| 1,2,4-Trichlorobenzene | 0.26 | mg/kg carbon | | |
| Hexachlorobenzene | 0.16 | mg/kg carbon | | |
| Dimethyl phthalate | 1.35 | mg/kg carbon | 19.0 | µg/kg |
| Diethyl phthalate | 6.73 | mg/kg carbon | | |
| Di-n-Butyl phthalate | 1.15 | mg/kg carbon | 13.0 | µg/kg |
| Butyl benzyl phthalate | 1.30 | mg/kg carbon | 23.0 | µg/kg |
| bis(2-Ethylhexyl) phthalate | 6.35 | mg/kg carbon | 710.0 | µg/kg |
| Di-n-octyl phthalate | 9.41 | mg/kg carbon | 140.0 | µg/kg |
| Dibenzofuran | 11.97 | mg/kg carbon | | |
| N-Nitrosodiphenylamine | 0.27 | mg/kg carbon | | |
| Phenol | 110 | mg/kg carbon | 130.0 | µg/kg |
| 2-Methylphenol | 14 | mg/kg carbon | | |
| 4-Methylphenol | 230 | mg/kg carbon | 22.0 | µg/kg |
| 2,4-Dimethylphenol | 21 | mg/kg carbon | | |
| Pentachlorophenol | 19J | mg/kg carbon | | |
| Benzyl alcohol | 110 | mg/kg carbon | | |
| Benzoic acid | 380 | mg/kg carbon | | |
| | | | | |
| Aroclor 1254 | 84.34 | mg/kg carbon | 210.0 | µg/kg |
| Aroclor 1260 | 15.66 | mg/kg carbon | 50.0 | µg/kg |
| Aldrin | | | 2.3 | µg/kg |
| Alpha-chlordane | | | 1.3 | µg/kg |
| BHC-delta | | | 11.0 | µg/kg |
| 4,4'-DDD | | | 160.0 | µg/kg |
| 4,4'-DDE | | | 45.0 | µg/kg |
| 4,4'-DDT | | | 180.0 | µg/kg |
| Dieldrin | | | 3.3 | µg/kg |
| Endosulfan I | | | 1.3 | µg/kg |
| Endosulfan II | | | 2.8 | µg/kg |
| Endosulfan sulfate | | | 9.4 | µg/kg |

Table 2, continued

Summary of Constituents Detected in Sediment

Rhone-Poulenc, Inc., Marginal Way Facility, West Parcel

| Constituent | AMEC 2012 Sampling | | Rhone-Poulenc 1995 Sampling | |
|-----------------|-----------------------|-------|-----------------------------|-------|
| | Maximum Concentration | Units | Maximum Concentration | Units |
| Endrin aldehyde | | | 5.1 | µg/kg |
| Endrin ketone | | | 5.1 | µg/kg |
| Gamma-chlordane | | | 4.4 | µg/kg |
| Methoxychlor | | | 12.0 | µg/kg |

Table 3
Sediment Characterization Data Report
AMEC Environment & Infrastructure, Inc.
April 19, 2012

| Constituent | Surface Sediment Concentration | | Subsurface Sediment Concentration | | Units |
|--------------------------|--------------------------------|-----------------|-----------------------------------|-----------------|------------------|
| | Maximum Concentration | Sample Location | Maximum Concentration | Sample Location | |
| Arsenic | 13 | RP-20 | 28.9 | RP-16-0020 | mg/kg dry weight |
| Cadmium | 0.8 | RP-20 | 2.9 | RP-08-0040 | mg/kg dry weight |
| Chromium | 32 | RP-20 | 38.9 | RP-16-0020 | mg/kg dry weight |
| Copper | 62.4 | RP-01 | 330 | RP-08-0020 | mg/kg dry weight |
| Lead | 23 | RP-11 | 52 | RP-23-0120 | mg/kg dry weight |
| Mercury | 0.16 | RP-17 | 0.5 | RP-05-0020 | mg/kg dry weight |
| Silver | | | 0.9 | RP-23-0080 | mg/kg dry weight |
| Vanadium | 78.3 | RP-20 | 83.9 | RP-20-0040 | mg/kg dry weight |
| Zinc | 107 | RP-20 | 134 | RP-23-0120 | mg/kg dry weight |
| | | | | | |
| Total LPAH | 167.9 | RP-01 | 192.58 | RP-23-0080 | mg/kg carbon |
| Naphthalene | 1.81 | RP-24 | 104.80 | RP-23-0080 | mg/kg carbon |
| Acenaphthylene | 1.39 | RP-12 | 7.58 | RP-26-0020 | mg/kg carbon |
| Acenaphthene | 5.49 | RP-06 | 29.69 | RP-23-0080 | mg/kg carbon |
| Fluorene | 22.62 | RP-01 | 14.41 | RP-23-0080 | mg/kg carbon |
| Phenathrene | 56.39 | RP-12 | 40 | RP-18-0020 | mg/kg carbon |
| Anthracene | 91.27 | RP-01 | 40.48 | RP-23-0080 | mg/kg carbon |
| 2-Methylnaphthalene | 7.66 | RP-16 | 21 | RP-09-0040 | mg/kg carbon |
| Total HPAH | 264.68 | RP-01 | 607.20 | RP-23-0020 | mg/kg carbon |
| Fluoranthene | 52.63 | RP-12 | 232.80 | RP-23-0020 | mg/kg carbon |
| Pyrene | 36.90 | RP-01 | 190.48 | RP-23-0020 | mg/kg carbon |
| Benzo(a)anthracene | 21.03 | RP-01 | 15.87 | RP-23-0020 | mg/kg carbon |
| Chrysene | 67.46 | RP-01 | 68.78 | RP-23-0020 | mg/kg carbon |
| Total Benzofluoranthenes | 51.59 | RP-01 | 63.49 | RP-23-0020 | mg/kg carbon |
| Benzo(a)pyrene | 21.43 | RP-01 | 15.87 | RP-23-0020 | mg/kg carbon |
| Indeno(1,2,3-cd)pyrene | 11.11 | RP-01 | 8.47 | RP-23-0020 | mg/kg carbon |
| Dibenz(a,h)anthracene | 4.44 | RP-06 | 3.46 | RP-24-0040 | mg/kg carbon |
| Benzo(g,h,i)perylene | 11.9 | RP-01 | 8.47 | RP-23-0020 | mg/kg carbon |
| 1,2-Dichlorobenzene | 0.1J | RP-10 | 0.18J | RP-24-0040 | mg/kg carbon |
| 1,4-Dichlorobenzene | 0.20 | RP-10 | 2.6J | RP-13-0040 | mg/kg carbon |
| 1,2,4-Trichlorobenzene | 0.26 | RP-01 | | | mg/kg carbon |
| Hexachlorobenzene | 0.16 | RP-11 | | | mg/kg carbon |

Table 3, continued
Sediment Characterization Data Report
AMEC Environment & Infrastructure, Inc.
April 19, 2012

| Constituent | Surface Sediment Concentration | | Subsurface Sediment Concentration | | Units |
|-----------------------------|--------------------------------|-----------------|-----------------------------------|-----------------|--------------|
| | Maximum Concentration | Sample Location | Maximum Concentration | Sample Location | |
| Dimethyl phthalate | 1.35 | RP-01 | 0.39 | RP-25-0040 | mg/kg carbon |
| Diethyl phthalate | 1.51J | RP-19 | 6.73 | RP-06-0020 | mg/kg carbon |
| Di-n-Butyl phthalate | | | 1.15 | RP-02-0020 | mg/kg carbon |
| Butyl benzyl phthalate | 1.25 | RP-03 | 1.30 | RP-24-0040 | mg/kg carbon |
| bis(2-Ethylhexyl) phthalate | 6.35 | RP-01 | 4.26 | RP-23-0120 | mg/kg carbon |
| Di-n-octyl phthalate | 3.37 | RP-01 | 9.41 | RP-19-0040 | mg/kg carbon |
| Dibenzofuran | 6.35 | RP-01 | 11.97 | RP-23-0080 | mg/kg carbon |
| N-Nitrosodiphenylamine | 0.27 | RP-10 | | | mg/kg carbon |
| | | | | | |
| Aroclor 1254 | 28.16 | RP-10 | 84.34 | RP-05-0020 | mg/kg carbon |
| Aroclor 1260 | 9.77 | RP-10 | 15.66 | RP-05-0020 | mg/kg carbon |
| | | | | | |
| Phenol | 43 | RP-13 | 110 | RP-07-0020 | mg/kg carbon |
| 2-Methylphenol | 3.4J | RP-10 | 14 | RP-12-0040 | mg/kg carbon |
| 4-Methylphenol | 62 | RP-13 | 230 | RP-08-0020 | mg/kg carbon |
| 2,4-Dimethylphenol | 3.6J | RP-10 | 21 | RP-26-0020 | mg/kg carbon |
| Pentachlorophenol | 15J | RP-05 | 19J | RP-06-0040 | mg/kg carbon |
| Benzyl alcohol | 110 | RP-17 | 110 | RP-16-0020 | mg/kg carbon |
| Benzoic acid | 230J | RP-20 | 380 | RP-23-0020 | mg/kg carbon |

Table 4
Shoreline Soil and Groundwater Characterization Data Report
AMEC Environment & Infrastructure, Inc.
March 12, 2012

| Constituent | Groundwater Concentration | | | Soil Concentration | | |
|--------------------------|---------------------------|-----------------|-------|-----------------------|-----------------|-------|
| | Maximum Concentration | Sample Location | Units | Maximum Concentration | Sample Location | Units |
| Aluminum | 880,000 | SL-14, 51 ft | µg/L | 17,800 | SL-15, 20 ft | mg/kg |
| Arsenic | 107 | SL-15, 16 ft | µg/L | 29.4J | SL-14, 15 ft | mg/kg |
| Cadmium | 6 | SL-15, 16 ft | µg/L | 0.6 | SL-14, 15 ft | mg/kg |
| Chromium | 2,590 | SL-14, 46 ft | µg/L | 30 | SL-07, 0.5 ft | mg/kg |
| Copper | 1,880 | SL-15, 16 ft | µg/L | 2,180J | SL-01, 0.5 ft | mg/kg |
| Lead | 196 | SL-10, 51 ft | µg/L | 22 | SL-14, 15 ft | mg/kg |
| Mercury | 9.76J | SL-15, 16 ft | µg/L | 83 | SL-08, 0.5 ft | mg/kg |
| Nickel | 610 | SL-10, 51 ft | µg/L | 40 | SL-07, 0.5 ft | mg/kg |
| Vanadium | 4,290 | SL-14, 46 ft | µg/L | 66.3 | SL-15, 20 ft | mg/kg |
| Zinc | 2,770 | SL-14, 46 ft | µg/L | 120 | SL-13, 0.5 ft | mg/kg |
| | | | | | | |
| Acenaphthene | | | | 28 | SL-01, 5 ft | µg/kg |
| Anthracene | | | | 13J | SL-01, 10 ft | µg/kg |
| Benzo(a)anthracene | | | | 28J | SL-01, 0.5 ft | µg/kg |
| Benzo(a)pyrene | | | | 38 | SL-01, 0.5 ft | µg/kg |
| Benzo(g,h,i)perylene | | | | 45 | SL-01, 0.5 ft | µg/kg |
| Benzoic acid | | | | 98J | SL-01, 10 ft | µg/kg |
| Chrysene | | | | 42 | SL-01, 0.5 ft | µg/kg |
| Dibenz(a,h)anthracene | | | | 16J | SL-01, 0.5 ft | µg/kg |
| Dibenzofuran | | | | 120 | SL-04, 0.5 ft | µg/kg |
| Fluoranthene | | | | 55 | SL-03, 0.5 ft | µg/kg |
| Fluorene | | | | 19 | SL-01, 10 ft | µg/kg |
| Indeno(1,2,3-cd)pyrene | | | | 42 | SL-01, 0.5 ft | µg/kg |
| Naphthalene | | | | 110 | SL-01, 5 ft | µg/kg |
| Pentachlorophenol | | | | 210 | SL-01, 0.5 ft | µg/kg |
| Phenathrene | | | | 110 | SL-04, 0.5 ft | µg/kg |
| Phenol | | | | 150 | SL-04, 5 ft | µg/kg |
| Pyrene | | | | 42 | SL-01, 0.5 ft | µg/kg |
| Total benzofluoranthenes | | | | 100 | SL-01, 0.5 ft | µg/kg |
| Total cPAHs | | | | 57.02 | SL-01, 0.5 ft | µg/kg |

Table 4, continued
Shoreline Soil and Groundwater Characterization Data Report
AMEC Environment & Infrastructure, Inc.
March 12, 2012

| Constituent | Groundwater Concentration | | | Soil Concentration | | |
|------------------------|---------------------------|-----------------|-------|-----------------------|-----------------|-------|
| | Maximum Concentration | Sample Location | Units | Maximum Concentration | Sample Location | Units |
| 1,2,4-Trimethylbenzene | 0.9J | SL-09, 30 ft | µg/L | | | |
| 1,3,5-Trimethylbenzene | 0.2J | SL-09, 30 ft | µg/L | | | |
| 1,4-Dichlorobenzene | 0.1J | SL-10, 36 ft | µg/L | | | |
| 2-Butanone | | | | 36 | SL-12, 50 ft | µg/kg |
| 4-Isopropyltoluene | 2.2 | SL-12, 41 ft | µg/L | 24 | SL-14, 15 ft | µg/kg |
| Acetone | 120 | SL-12, 41 ft | µg/L | 190 | SL-12, 50 ft | µg/kg |
| Benzene | 1.3 | SL-12, 41 ft | µg/L | 28 | SL-02, 10 ft | µg/kg |
| Carbon Disulfide | 1.7 | SL-14, 46 ft | µg/L | 38 | SL-12, 35 ft | µg/kg |
| cis-1,2-dichloroethene | 0.4 | SL-14, 21 ft | µg/L | 2.5 | SL-14, 15 ft | µg/kg |
| m,p-Xylene | 1.8J | SL-09, 30 ft | µg/L | 1.5 | SL-01, 5 ft | µg/kg |
| Methylene chloride | 4.1 | SL-12, 46 ft | µg/L | 22 | SL-11, 30 ft | µg/kg |
| o-Xylene | 0.9J | SL-09, 30 ft | µg/L | | | |
| sec-Butylbenzene | | | | 0.8J | SL-01, 5 ft | µg/kg |
| Tetrachloroethene | | | | 1.7J | SL-14, 15 ft | µg/kg |
| Toluene | 440 | SL-12, 46 ft | µg/L | 970 | SL-12, 50 ft | µg/kg |
| Trichloroethene | | | µg/L | 4 | SL-14, 15 ft | µg/kg |
| | | | | | | |
| Aroclor 1254 | | | | 5,900 | SL-01, 0.5 ft | µg/kg |
| Aroclor 1260 | | | | 160 | SL-02, 0.5 ft | µg/kg |

Table 5
Northwest Corner Affected Soil Removal
Report Geomatrix Consultants
May 23, 2007

| Constituent | Soil Concentration | | | |
|-----------------------------|-----------------------|-----------------|-------------------|-------|
| | Maximum Concentration | Sample Location | Sample Depth feet | Units |
| Arsenic | 4.53 | NWC-1-12W | 0.5 to 1.0 | mg/kg |
| Barium | 169 | NWC-2-39W | 2.0 to 2.5 | mg/kg |
| Cadmium | 0.288 | NWC-2-39W | 2.0 to 2.5 | mg/kg |
| Chromium | 15.1 | NWC-1-12W | 0.5 to 1.0 | mg/kg |
| Copper | 18,200 | NWC-2-39W | 2.0 to 2.5 | mg/kg |
| Lead | 28.2 | NWC-2-39W | 2.0 to 2.5 | mg/kg |
| Mercury | 1.91 | NWC-2-39W | 2.0 to 2.5 | mg/kg |
| Selenium | 0.8J | NWC-1-2W | 0.5 to 1.0 | mg/kg |
| Silver | 0.219 | NWC-1-12W | 0.5 to 1.0 | mg/kg |
| Acenaphthylene | 3.7 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| Anthracene | 7.5 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| Benzo(a)anthracene | 55 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| Benzo(a)pyrene | 75 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| Benzo(b)fluoranthene | 97 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| Benzo(g,h,i)perylene | 68 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| Benzo(k)fluoranthene | 31 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| bis(2-Ethylhexyl) phthalate | 34 | NWC-1-2W | 0.5 to 1.0 | µg/kg |
| Butyl benzyl phthalate | 23 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| Chrysene | 79 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| Dibenzo(a,h)anthracene | 13 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| Dibenzofuran | 4.1 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| di-n-Butylphthalate | 15 | NWC-1-22W | 1.0 to 1.5 | µg/kg |
| Fluoranthene | 97 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| Indeno(1,2,3-cd)pyrene | 63 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| 2-Methylnaphthalene | 13 | NWC-1-22W | 1.0 to 1.5 | µg/kg |
| Naphthalene | 14 | NWC-1-22W | 1.0 to 1.5 | µg/kg |
| Pentachlorophenol | 550 | NWC-1-22W | 1.0 to 1.5 | µg/kg |
| Phenathrene | 36 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| Phenol | 17 | NWC-1-22W | 1.0 to 1.5 | µg/kg |
| Pyrene | 95 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| 2,4,5-Trichlorophenol | 7.9 | NWC-1-22W | 1.0 to 1.5 | µg/kg |
| Total cPAHs | 106 | NWC-1-12W | 0.5 to 1.0 | µg/kg |
| GRO-NWTPH | 13,000 | NWC-2-6W | 2.0 to 3.0 | mg/kg |
| DRO-NWTPH | 2,100 | NWC-2-36W | 3.5 to 4.0 | mg/kg |
| RRO-NWTPH | 470 | NWC-2-6W | 2.0 to 3.0 | mg/kg |

Table 6
Voluntary Interim Measure Report
Hazardous Waste Storage Area and Transformer A Area Cleanup
Geomatrix Consultants, Inc.
August 18, 2006

| Constituent | Catch Basin Water Concentration | | Catch Basin Sediment Concentration | | Soil Concentration prior to removal action | |
|------------------------|---------------------------------|-------|------------------------------------|-------|--|-------|
| | Maximum Concentration | Units | Maximum Concentration | Units | Maximum Concentration | Units |
| TPH-D | 1,100 | mg/L | 6,800 | mg/kg | 9,300 | mg/kg |
| TPH-O | 150 | mg/L | 1,200 | mg/kg | 1,200 | mg/kg |
| | | | | | | |
| Arsenic | 0.090 | mg/L | | | | |
| Chromium | 0.082 | mg/L | 14.4 | mg/kg | 13.3 | mg/kg |
| Copper | 6.39 | mg/L | 110 | mg/kg | 540 | mg/kg |
| Lead | 0.07 | mg/L | 4 | mg/kg | 4 | mg/kg |
| Mercury | 0.0006 | mg/L | | | 0.11 | mg/kg |
| Zinc | 0.395 | mg/L | 35.0 | mg/kg | 34.6 | mg/kg |
| | | | | | | |
| Phenanthrene | | | 220J | µg/kg | 290 | µg/kg |
| Fluoranthene | 5.3J | µg/L | 350 | µg/kg | 610 | µg/kg |
| Pyrene | 5.5J | µg/L | 320 | µg/kg | 570 | µg/kg |
| Benzo(a)anthracene | 3.8J | µg/L | | | 160J | µg/kg |
| Chrysene | 4.1J | µg/L | 190J | µg/kg | 310 | µg/kg |
| Benzo(b)fluoranthene | 3.8J | µg/L | | | 260 | µg/kg |
| Benzo(k)fluoranthene | | | 160J | µg/kg | 240J | µg/kg |
| Indeno(1,2,3-cd)pyrene | | | | | 160J | µg/kg |
| Benzo(ghi)perylene | | | | | 160J | µg/kg |
| 4-Methylphenol | 810 | µg/L | 240J | µg/kg | | |
| 2-Methylphenol | 5.9J | µg/L | | | | |
| 2,4-Dimethylphenol | 3.6J | µg/L | | | | |
| Benzoic acid | 120 | µg/L | | | | |
| Naphthalene | 3.0J | µg/L | | | | |
| 2-Methylnaphthalene | 10 | µg/L | | | | |
| Phenol | 63 | µg/L | | | | |

Table 7
Revised Pre-Demolition Investigation Report
Geomatrix Consultants, Inc.
May 8, 2006

| Constituent | Test Pit 2, Old Meal Bin Soil Sample | | Test Pit 7, Old Meal Bin Stairway Soil Sample | | | |
|-----------------------|---|-------|---|-------|----------------------------|-------|
| | Maximum Concentration | Units | Maximum Concentration | Units | | |
| Methylene chloride | 3.2 | µg/kg | 5.0 | µg/kg | | |
| Acetone | 44 | µg/kg | 46 | µg/kg | | |
| Chromium | 29 | mg/kg | 34.7 | mg/kg | | |
| Copper | 12.9 | mg/kg | 19.5 | mg/kg | | |
| Lead | 7.4 | mg/kg | 22.0 | mg/kg | | |
| Mercury | 0.02 | mg/kg | 0.06 | mg/kg | | |
| Zinc | 34.7 | mg/kg | 52.0 | mg/kg | | |
| | | | | | | |
| | Scale Pit Sump Water | | Scale Pit Sump Crystalline Material | | Scale Pit Sump Sediment | |
| | Maximum Concentration | Units | Maximum Concentration | Units | Maximum Concentration | Units |
| Acetone | 44 | µg/L | 1,800 | µg/kg | | |
| Carbon disulfide | | | 12 | µg/kg | | |
| 2-Butanone | | | 190 | µg/kg | | |
| Toluene | | | 83 | µg/kg | | |
| Phenol | | | 2,200 | µg/kg | 120 | µg/kg |
| 4-Methylphenol | 3.6 | µg/L | 3,300 | µg/kg | | |
| Naphthalene | | | 250 | µg/kg | | |
| 2-Methylnaphthalene | | | 1,500 | µg/kg | 89 | µg/kg |
| 2,4-Dichlorophenol | 4.2J | µg/L | | | | |
| 2,4,6-Trichlorophenol | 18 | µg/L | | | | |
| 2,4,5-Trichlorophenol | 210 | µg/L | 14,000 | µg/kg | | |
| Dimethylphthalate | | | | | 120 | µg/kg |
| Acenaphthylene | | | 3,300 | µg/kg | | |
| Acenaphthaene | | | 400 | µg/kg | | |
| Dibenzofuran | | | 610 | µg/kg | 66 | µg/kg |
| Fluorene | | | 2,600 | µg/kg | 92 | µg/kg |
| Pentachlorophenol | 510 | µg/L | 480,000 | µg/kg | 14,000 | µg/kg |
| Phenanthrene | | | 22,000 | µg/kg | 1,200 | µg/kg |
| Carbazole | | | 1,700 | µg/kg | 110 | µg/kg |
| Anthracene | | | 5,600 | µg/kg | 200 | µg/kg |
| Di-n-butyl phthalate | | | | | 700 | µg/kg |
| Fluoranthene | | | 37,000 | µg/kg | 1,800 | µg/kg |

Table 7, continued
Revised Pre-Demolition Investigation Report
Geomatrix Consultants, Inc.
May 8, 2006

| Constituent | Scale Pit Sump Water | | Scale Pit Sump Crystalline Material | | Scale Pit Sump Sediment | |
|----------------------------|-----------------------|-------|-------------------------------------|-------|-------------------------|-------|
| | Maximum Concentration | Units | Maximum Concentration | Units | Maximum Concentration | Units |
| Pyrene | | | 24,000 | µg/kg | 1,500 | µg/kg |
| Butyl benzyl phthalate | | | | | 310 | µg/kg |
| Benzo(a)anthracene | | | 14,000 | µg/kg | 540 | µg/kg |
| Bis(2-ethylhexyl)phthalate | | | 8,600 | µg/kg | 6,200 | µg/kg |
| Chrysene | | | 14,000 | µg/kg | 950 | µg/kg |
| Di-n-octyl phthalate | | | | | 370 | µg/kg |
| Benzo(b)fluoranthene | | | 17,000 | µg/kg | 1,300 | µg/kg |
| Benzo(k)fluoranthene | | | 13,000 | µg/kg | 1,000 | µg/kg |
| Benzo(a)pyrene | | | 13,000 | µg/kg | 700 | µg/kg |
| Indeno(1,2,3-cd)pyrene | | | 4,400 | µg/kg | 330 | µg/kg |
| Dibenz(a,h)anthracene | | | 1,000 | µg/kg | 80 | µg/kg |
| Benzo(ghi)perylene | | | 4,200 | µg/kg | 360 | µg/kg |
| | | | | | | |
| Antimony | 0.10 | mg/L | | | | |
| Arsenic | 0.20 | mg/L | 70 | mg/kg | 90 | mg/kg |
| Cadmium | 0.06 | mg/L | 13 | mg/kg | 19 | mg/kg |
| Calcium | | | | | 40,600 | mg/kg |
| Chromium | 0.25 | mg/L | 107 | mg/kg | 213 | mg/kg |
| Copper | 5.38 | mg/L | 2380 | mg/kg | 475 | mg/kg |
| Iron | | | | | 156,000 | mg/kg |
| Lead | 2.2 | mg/L | 3,070 | mg/kg | 3,950 | mg/kg |
| Magnesium | | | | | 6,240 | mg/kg |
| Mercury | 0.008 | mg/L | 1.19 | mg/kg | 1.43 | mg/kg |
| Potassium | | | | | 7,980 | mg/kg |
| Sodium | | | | | 42,400 | mg/kg |
| Zinc | 4.51 | mg/L | 6,960 | mg/kg | 3,740 | mg/kg |
| | | | | | | |
| Bromide | | | | | 95.7 | mg/kg |
| Fluoride | | | | | 1,060 | mg/kg |
| Sulfate | | | | | 274,000 | mg/kg |
| Chloride | | | | | 38,100 | mg/kg |
| Nitrate | | | | | 737 | mg/kg |

Table 7, continued
Revised Pre-Demolition Investigation
Report Geomatrix Consultants, Inc.
May 8, 2006

| Constituent | Copper Sump Water | | Copper Sump Sediment | | I-120 Sump Upper Water | | I-120 Sump Bottom Water | |
|----------------------------|-----------------------|-------|-----------------------|-------|------------------------|-------|-------------------------|-------|
| | Maximum Concentration | Units | Maximum Concentration | Units | Maximum Concentration | Units | Maximum Concentration | Units |
| Methylene chloride | | | 24J | µg/kg | | | | |
| Acetone | | | 830J | µg/kg | 68 | µg/L | 840 | µg/L |
| Carbon disulfide | | | 29J | µg/kg | | | | |
| 2-Butanone | | | 140J | µg/kg | | | | |
| Toluene | | | 10J | µg/kg | 310 | µg/L | 30,000 | µg/L |
| | | | | | | | | |
| Phenol | | | | | 330 | µg/L | 9,000 | µg/L |
| 2-Methylphenol | | | | | 26 | µg/L | | |
| 4-Methylphenol | 2.7 | µg/L | | | 19,000 | µg/L | 72,000 | µg/L |
| 2,4-Dimethylphenol | | | | | 26 | µg/L | | |
| Benzoic acid | | | | | 100 | µg/L | | |
| Phenanthrene | | | 6,900 | µg/kg | | | | |
| Carbazole | | | 1,600 | µg/kg | | | | |
| Anthracene | | | 950 | µg/kg | | | | |
| Fluoranthene | | | 23,000 | µg/kg | | | | |
| Pyrene | | | 17,000 | µg/kg | | | | |
| Benzo(a)anthracene | | | 8,700 | µg/kg | | | | |
| Bis(2-ethylhexyl)phthalate | 1.2 | µg/L | 22,000 | µg/kg | 12 | µg/L | | |
| Chrysene | | | 14,000 | µg/kg | | | | |
| Benzo(b)fluoranthene | | | 26,000 | µg/kg | | | | |
| Benzo(k)fluoranthene | | | 20,000 | µg/kg | | | | |
| Benzo(a)pyrene | | | 17,000 | µg/kg | | | | |
| Indeno(1,2,3-cd)pyrene | | | 7,400 | µg/kg | | | | |
| Dibenz(a,h)anthracene | | | 1,800 | µg/kg | | | | |
| Benzo[ghi]perylene | | | 6,600 | µg/kg | | | | |
| | | | | | | | | |
| Aroclor 1254 | | | 20,000J | µg/kg | | | 200J | µg/L |
| | | | | | | | | |
| TPH | | | | | | | 74J | mg/L |
| Diesel | | | | | | | 42 | mg/L |
| Motor oil | | | | | | | 43 | mg/L |

Table 7, continued
Revised Pre-Demolition Investigation
Report Geomatrix Consultants, Inc.
May 8, 2006

| Constituent | Copper Sump Water | | Copper Sump Sediment | | I-120 Sump Upper Water | | I-120 Sump Bottom Water | |
|-------------|-----------------------|-------|-----------------------|-------|------------------------|-------|-------------------------|-------|
| | Maximum Concentration | Units | Maximum Concentration | Units | Maximum Concentration | Units | Maximum Concentration | Units |
| Antimony | | | | | | | 0.15 | mg/L |
| Arsenic | | | | | | | 0.09 | mg/L |
| Cadmium | | | 3.0 | mg/kg | | | 0.013 | mg/L |
| Chromium | | | 47 | mg/kg | 0.008 | mg/L | 0.156 | mg/L |
| Copper | 0.011 | mg/L | 1,730 | mg/kg | 0.039 | mg/L | 9.67 | mg/L |
| Lead | | | 78 | mg/kg | 0.001 | mg/L | 0.22 | mg/L |
| Mercury | | | 1.19 | mg/kg | | | 0.022 | mg/L |
| Zinc | 0.022J+ | mg/L | 1,060 | mg/kg | 0.090J+ | mg/L | 3.41 | mg/L |

Table 8
Round 6 Groundwater Monitoring
Rhone-Poulenc Marginal Way
Facility Tukwila, Washington
AGI Technologies
January 14, 2000

| Constituent | Appendix IX Analysis | | | LNAPL Well H-10 | | Non-Appendix IX Wells | | |
|------------------------|-----------------------|-------|-----------------|-----------------------|-------|-----------------------|-------|-----------------|
| | Maximum Concentration | Units | Sample Location | Maximum Concentration | Units | Maximum Concentration | Units | Sample Location |
| Benzene | 130 | µg/L | MW-17 | | | 85 | µg/L | MW-18 |
| Toluene | 570,000 | µg/L | MW-17 | 360,000 | mg/kg | 370,000 | µg/L | H-11 |
| Ethylbenzene | 100 | µg/L | MW-17 | | | 26 | µg/L | H-11 |
| Xylene (total) | 24 | µg/L | H-10 | | | 92 | µg/L | MW-18 |
| 1,2,4-Trimethylbenzene | | | | | | 1.1 | µg/L | MW-14 |
| | | | | | | | | |
| Benzyl alcohol | 17 | µg/L | H-10 | | | | | |
| 2-Methylphenol | 220 E | µg/L | H-10 | | | | | |
| 4-Methylphenol | 170 E | µg/L | MW-17 | | | | | |
| 2,4-Dimethylphenol | 0.8 J | µg/L | H-10 | | | | | |
| Naphthalene | 0.3 MJ | µg/L | MW-17 | | | | | |
| Pentachlorophenol | 3.2 J | µg/L | MW-17 | | | | | |
| 1,4-Phenylenediamine | 12 Y | µg/L | MW-17 | | | | | |
| | | | | | | | | |
| Arsenic | 0.102 | mg/L | MW-25 | | | 0.066 | mg/L | MW-22 |
| Barium | 0.063 | mg/L | MW-25 | | | | | |
| Chromium | 0.048 | mg/L | MW-25 | | | 0.35 | mg/L | MW-16 |
| Copper | 0.12 | mg/L | MW-25 | | | 0.21 | mg/L | MW-15 |
| Lead | 0.014 | mg/L | MW-25 | | | 0.022 | mg/L | DM-8 |
| Mercury | 0.00036 | mg/L | MW-25 | | | 0.00027 | mg/L | H-6 |
| Nickel | | | | | | 0.032 | mg/L | MW-16 |
| Silver | 0.0004 | mg/L | MW-25 | | | | | |
| Tin | 0.06 | mg/L | MW-17 | | | | | |
| Vanadium | 0.37 | mg/L | MW-25 | | | 2.2 | mg/L | MW-16 |
| Zinc | 0.014 | mg/L | MW-17 | | | 0.075 | mg/L | H-9 |

Notes:

E – value above linear range of detector

MJ – estimated value obtained from unusually integrated chromatograph

Y – indicates a raised reporting limit due to matrix interferences. The analyte may be present at or below the listed concentration, but in the opinion of the analyst, confirmation was inadequate.

Table 9
Interim Measures Report, PCB Remediation & Sewer
Cleaning Rhodia, Inc.
East Marginal Way Facility, Tukwila,
Washington April 1, 1998

| Constituent | Compressor Pad Remediation | | Piping Trench Soil Remediation | | Outfall 7 Rinsate and Stormwater Samples | | Sewer Sediment Sample | |
|------------------------|----------------------------|-------|--------------------------------|-------|--|-------|-----------------------|-------|
| | Maximum Concentration | Units | Maximum Concentration | Units | Maximum Concentration | Units | Maximum Concentration | Units |
| Barium, TCLP | | | | | | | 1.4 | mg/L |
| Cadmium, TCLP | | | | | | | 0.035 | mg/L |
| Copper | | | | | 1.9 | mg/L | 6,300 | mg/kg |
| Lead | | | | | 0.14 | mg/L | | |
| Mercury | | | | | 0.0056 | mg/L | | |
| Zinc | | | | | 0.32 | mg/L | | |
| | | | | | | | | |
| Phenanthrene | | | | | 6J | µg/L | | |
| Fluoranthene | | | | | 51 | µg/L | | |
| Pyrene | | | | | 36 | µg/L | | |
| Benzo(a)anthracene | | | | | 23 | µg/L | | |
| Chrysene | | | | | 26 | µg/L | | |
| Benzo(b)fluoranthene | | | | | 20 | µg/L | | |
| Benzo(k)fluoranthene | | | | | 12 | µg/L | | |
| Benzo(a)pyrene | | | | | 12 | µg/L | | |
| Indeno(1,2,3-cd)pyrene | | | | | 11 | µg/L | | |
| Benzo(g,h,i)perylene | | | | | 10 | µg/L | | |
| | | | | | | | | |
| Aroclor 1254 | 2.42 | mg/kg | 1,588.71 | mg/kg | 1.3 | µg/L | 6.6 | mg/kg |
| Aldrin | | | | | 0.062 | µg/L | | |
| 4,4'-DDE | | | | | 0.021 | µg/L | | |
| DDT | | | | | 0.067 | µg/L | | |
| Heptachlor epoxide | | | | | 0.028 | µg/L | | |
| | | | | | | | | |
| Acetone | | | | | | | 4,100 | µg/L |
| Toluene | | | | | | | 700 | µg/L |
| m-xylene | | | | | | | 310 | µg/L |
| p-xylene | | | | | | | 310 | µg/L |
| o-xylene | | | | | | | 500 | µg/L |

Table 10
RCRA Facility Investigation
Round 3 Data and Sewer Sediment Technical Memorandum
Rhone-Poulenc, Inc.
December 24, 1996

| Constituent | Outfall Sewer Sediment | | Process Sewer Sediment | | Storm Sewer Outfall Intertidal Sediment | |
|-----------------------------|------------------------|-------|------------------------|-------|---|-----------|
| | Maximum Concentration | Units | Maximum Concentration | Units | Maximum Concentration | Units |
| Benzene | 6 | µg/kg | | | | |
| Ethylbenzene | 15 | µg/kg | 24 | µg/kg | | |
| Toluene | 76,000 | µg/kg | 33,000 | µg/kg | | |
| Xylenes (total) | 89 | µg/kg | 110 | µg/kg | | |
| | | | | | | |
| Arsenic | 156 | mg/kg | 400 | mg/kg | 22 | mg/kg-dry |
| Cadmium | 22.55 | mg/kg | 46 | mg/kg | 0.9 | mg/kg |
| Chromium | 202 | mg/kg | 220 | mg/kg | 41.1 | mg/kg |
| Copper | 31,200 | mg/kg | 41,300 | mg/kg | 83.5 | mg/kg |
| Lead | 427 | mg/kg | 2,920 | mg/kg | 133 | mg/kg |
| Mercury | | | | | 0.66 | mg/kg |
| Silver | 4.2 | mg/kg | 318 | mg/kg | 1 | mg/kg |
| Zinc | 3,930 | mg/kg | 4,410 | mg/kg | 191 | mg/kg |
| | | | | | | |
| Arochlor 1254 | 526,000 | µg/kg | 9,300 | µg/kg | | |
| Arochlor 1260 | | | 240 | µg/kg | | |
| | | | | | | |
| 2-Methylnaphthalene | 0.35 | ppm C | 0.15 | ppm C | | |
| 2-Methylphenol | 330 | µg/kg | | µg/kg | | |
| 4-Methylphenol | 31,000 | µg/kg | 8,500 | µg/kg | | |
| Acenaphthene | 5.20 | ppm C | 1,450 | ppm C | | |
| Acenaphthylene | 0.03 | ppm C | 0.08 | ppm C | | |
| Anthracene | 6.53 | ppm C | 1.79 | ppm C | | |
| Benzo(a)anthracene | 15.50 | ppm C | 5.53 | ppm C | | |
| Benzo(a)pyrene | 14.40 | ppm C | 2.61 | ppm C | | |
| Benzo(b)fluoranthene | 150,000 | µg/kg | 40,000 | µg/kg | | |
| Benzo(ghi)perylene | 2.66 | ppm C | 2.86 | ppm C | | |
| Benzo(k)fluoranthene | 84,000 | µg/kg | 35,000 | µg/kg | | |
| Benzyl alcohol | | | 2,500 | µg/kg | | |
| Benzyl butyl phthalate | 0.44 | ppm C | 2,481 | ppm C | | |
| Bis(2-ethylhexyl) phthalate | 8.19 | ppm C | 1,120 | ppm C | | |
| Carbazole | 54,000 | µg/kg | 15,000 | µg/kg | | |

Table 10, continued
RCRA Facility Investigation
Round 3 Data and Sewer Sediment Technical Memorandum
Rhone-Poulenc, Inc.
December 24, 1996

| Constituent | Outfall Sewer Sediment | | Process Sewer Sediment | | Storm Sewer Outfall Intertidal Sediment | |
|--------------------------|------------------------|-------|------------------------|-------|---|-----------|
| | Maximum Concentration | Units | Maximum Concentration | Units | Maximum Concentration | Units |
| Chrysene | 21.04 | ppm C | 3.05 | ppm C | | |
| Di-n-butyl phthalate | | | 1.32 | ppm C | | |
| Di-n-octyl phthalate | 50.00 | ppm C | 112 | ppm C | | |
| Dibenzo(a,h)anthracene | 3.54 | ppm C | 1.25 | ppm C | | |
| Dibenzofuran | 2.21 | ppm C | 0.97 | ppm C | | |
| Dimethyl phthalate | 0.0537 | ppm C | 0.28 | ppm C | | |
| Fluoranthene | 44.30 | ppm C | 19.08 | ppm C | | |
| Fluorene | 5.20 | ppm C | 1.41 | ppm C | | |
| HPAH | 178.41 | ppm C | 63.80 | ppm C | | |
| Indeno(1,2,3-c,d)pyrene | 8.97 | ppm C | 2.67 | ppm C | | |
| LPAH | 56.04 | ppm C | 19.05 | ppm C | | |
| Naphthalene | 1.04 | ppm C | 0.27 | ppm C | | |
| Pentachlorophenol | 480 | µg/kg | | | | |
| Phenanthrene | 37.65 | ppm C | 13.93 | ppm C | | |
| Phenol | 7,600 | µg/kg | 3,500 | µg/kg | 32 | µg/kg-dry |
| Pyrene | 42.08 | ppm C | 15.27 | ppm C | | |
| Total benzofluoranthenes | 25.91 | ppm C | 15.60 | ppm C | | |

Table 11
RCRA Facility Investigation (RFI) Report
For the Marginal Way Facility, Tukwila, Washington
Rhone-Poulenc
June 19, 1995

| Constituent | Soil Concentration | | | Sediment Concentration | |
|--------------------|-----------------------|-------|-------------------------|------------------------|-------|
| | Maximum Concentration | Units | Soil Investigation Area | Maximum Concentration | Units |
| Aluminum | 19,700 | mg/kg | A2 | 22,600 | mg/kg |
| Antimony | 21.2 | mg/kg | A10 | | |
| Arsenic | 61.4 | mg/kg | A10 | 9.9 | mg/kg |
| Barium | 80.3 | mg/kg | A6 | 56.1 | mg/kg |
| Beryllium | 1.10 | mg/kg | A2 | 0.81 | mg/kg |
| Cadmium | 5.0 | mg/kg | A10 | 0.40 | mg/kg |
| Calcium | 34,400 | mg/kg | A10 | 5,700 | mg/kg |
| Chromium | 64.9 | mg/kg | A9 | 25 | mg/kg |
| Cobalt | 28.7 | mg/kg | A5 | 13.9 | mg/kg |
| Copper | 6,850 | mg/kg | A1 | 57.4 | mg/kg |
| Iron | 50,400 | mg/kg | A5 | 25,400 | mg/kg |
| Lead | 116 | mg/kg | A7 | 26 | mg/kg |
| Magnesium | 15,100 | mg/kg | A5 | 6,450 | mg/kg |
| Manganese | 941 | mg/kg | A5 | 320 | mg/kg |
| Mercury | 268 | mg/kg | A6 | 0.09 | mg/kg |
| Nickel | 65.7 | mg/kg | A5 | 23.40 | mg/kg |
| Potassium | 902 | mg/kg | A2 | | |
| Selenium | 0.42 | mg/kg | A1 | | |
| Silver | 3.5 | mg/kg | A1 | 0.190 | mg/kg |
| Sodium | 4,200 | mg/kg | A7 | 3,940 | mg/kg |
| Vanadium | 185 | mg/kg | A7 | 71.2 | mg/kg |
| Zinc | 1,990 | mg/kg | A5 | 92.5 | mg/kg |
| | | | | | |
| Acetone | 13.0 | mg/kg | A4 | | |
| Benzene | 0.23 | mg/kg | A4 | | |
| Bromoform | 0.002 | mg/kg | A4 | | |
| 2-Butanone | 1.1 | mg/kg | A4 | | |
| Carbon disulfide | 0.006 | mg/kg | A7 | | |
| Ethylbenzene | 6.4 | mg/kg | A2 | | |
| Formaldehyde | 3.4 | mg/kg | A2 | | |
| Methylene chloride | 1.6 | mg/kg | A4 | | |
| 2-Propanol | 10 | mg/kg | A2 | | |

Table 11, continued
RCRA Facility Investigation (RFI) Report
For the Marginal Way Facility, Tukwila,
Washington Rhone-Poulenc
June 19, 1995

| Constituent | Soil Concentration | | | Sediment Concentration | |
|----------------------------|-----------------------|-------|-------------------------|------------------------|-------|
| | Maximum Concentration | Units | Soil Investigation Area | Maximum Concentration | Units |
| Trichloroethene | 0.2 | mg/kg | A4 | | |
| Toluene | 4,900 | mg/kg | A4 | | |
| Xylene | 13 | mg/kg | A2 | | |
| Acenaphthene | 0.13 | mg/kg | A2 | | |
| Anthracene | 0.26 | mg/kg | A2 | 26 | µg/kg |
| Benz[a]anthracene | 0.46 | mg/kg | A2 | 220 | µg/kg |
| Benzo(a)pyrene | 0.65 | mg/kg | A4 | 170 | µg/kg |
| Benzo(b)fluoranthene | 0.72 | mg/kg | A4 | 240 | µg/kg |
| Benzo(k)fluoranthene | 0.59 | mg/kg | A4 | 250 | µg/kg |
| Benzo(g,h,i)perylene | 0.41 | mg/kg | A4 | 91 | µg/kg |
| Benzyl alcohol | 0.19 | mg/kg | A2 | | |
| Benzyl butyl phthalate | 0.09 | mg/kg | A4 | 23 | µg/kg |
| Bis(2-ethylhexyl)phthalate | 6.80 | mg/kg | A4 | 710 | µg/kg |
| Carbazole | 0.17 | mg/kg | A4 | | |
| Chrysene | 0.84 | mg/kg | A4 | 410 | µg/kg |
| 2,4-Dimethylphenol | 0.29 | mg/kg | A2 | | |
| Di-n-butyl phthalate | 0.43 | mg/kg | A2 | 13 | µg/kg |
| Di-n-octyl phthalate | | | | 140 | µg/kg |
| Dibenzo(a,h)anthracene | | | | 26 | µg/kg |
| Dibenzofuran | 0.083 | mg/kg | A2 | | |
| Dimethyl phthalate | | | | 19 | µg/kg |
| Fluoranthene | 1.80 | mg/kg | A4 | 1,200 | µg/kg |
| Fluorene | 0.15 | mg/kg | A2 | 15 | µg/kg |
| Indeno(1,2,3-cd)pyrene | 0.44 | mg/kg | A4 | 120 | µg/kg |
| Naphthalene | 0.29 | mg/kg | A4 | | |
| 2-Methylnaphthalene | 0.10 | mg/kg | A4 | 17 | µg/kg |
| 2-Methylphenol | 7.50 | mg/kg | A2 | | |
| 4-Methylphenol | 5.10 | mg/kg | A2 | 22 | µg/kg |
| Pentachlorophenol | 4.90 | mg/kg | A1 | | |
| Phenanthrene | 1.40 | mg/kg | A2 | 470 | µg/kg |
| Phenol | 6.20 | mg/kg | A2 | 130 | µg/kg |
| Pyrene | 1.50 | mg/kg | A4 | 890 | µg/kg |
| Vanillin | 450 | mg/kg | A1 | | |

Table 11, continued

**RCRA Facility Investigation (RFI) Report
For the Marginal Way Facility, Tukwila,
Washington Rhone-Poulenc
June 19, 1995**

| Constituent | Soil Concentration | | | Sediment Concentration | |
|--------------------|-----------------------|-------|-------------------------|------------------------|-------|
| | Maximum Concentration | Units | Soil Investigation Area | Maximum Concentration | Units |
| Aldrin | | | | 2.3 | µg/kg |
| Alpha-chlordane | 0.018 | mg/kg | A5 | 1.3 | µg/kg |
| Aroclor-1254 | 2.8 | mg/kg | A3 | 210 | µg/kg |
| Aroclor-1260 | | | | 50 | µg/kg |
| BHC-delta | | | | 11 | µg/kg |
| 4,4'-DDD | 0.20 | mg/kg | A5 | 160 | µg/kg |
| 4,4'-DDE | 0.62 | mg/kg | A5 | 45 | µg/kg |
| 4,4'-DDT | 2.6 | mg/kg | A5 | 180 | µg/kg |
| Dieldrin | 0.0095 | mg/kg | A5 | 3.3 | µg/kg |
| Endosulfan I | 0.0065 | mg/kg | A5 | 1.3 | µg/kg |
| Endosulfan II | 0.024 | mg/kg | A5 | 2.8 | µg/kg |
| Endosulfan sulfate | 0.0096 | mg/kg | A5 | 9.4 | µg/kg |
| Endrin | 0.022 | mg/kg | A5 | | |
| Endrin aldehyde | 0.11 | mg/kg | A5 | 5.1 | µg/kg |
| Endrin ketone | 0.019 | mg/kg | A5 | 5.1 | µg/kg |
| Gamma-chlordane | 0.026 | mg/kg | A5 | 4.4 | µg/kg |
| Methoxychlor | 0.04 | mg/kg | A5 | 12 | µg/kg |
| | | | | | |
| TPH | 645 | mg/kg | A6 | | |

Attachment 3

Tabulated Preliminary Screening Tables and PRGs

Table 1
Screening of Constituents Historically Detected in Groundwater Vs. Draft 2020 PRGs

| Constituent | Maximum | | Notes | | Over Lowest Vapor Intrusion Value |
|------------------------|---------|-------|---|------------------------------------|-----------------------------------|
| | | Units | Over Lowest of Groundwater to Protect Drinking Water Values | Over Lowest of Surface Water Value | |
| Aluminum | 880,000 | µg/L | Yes | NA | NA |
| Arsenic | 107 | µg/L | Yes | Yes | NA |
| Barium | 63 | µg/L | No | No | NA |
| Cadmium | 6 | µg/L | Yes | Yes | NA |
| Calcium | 176000 | µg/L | NA | NA | NA |
| Chromium | 2,590 | µg/L | Yes | NA | NA |
| Copper | 1,880 | µg/L | Yes | Yes | NA |
| Iron | 248000 | µg/L | Yes | Yes | NA |
| Lead | 196 | µg/L | Yes | Yes | NA |
| Magnesium | 308000 | µg/L | NA | NA | NA |
| Manganese | 4030 | µg/L | Yes | Yes | NA |
| Mercury | 9.76 J | µg/L | Yes | Yes | NA |
| Nickel | 610 | µg/L | Yes | Yes | NA |
| Potassium | 118000 | µg/L | NA | NA | NA |
| Selenium | 50 | µg/L | No | Yes | NA |
| Silver | 0.4 | µg/L | No | No | NA |
| Sodium | 3890000 | µg/L | NA | NA | NA |
| Tin | 60 | µg/L | No | No | NA |
| Vanadium | 4,290 | µg/L | Yes | No | NA |
| Zinc | 2,770 | µg/L | No | Yes | NA |
| | | | | | |
| Acetone | 120 | µg/L | No | No | No |
| Benzene | 130 | µg/L | No | Yes | Yes |
| Bromoform | ND | | -- | -- | -- |
| 2-Butanone | 1.3 | µg/L | No | No | No |
| sec-Butylbenzene | ND | | -- | -- | NA |
| Carbon disulfide | 1.7 | µg/L | No | No | No |
| 1,4-Dichlorobenzene | 0.1 J | µg/L | No | No | No |
| cis-1,2-Dichloroethene | 0.4 | µg/L | No | No | NA |
| Ethylbenzene | 100 | µg/L | Yes | Yes | Yes |
| 4-Isopropyl toluene | 2.2 | µg/L | NA | NA | NA |
| Methylene chloride | 4.1 | µg/L | No | No | No |
| Tetrachloroethene | ND | | -- | -- | -- |
| Toluene | 570,000 | µg/L | Yes | Yes | Yes |
| Trichloroethene | ND | | -- | -- | -- |
| 1,2,4-Trimethylbenzene | 1.1 | µg/L | No | NA | No |
| 1,3,5-Trimethylbenzene | 0.2 J | µg/L | No | No | No |
| Xylene (total) | 92 | µg/L | No | No | No |
| m,p-Xylene | 1.8J | µg/L | No | No | No |

| Constituent | Maximum | | Notes | | |
|----------------------------|---------|-------|---|------------------------------------|-----------------------------------|
| | | Units | Over Lowest of Groundwater to Protect Drinking Water Values | Over Lowest of Surface Water Value | Over Lowest Vapor Intrusion Value |
| o-Xylene | 0.9J | µg/L | No | No | No |
| Acenaphthene | ND | | -- | -- | -- |
| Acenaphthylene | ND | | -- | -- | -- |
| Anthracene | ND | | -- | -- | -- |
| Benzo[a]anthracene | ND | | -- | -- | -- |
| Total Benzofluoranthenes | ND | | -- | -- | -- |
| Benzo(k)fluoranthene | -- | | -- | -- | -- |
| Benzo[ghi]perylene | ND | | -- | -- | -- |
| Benzo(a)pyrene | ND | | -- | -- | -- |
| Benzoic acid | ND | | -- | -- | -- |
| Benzyl alcohol | 17 | µg/L | No | No | NA |
| Bis(2-ethylhexyl)phthalate | 5.1 | µg/L | | | |
| Butyl benzyl phthalate | ND | | -- | -- | -- |
| Carbazole | ND | | -- | -- | -- |
| Chrysene | ND | | -- | -- | -- |
| Dibenz(a,h)anthracene | ND | | -- | -- | -- |
| Dibenzofuran | ND | | -- | -- | -- |
| 2,4-Dimethylphenol | 0.8 J | µg/L | No | No | NA |
| Di-n-butyl phthalate | ND | | -- | -- | -- |
| Fluoranthene | ND | | -- | -- | -- |
| Fluorene | ND | | -- | -- | -- |
| Indeno(1,2,3-cd)pyrene | ND | | -- | -- | -- |
| 2-Methylnaphthalene | ND | | -- | -- | -- |
| 2-Methylphenol | 220 E | µg/L | No | Yes | NA |
| 4-Methylphenol | 170 E | µg/L | No | No | NA |
| Naphthalene | 0.3 MJ | µg/L | Yes | Yes | No |
| Pentachlorophenol | 3.2 J | µg/L | Yes | No | NA |
| Phenanthrene | ND | | | | |
| Phenol | 400 ES | µg/L | No | Yes | NA |
| 1,4-Phenylenediamine | 12 Y | µg/L | No | NA | NA |
| Pyrene | ND | | -- | -- | -- |
| 2,4,5-Trichlorophenol | ND | | -- | -- | -- |

Table 2
Screening of Constituents Historically Detected in Soil Vs. Draft 2020 PRGs

| Constituent | Maximum Soil | | Notes | | | | |
|------------------------|--------------|-------|---------------------------------------|--|---|--|---|
| | | Units | Lowest of Residential Soil RSL Values | Lowest of Composite Worker Soil RSL Values (or Background if Higher) | LDW PCUL SL-8 Protect Sediment via Bank Erosion | EPA RSL Soil Screening Level to Protect Groundwater (Risk-based) | EPA RSL Soil Screening Level to Protect Groundwater (MCL-based) |
| Aluminum | 19,700 | mg/kg | No | No | No | No | NA |
| Antimony | 21.2 | mg/kg | No | No | No | Yes | Yes |
| Arsenic | 61.4 | mg/kg | Yes | Yes | Yes | Yes | Yes |
| Barium | 169 | mg/kg | No | No | No | Yes | Yes |
| Beryllium | 1.1 | mg/kg | No | No | No | No | No |
| Cadmium | 5 | mg/kg | No | No | No | Yes | Yes |
| Calcium | 34,400 | mg/kg | NA | NA | NA | NA | NA |
| Chromium | 64.9 | mg/kg | Yes | Yes | No | No | No |
| Cobalt | 28.7 | mg/kg | Yes | No | No | Yes | NA |
| Copper | 18,200 | mg/kg | Yes | No | Yes | Yes | Yes |
| Iron | 50,400 | mg/kg | No | No | No | Yes | NA |
| Lead | 116 | mg/kg | No | No | No | NA | Yes |
| Magnesium | 15,100 | mg/kg | NA | NA | NA | NA | NA |
| Manganese | 941 | mg/kg | No | No | NA | Yes | NA |
| Mercury | 268 | mg/kg | Yes | Yes | Yes | Yes | Yes |
| Nickel | 65.7 | mg/kg | No | No | No | Yes | NA |
| Potassium | 902 | mg/kg | NA | NA | NA | NA | NA |
| Selenium | 0.8 J | mg/kg | No | No | No | Yes | Yes |
| Silver | 3.5 | mg/kg | No | No | No | Yes | NA |
| Sodium | 4,200 | mg/kg | NA | NA | NA | NA | NA |
| Vanadium | 185 | mg/kg | No | No | No | Yes | NA |
| Zinc | 1,990 | mg/kg | No | No | Yes | Yes | NA |
| | | | | | | | |
| Acetone | 13 | mg/kg | No | No | NA | Yes | NA |
| Benzene | 0.23 | mg/kg | No | No | NA | Yes | Yes |
| Bromoform | 0.002 | mg/kg | No | No | NA | Yes | No |
| 2-Butanone | 1.1 | mg/kg | No | No | NA | No | NA |
| sec-Butylbenzene | 0.0008 J | mg/kg | No | No | NA | No | NA |
| Carbon disulfide | 0.038 | mg/kg | No | No | NA | No | NA |
| 1,4-Dichlorobenzene | 0.0092 | mg/kg | No | No | No | Yes | No |
| cis-1,2-Dichloroethene | 0.0025 | mg/kg | No | No | NA | No | NA |
| Ethylbenzene | 6.4 | mg/kg | Yes | No | NA | Yes | Yes |
| Formaldehyde | 3.4 | mg/kg | No | No | NA | Yes | NA |
| 4-Isopropyl toluene | 0.024 | mg/kg | NA | NA | NA | NA | NA |
| Methylene chloride | 1.6 | mg/kg | No | No | NA | Yes | Yes |
| Tetrachloroethene | 0.0017 J | mg/kg | No | No | NA | No | No |

| Constituent | Maximum Soil | | Notes | | | | |
|----------------------------|--------------|-------|---------------------------------------|--|---|--|---|
| | | Units | Lowest of Residential Soil RSL Values | Lowest of Composite Worker Soil RSL Values (or Background if Higher) | LDW PCUL SL-8 Protect Sediment via Bank Erosion | EPA RSL Soil Screening Level to Protect Groundwater (Risk-based) | EPA RSL Soil Screening Level to Protect Groundwater (MCL-based) |
| Toluene | 4,900 | mg/kg | No | No | NA | Yes | Yes |
| Trichloroethene | 0.2 | mg/kg | No | No | NA | Yes | Yes |
| 1,2,4-Trimethylbenzene | ND | | -- | -- | -- | -- | -- |
| 1,3,5-Trimethylbenzene | ND | | -- | -- | -- | -- | -- |
| Xylene (total) | 13 | mg/kg | No | No | NA | Yes | NA |
| m,p-Xylene | 0.0015 | mg/kg | No | No | NA | No | NA |
| o-Xylene | ND | | -- | -- | -- | -- | -- |
| Acenaphthene | 0.13 | mg/kg | No | No | No | No | NA |
| Acenaphthylene | 0.0037 | mg/kg | NA | NA | No | NA | NA |
| Anthracene | 0.26 | mg/kg | No | No | No | No | NA |
| Benzo[a]anthracene | 0.46 | mg/kg | No | No | No | Yes | NA |
| Total Benzofluoranthenes | 0.1 | mg/kg | NA | NA | NA | NA | NA |
| Benzo(b)fluoranthene | 0.72 | mg/kg | No | No | NA | Yes | NA |
| Benzo(k)fluoranthene | 0.59 | mg/kg | No | No | NA | No | NA |
| Benzo[ghi]perylene | 0.41 | mg/kg | NA | NA | No | NA | NA |
| Benzo(a)pyrene | 0.65 | mg/kg | Yes | No | No | Yes | No |
| Benzoic acid | 0.098 J | mg/kg | No | No | No | No | NA |
| Benzyl alcohol | 0.19 | mg/kg | No | No | Yes | No | NA |
| Bis(2-ethylhexyl)phthalate | 6.8 | mg/kg | No | No | Yes | Yes | Yes |
| Butyl benzyl phthalate | 0.023 | mg/kg | No | No | No | No | NA |
| Carbazole | 0.17 | mg/kg | NA | NA | NA | NA | NA |
| Chrysene | 0.84 | mg/kg | No | No | No | No | NA |
| Dibenz(a,h)anthracene | 0.016 J | mg/kg | No | NA | No | No | NA |
| Dibenzofuran | 0.12 | mg/kg | No | No | No | No | NA |
| 2,4-Dimethylphenol | 0.29 | mg/kg | No | No | Yes | No | NA |
| Di-n-butyl phthalate | 0.43 | mg/kg | No | No | No | No | NA |
| Fluoranthene | 1.8 | mg/kg | No | No | Yes | No | NA |
| Fluorene | 0.15 | mg/kg | No | No | No | No | NA |
| Indeno(1,2,3-cd)pyrene | 0.44 | mg/kg | No | No | No | No | NA |
| 2-Methylnaphthalene | 0.1 | mg/kg | No | No | No | No | NA |
| 2-Methylphenol | 7.5 | mg/kg | No | No | Yes | Yes | NA |
| 4-Methylphenol | 5.1 | mg/kg | No | No | Yes | Yes | NA |
| Naphthalene | 0.29 | mg/kg | No | No | No | Yes | NA |
| Pentachlorophenol | 4.9 | mg/kg | Yes | Yes | Yes | No | No |
| Phenanthrene | 1.4 | mg/kg | NA | NA | No | NA | NA |
| Phenol | 6.2 | mg/kg | No | No | Yes | Yes | NA |
| 2-Propanol | 10 | mg/kg | No | No | NA | Yes | NA |
| Pyrene | 1.5 | mg/kg | No | No | No | No | NA |

| Constituent | Maximum Soil | | Notes | | | | |
|-----------------------|--------------|-------|---------------------------------------|--|---|--|---|
| | | Units | Lowest of Residential Soil RSL Values | Lowest of Composite Worker Soil RSL Values (or Background if Higher) | LDW PCUL SL-8 Protect Sediment via Bank Erosion | EPA RSL Soil Screening Level to Protect Groundwater (Risk-based) | EPA RSL Soil Screening Level to Protect Groundwater (MCL-based) |
| 2,4,5-Trichlorophenol | 0.0079 | mg/kg | No | No | No | No | NA |
| Vanillin | 450 | mg/kg | NA | NA | NA | NA | NA |
| Total cPAHs | 0.106 | mg/kg | NA | NA | NA | NA | NA |
| | | | | | | | |
| Alpha chlordane | 0.018 | mg/kg | No | No | NA | Yes | No |
| 4,4'-DDD | 0.2 | mg/kg | No | No | No | Yes | NA |
| 4,4'-DDE | 0.62 | mg/kg | No | No | No | Yes | NA |
| 4,4'-DDT | 2.6 | mg/kg | Yes | No | Yes | Yes | NA |
| Dieldrin | 0.0095 | mg/kg | No | No | Yes | Yes | NA |
| Endosulfan I | 0.0065 | mg/kg | NA | NA | No | NA | NA |
| Endosulfan II | 0.024 | mg/kg | NA | NA | No | NA | NA |
| Endosulfan sulfate | 0.0096 | mg/kg | No | No | No | No | NA |
| Endrin | 0.022 | mg/kg | No | No | No | No | No |
| Endrin aldehyde | 0.11 | mg/kg | NA | NA | NA | NA | NA |
| Endrin ketone | 0.019 | mg/kg | NA | NA | NA | NA | NA |
| Gamma-chlordane | 0.026 | mg/kg | No | No | NA | Yes | No |
| Methoxychlor | 0.04 | mg/kg | No | No | No | No | No |
| PCBs (Arochlor 1254) | 1,588.71 | mg/kg | Yes | Yes | NA | Yes | NA |

Attachment 4

Groundwater Sampling Field Log

